



# SQUANNACOOK RIVER DAM REMOVAL BASIS OF DESIGN

November 2025



**Town of Groton**  
173 Main Street  
Groton, MA 01450





# Squannacook River Dam Removal

---

## Basis of Design Report

### Groton & Shirley, Massachusetts

---

## Table of Contents

<b>EXECUTIVE SUMMARY .....</b>	<b>3</b>
<b>1.0 INTRODUCTION .....</b>	<b>5</b>
1.1 Project Goals and Objectives.....	5
1.2 Site Visit and Background Information .....	7
<b>2.0 PROJECT AREA .....</b>	<b>9</b>
2.1 Pre-Colonial Context.....	9
2.2 Squannacook River Dam .....	9
2.3 Squannacook River Dam Impoundment .....	15
2.4 Project Reach of Squannacook River .....	17
<b>3.0 SEDIMENT ASSESSMENT AND MANAGEMENT .....</b>	<b>33</b>
3.1 Background and Feasibility Study Phase .....	33
3.2 Updated Due Diligence Review .....	36
3.3 Pre-Permitting Phase Sediment Sampling Plan .....	40
3.4 Sediment Sampling Results .....	42
<b>4.0 HYDROLOGIC AND HYDRAULIC ANALYSIS .....</b>	<b>45</b>
4.1 Model Development.....	45
4.2 Model Results .....	52
4.3 Fish Passage.....	58
4.4 Scour Assessment.....	72
4.5 Estimated Change in Average Groundwater Elevation Post Dam Removal Well .....	75
<b>5.0 PRELIMINARY DAM REMOVAL DESIGN .....</b>	<b>81</b>
<b>6.0 DISCUSSION .....</b>	<b>83</b>
6.1 Potential Ecological Impacts and Benefits .....	83
6.2 Potential Impacts and Benefits for Flooding, Infrastructure, and Recreation .....	84
6.3 Environmental Permitting.....	85
<b>7.0 ESTIMATED PROJECT COSTS AND FUTURE PHASING .....</b>	<b>87</b>



## **ATTACHMENTS**

ATTACHMENT A – Sediment Quality Laboratory Results

ATTACHMENT B – ResilientMass Action Team (RMAT) Report

ATTACHMENT C – 60% Design Plans

ATTACHMENT D – 60% Opinion of Probable Cost

ATTACHMENT E – Proposed Site Renderings



# Squannacook River Dam Removal

---

## Basis of Design Report

### Groton & Shirley, Massachusetts

---

#### EXECUTIVE SUMMARY

This Basis of Design (BOD) report summarizes the updated pre-permit-level design phase work conducted in 2024 and 2025 for the dam removal of the Squannacook River Dam in Groton and Shirley, MA. The primary Project goals include improving public safety, eliminating the liability and maintenance needs required by the Dam, restoring aquatic connectivity along the Squannacook River, and restoring riverine habitat to the Squannacook River Dam impoundment. The Dam is the first of five on the Squannacook River, representing a critical barrier to fish passage and aquatic conductivity. The Dam has no functional use and is deteriorated, posing a risk to people and infrastructure in the event of dam failure.

In the previous 2024 dam removal feasibility study conducted by Horsley Witten Group, Inc. (HW), a concept-level evaluation of dam removal was undertaken to identify benefits, potential challenges, and questions requiring additional study. The feasibility study found that dam removal would reduce risk of flooding upstream of the dam and eliminate the risk of damage to infrastructure or loss of life in the event of dam failure. The study also found that dam removal would provide significant ecological benefits. A few topics requiring further study were identified, including investigating sediment quality, assessing potential scour risk along infrastructure upstream of the Dam, and evaluating potential impacts to drinking water wells near the dam impoundment. These topics were addressed in this current pre-permit-level design phase.

During this current design phase, potential historic threats associated with sediment quality in the dam impoundment were investigated through a due diligence review and sediment sampling of the Thompson Mill Pond area of the impoundment. Analysis was performed on the typical set of compounds specified under the Massachusetts Department of Environmental Protection (MassDEP) Water Quality Certification (WQC). Additionally, impounded sediment was analyzed for the presence of asbestos based on the concerns of an abutter. No exceedances of Massachusetts Contingency Plan (MCP) S-1/GW-1 standards for human health were detected for any analyte in either sampling round.

In this current design phase, a two-dimensional, unsteady-state hydrologic and hydraulic (H&H) model was developed to further evaluate impacts of dam removal on flooding, daily water elevation in the impoundment, sediment transport, scour risk to the West Groton Bridge and nearby retaining walls and embankments, fish passage, and recreation. As is typical, dam removal is modeled to result in sediment transport from upstream of the dam to downstream areas of the river over several years. The West Groton Bridge and other infrastructure upstream of the dam are not predicted to experience increased risk of scour. Impoundment water levels are expected to lower by as much as 10.11 feet during median flows, and the Thompson Mill Pond is expected to convert into a bordering vegetated wetland. This reduction in water



elevations is not expected to impact the performance of any nearby private drinking water wells. Removal of the dam is predicted to eliminate a major obstacle to fish passage, and aquatic species are expected to be able to achieve upstream passage during some if not all flow conditions.

Dam removal is anticipated to have a positive overall effect on river health. Dam removal also eliminates the significant hazard that exists in the event of dam failure, which carries the risk of causing loss of life and damage to nearby structures. Dam removal is anticipated to reduce flooding and scour risks for buildings and infrastructure in the vicinity of the dam. Project costs for the remaining phases of dam removal are estimated to range from \$1.2 - 1.7M, but it is important to note that funding opportunities for dam removals are readily available, especially compared to the limited funding sources available for continued monitoring, maintenance, and repairs of the dam.



## 1.0 INTRODUCTION

The Horsley Witten Group, Inc. (HW) is pleased to provide this Basis of Design (BOD) report to the Town of Groton (the Town) summarizing the updated pre-permit-level design phase work conducted in 2024 and 2025 for the dam removal and river restoration opportunities of the Squannacook River Dam (the Dam) in Groton and Shirley, MA (the Site). This work was completed for the Town with support from the Department of Public Works (DPW) and Conservation Department (CD). Additional project partners include Mr. Helmar Nielsen (the Co-Owner). The Nashua River Watershed Association (NRWA) is also assisting with project outreach and has provided additional background documentation on the Dam.

Prior to this current pre-permit-level design phase of the project, HW completed a dam removal feasibility study for the Site under contract to the Massachusetts Division of Ecological Restoration (DER). This current pre-permit-level design phase is a follow-on from that initial Feasibility Study. Pre-permit-level design work completed under the current project phase included:

- Additional field data collection of river bathymetry and Dam and retaining wall elevation data;
- Updated sediment sample collection and analysis;
- Updated hydrologic and hydraulic modeling; and
- Updated Project design plans to advance the Feasibility Study designs to the pre-permitting-level design phase.

This Pre-Permitting-Level BOD Report summarizes background information for the Squannacook River Dam as well as new field work, modeling, and analyses completed since the Feasibility Study was completed in the summer of 2024. This report provides rationale for the design features included in the current, pre-permit-level design.

### 1.1 Project Goals and Objectives

The Squannacook River is a 16.4-mile-long tributary of the Nashua River; itself a tributary to the Merrimack River. The Squannacook River forms the border between the Towns of Groton and Shirley and the Dam itself is located half in Groton and half in Shirley. The Groton half of the Dam is owned by the Town of Groton (the Town), and the Shirley half is privately owned. The Dam is situated just downstream from the West Groton Bridge, 2.5 miles upstream of the confluence of the Squannacook and Nashua Rivers. From downstream to upstream, the Squannacook River Dam is the first of five dams located on the Squannacook River, making it a critical barrier to migratory fish passage.

**Figure 1** identifies key features discussed in this report. These are discussed at greater length below. In this report, all left and right directional references are relative to the direction of the river flow looking downstream; river left refers to the river's left (generally approximately east) bank and river right refers to the river's right (generally approximately west) bank. All elevation data given in this report are relative to the NAVD88 vertical datum in units of feet.






Figure 1. Key Project Area Features

The primary Project goals and objectives include:

- 1) Improving public safety;
- 2) Elimination of liability and maintenance needs required by the Dam;
- 3) Restoring aquatic connectivity along the Squannacook River; and
- 4) Restoring riverine habitat to the Squannacook River Dam impoundment.

The Dam has had no known functional use since at least 1986. While the Groton half of the Dam underwent significant repairs in 2013, there is no known record of repairs to the Shirley half of the Dam since at least 1926. According to the Squannacook River Dam Phase I Inspection Evaluation prepared by Haley & Aldrich Inc. (2023), the portion of the Dam located in Shirley is in need of repair as a large portion of the Dam's concrete structure is either loose or deteriorated. Debris has also accumulated along the Dam in general. At present, the Dam creates an impoundment exacerbating flood risk to surrounding properties and infrastructure along Townsend Road in Groton and along Route 225 in Groton and Shirley and creating a risk to downstream infrastructure if the Dam were to breach. Due to the deteriorated state of the Dam, which includes structural and functional deficiencies, the Dam has been identified by the Town and the Shirley-side private co-owner as a candidate for removal. This pre-permit-level study assesses the potential impacts of removing the Dam and provides a preliminary design for dam removal.

## 1.2 Site Visit and Background Information

Information referenced in this report includes observations and data collected during site visits on January 24, 30, and 31, and November 19 and 20, 2024; background information provided by Project Partners, and other readily available information collected by HW. Information on the Dam and the adjacent areas along the Squannacook River that was reviewed in preparation of this report includes:

- 1) Map of Shirley from the Survey of 1830, provided by the Shirley Historical Society, dated 1830;
- 2) Proposed Bridge Replacement Plans: Route 225 Over Squannacook River, prepared for Mass Highway by Luchs Associates, Inc., dated January 14, 1995;
- 3) Contour Map of the Land Surface now under W. Groton Pond, prepared by CDM Camp Dresser & McKee, dated March 2000. Provided by Carl Canner.
- 4) Petapawag Area of Critical Environmental Concern Designation, Massachusetts Department of Conservation and Recreation, December 2002;
- 5) Groton at 350: The History of a Massachusetts Town, 1655-2005, by Barbara Murray, Deborah E. Johnson, and Jaume Kulesz, 2005;
- 6) Historical Inventory Form A: West Groton, prepared for the Massachusetts Historical Commission by Sanford Johnson, 2006;
- 7) Shirley Reconnaissance Report, Massachusetts Heritage Landscape Inventory Program, June 2006;



- 8) Community-Wide Archaeological Reconnaissance Survey of Groton, Massachusetts, University of Massachusetts Archaeological Services Department of Anthropology, March 2011;
- 9) Flood Insurance Study, Middlesex County, Massachusetts. By Federal Emergency Management Agency, dated July 2016;
- 10) Magnitude of Flood Flows at Selected Annual Exceedance Probabilities for Streams in Massachusetts, U.S. Geological Survey Scientific Investigations Report, dated 2017;
- 11) Well Drilling Database, Massachusetts Executive Office of Energy and Environmental Affairs, 2018;
- 12) Squannacook River Dam Phase I Inspection/Evaluation, prepared for the Town of Groton by Haley & Aldrich, Inc., dated May 5, 2023; and
- 13) Property Tax Parcels, MassGIS, dated March 2024.

As mentioned above, HW visited the site three times during the project's initial Feasibility Study in January 2024 and returned to the site twice during the current pre-permit-level design study in November 2024, as described below.

- **January 24:** HW conducted a topographic and bathymetric survey of the Site. Within the river, HW probed the channel bottom in order to measure the depth of soft sediment that has accumulated within the impoundment upstream of the Dam. Survey data was collected using total station and GPS-RTK methods.
- **January 30:** HW conducted a delineation of wetland resource areas in the immediate vicinity of the Dam. Wetland resources identified during the delineation included Bank, Riverfront Area, Land Subject to Flooding, and Land Under Water Bodies and Waterways.
- **January 31:** HW continued the topographic and bathymetric survey and also collected sediment samples from six locations along the Squannacook River. Sediment samples were combined from each of two similarly situated discrete locations to produce two composite samples for laboratory analysis: one upstream sample within the impoundment and one downstream sample.

HW also met with Project Partners at the site on January 31 to discuss site conditions and project goals. During this initial on-site meeting, Project Partners discussed goals for removal as well as potential items for study, including proximity of the impoundment to wells and abutter concerns. Project Partners also discussed timing and resources for potential public engagement opportunities after the results of this feasibility study are determined. Groton Town representatives shared information on recent Dam repairs and logistics related to Dam access.

- **November 19:** HW collected additional bathymetric data of the Squannacook River downstream of the Dam. A flow measurement was collected in the river approximately 350 feet downstream of the Dam. HW also collected sediment samples from six additional locations along the Thompson Mill Pond portion of the river. Similarly situated discrete samples were combined into two composite samples for laboratory analysis of

typical sediment quality parameters: one in an area of potential mobile accumulated sediment, and one in an area in which sediment may become exposed to the surface post-dam removal. Discrete samples were submitted for laboratory analysis for asbestos and volatile organic compounds (VOCs), which were not composited in order to increase the precision of the sediment quality analysis.

- **November 20:** HW continued the bathymetric survey. Bathymetric data was collected in the Thompson Mill Pond area and at transects upstream of the previous limit of the bathymetric survey. HW collected more detailed sediment probing of the area upstream of the Dam. HW also collected drone footage and photography of the Dam, river, and impoundment.

## 2.0 PROJECT AREA

### 2.1 Pre-Colonial Context

The Groton and Shirley area is rich in pre-colonial history. According to archaeological reconnaissance surveys completed in both towns, the Nipmuc people occupied the region for up to 13,000 years prior to colonial settlement of the area.<sup>1,2</sup> The Nashua River and its tributaries like the Squannacook River served as the homeland to the Nipmuc, and the rivers were heavily used for transportation, food, and water.<sup>3</sup> Due to the large number of wetlands, rivers, and streams, the Nipmuc people referred to the area as “Petapawag”, which roughly translates into English as “swampy place.”<sup>4</sup> To this day much of Groton is included in the Petapawag Area of Critical Environmental Concern (though not the dam site itself).<sup>5</sup> The extensive wetlands would have served as an important source of fresh water and food in the forms of prey and edible plants such as cattails.<sup>6</sup>

### 2.2 Squannacook River Dam

The Squannacook River Dam (National ID: MA 00442), also called the Leatherboard Dam or the West Groton Dam, is located within Middlesex County in Groton and Shirley, Massachusetts at 42.60292° N, 71.6272° W. The Dam is located along the Squannacook River, approximately 2.5 miles upstream of its confluence with the Nashua River and approximately 100 feet downstream of the West Groton Bridge (Route 225). The Dam is adjacent to RiverCourt Residences, a senior living facility that occupies the former mill building associated with the Dam. The former mill building is listed on the MassHistoric Commission Inventory’s National Register of Historic Places, but the Dam itself does not have historic listing status.

---

<sup>1</sup> Massachusetts Heritage Landscape Inventory Program

<sup>2</sup> University of Massachusetts Archaeological Services Department of Anthropology, “Community-Wide Archaeological Reconnaissance Survey of Groton, Massachusetts,” March 2011

<sup>3</sup> Ibid.

<sup>4</sup> <https://www.rivers.gov/sites/rivers/files/documents/plans/nashua-plan.pdf>

<sup>5</sup> <https://www.mass.gov/info-details/petapawag-acec>

<sup>6</sup> University of Massachusetts Archaeological Services Department of Anthropology, “Community-Wide Archaeological Reconnaissance Survey of Groton, Massachusetts,” March 2011



The earliest available mapping of the West Groton area comes from an 1830 survey of Shirley (Figure 2). The survey shows a bridge (most likely the West Groton Bridge) and building along the Squannacook River in West Groton, but no dam is depicted. In the survey, there is no depiction of Thompson Mill Pond, or of any other backwater areas that are currently impounded just upstream of the Dam. The sharp bend that is characteristic of the Squannacook River upstream of the West Groton Bridge is depicted.

Prior to the construction of a dam near the West Groton Bridge, alewife and shad are recorded in the upper reaches of the Squannacook River in ledger entries dated May 19, 1812 and May 4, 1819 (Figure 3).




Figure 2. 1830 Survey of Shirley – West Groton Bridge Identified in Red Circle




Figure 3. Ledger of Jesse Farnsworth and John Heald, 1812-1821

No construction records are available for the original Dam, although the year 1926 is imprinted in concrete on the Dam. This date likely represents a major reconstruction rather than the original construction date. The earliest available USGS maps, dated 1893 (**Figure 4**) show a dam impoundment at the site, and there is little evident change in the size of the impoundment behind the Dam when comparing that oldest map to current conditions. In *Groton at 350*, Murray, Kulesz, and Johnson write that a sawmill was established at the site of the Dam prior to 1744. According to the Massachusetts Historical Commission (MHC) Form A prepared by Sanford Johnson (Background Document #3), the area around West Groton was sparsely populated until 1847, at which time railroad services expanded into the area. Around this time a grist-and-saw mill was constructed by Thomas Tarbell at the current location of the RiverCourt Residences. By 1875, the Tarbell Mill was replaced by E.H. Sampson's Groton Leatherboard factory, which quickly became the primary industrial center in West Groton. The Groton Historical Commission researchers have claimed that the Groton Leatherboard factory was the first factory in the nation to produce leatherboard, an artificial leather product made of scrap leather, waste paper, and wood pulp.



Figure 4. USGS Topographic Maps of Groton (left two, 1893 and 1935) and Shirley (right, 1965)

After a fire in 1914, the leatherboard factory began the process of replacing its wood frame mill building and three wood storehouses with the brick buildings that make up the current RiverCourt Residences. Mill operations resumed in 1916 and were ongoing at the site until 1978. Mr. Helmar Nielsen purchased the mill buildings in 1979 and began production of metal art frames for six to seven years. In 1996, The Town of Groton acquired the buildings and the portion of the Dam located in Groton. The Shirley portion of the Dam is still owned by Mr. Nielsen. The mill site was listed on the National Register of Historic Places in 2002.





Figure 5. Groton Leatherboard Company workers outside of the reconstructed brick mill building, approximately 1916. Photo courtesy of Stanley J. Kopec.

The current Dam is a run-of-the-river, stone masonry and concrete structure, approximately 150 feet long with a structural height of 18 feet and crest elevation of 228.15 feet. On the river right side of the Dam, a masonry retaining wall meets the Dam at approximately the dam elevation. This retaining wall provides structural support to Groton Road in Shirley (Route 225).

On the river left side of the dam, a 10-foot-high masonry training wall extends from the Dam parallel to the riverbank, forming a penstock. An overflow spillway at elevation 225.85 is located along this penstock, and a low level outlet structure consisting of a square wooded gate about 40 inches wide and tall is located at the bottom of the training wall. According to the DPW, the low level outlet is rarely used except in dry periods (typically in summer) when flow in the Squannacook River is insufficient out of the overflow spillway and the upstream impoundment becomes stagnant. During these times, the low level outlet is opened by one foot.





Figure 6. The Squannacook River Dam looking west, from the penstock (left bank) to Groton Road (Route 225) (right bank)

At the base of the Dam, a concrete splashpad dissipates water that flows out of the overflow spillway along the penstock. Bedrock outcrop is located along the base of the main spillway of the Dam.

A 6-foot diameter pipe runs from the penstock approximately 100 to 150 feet along the former mill building – previously used to generate power at the mill. The pipe was plugged with concrete at some point between 1999 and 2006. A discharge channel from the former mill building runs between the legacy bank of the Squannacook River and the parking lot of the RiverCourt Residences, forming a peninsula in the river. A wooden pedestrian bridge on steel trusses connects the peninsula to the parking lot (**Figure 7**).



Figure 7. Looking east from the peninsula to the former mill building and parking lot

The Dam is jointly owned by the Town of Groton and by Mr. Helmar Nielsen, with ownership divided on the Groton-Shirley town line. Groton performed dam repairs to its side of the Dam as recently as 2013. During the repairs, cracked and spalling concrete on the Groton side of the Dam was chipped and repaired with reinforced concrete. The Shirley side (river-right) of the dam is due for repairs, and the overall condition of the Dam is rated by the Massachusetts Office of Dam Safety as “Fair” due to the maintenance needs of the Shirley side. The Office of Dam Safety also classified the Dam as an Intermediate, High Hazard dam due to its size and the potential risk of loss of life and property damage in the event of failure. Necessary repairs to the Dam were estimated by Haley & Aldrich in 2023 to cost \$306,000. A study by Haley & Alrich to develop an updated repair cost estimate is ongoing concurrent to this dam removal study.



## 2.3 Squannacook River Dam Impoundment

### 2.3.1 Impoundment Characteristics

According to the Haley & Aldrich 2023 inspection report of the Dam, the impoundment upstream of the Dam holds a maximum capacity of 110 acre-feet of water. The surface area of the impoundment was estimated to be 28 acres, which includes the area immediately upstream of the Dam up to the base of the next upstream dam, the Hollingsworth & Vose Co. Dam.

HW survey data shows that at its deepest point, the impoundment bottom is 15.5 feet lower than the Dam spillway elevation and 9.6 feet lower than the estimated bedrock elevation underlying the Dam. The backwater section of the impoundment immediately upstream/directly north of the Dam (locally referred to as “Thompson Mill Pond”) was dredged in 2003, during which the impoundment was deepened by as much as 5 feet. The impoundment extents immediately upstream of the Dam are shown schematically below in **Figure 8**. The extents shown in **Figure 8** only include the project area, and do not include the full extent of the impoundment extending further upstream, as estimated in the Haley & Aldrich 2023 inspection report.



Figure 8. Squannacook River Dam Impoundment Schematic



### 2.3.2 Longitudinal Profile

**Figure 9** is a longitudinal profile developed based on bathymetric and sediment probing data surveyed by HW along the approximate historic channel centerline through the Dam impoundment to approximately 630 feet upstream of the Dam. The figure includes the locations of the Dam and the West Groton Bridge.




Figure 9. Longitudinal Profile of Squannacook River in Vicinity of Squannacook River Dam

### 2.3.3 Impoundment Sediment

#### Sediment Composition

Sediment samples composited from within the impoundment consisted mostly of brown poorly graded sand, and field observations included gravel and cobbles as well. HW field staff probed the channel bottom in order to measure the depth of soft sediment that has accumulated within the impoundment upstream of the Dam. HW found minimal soft sediment had accumulated within the impoundment along the main river channel upstream of the Dam, measuring approximately 0.1 feet at its thickest point, located approximately 290 feet upstream from the Dam near Transect 11. Within the Thompson Mill Pond area of the impoundment, sediment was found to be thicker, ranging from 0 to 3 feet in thickness. Sediment in Thompson Mill Pond was mostly concentrated in the northwest corner and at the interface with the main river channel.

#### Sediment Volumes

In addition to soft sediment, impounded sediment extends from the Dam to approximately 90 feet upstream of the Dam, and the mobile sediment volume is estimated to be approximately 2,630 cubic yards. The greatest thickness of impounded sediment (including soft and hard sediment) is estimated to be 12.4 ft, immediately upstream of the Dam. This value was obtained through consideration of the channel's elevation at that location (227.2 feet) and the assumption that pre-impoundment conditions at that location would have been similar to the elevation of the channel immediately downstream of the Dam (214.8 feet). Additional probing of the Thompson Mill Pond area was performed in this current study; as discussed further below, this area is not expected to experience sediment transport and therefore is not included in the estimate of total mobile sediment volume.

## 2.4 Project Reach of Squannacook River

### 2.4.1 Upstream Reach

The reach upstream of the Project area (along the Squannacook River from 900 feet upstream of the Squannacook River Dam up to the H&V Dam) (**Figure 10**) is characterized by a relatively gentle channel slope (0.8%)<sup>7</sup>, and an overwidened width measured by HW to be around 95 feet (influenced by dam impoundment effects). A number of side channels and inlets are present along the upstream reach, also possibly influenced by the impoundment tailwater elevation. Vegetation on both sides of the river upstream of the Dam consists of an open mix of native tree species as well as both native and invasive shrub and vine species. Evidence of beaver activity was observed on the right bank of the upstream reach.

---

<sup>7</sup> Classifying Your Stream Slope, *The Watershed Center*, Niwot, CO



Figure 10. Reach of Squannacook River Upstream of West Groton Bridge

#### 2.4.2 Downstream Reach

The downstream reach of the Squannacook River below the Dam (**Figure 11**) is a relatively natural segment of river, extending from downstream of the Squannacook River for 2.5 miles to its confluence with the Nashua River. The left bank along the mill building may have been altered for the construction of the mill's discharge channel.

This section of river slopes at a moderate 1.4%<sup>8</sup>. Despite the low gradient, water was observed flowing at a high velocity in this section. The river substrate consists of coarse material including gravel, cobbles, and boulders. The existing high velocity and coarse substrate are very likely a consequence of the high-energy outflow of the Dam, which drops over 12 feet from the crest of the Dam to the end of the plunge pool (approximately 50 feet downstream of the Dam). This downstream reach has an estimated bankfull width of 57 feet, nearly 40 feet narrower than the upstream reach, and is likely a reasonable estimate of the river's natural bankfull width were the Dam to be removed. Vegetation observed on the east and west banks downstream of the Dam includes various trees and shrubs from the alluvial hardwood community and the white pine-oak forest community, as well as both native and invasive vine species. The downstream reach

---

<sup>8</sup> Ibid.



appears to be a good candidate to use as a reference reach for the project area of the Squannacook River.



Figure 11. Reach of Squannacook River Downstream of Squannacook River Dam

Relative elevation mapping of the Squannacook River valley provided by NRWA (developed by Shirley resident Sarah Widing) indicates that the downstream reach may have historically meandered river-left in the location of the former mill building and the former Boston and Maine Railroad (**Figure 12**). Meander scars, left by the former path of the river, are visible north of West Groton Street. The current course of the Squannacook River may have been altered for the construction of the mill or the railroad, although insufficient information is available to be certain of this.




Figure 12. Relative Elevation Map of Squannacook River Valley, Courtesy of Sarah Widing

### 2.4.3 Natural Resources

The site supports freshwater wetland resource areas, as defined under the Massachusetts *Wetlands Protection Act* (M.G.L. Ch. 131 § 40), the Town of Groton Wetlands Bylaw (Chapter 215), the Town of Shirley Wetlands Bylaw, and their respective regulations and/or policies. An HW wetlands biologist identified and delineated these resource areas during the January 30, 2024 site visit. Jurisdictional areas identified on or adjacent to the site include Bank; Riverfront Area (RA); Land Subject to Flooding (LSF); Land Under Water Bodies and Waterways (LUW), the 50-foot No Disturb Buffer and 100-foot Buffer to Bank within the Town of Groton, and the 25-foot Vegetated Buffer and 100-foot Buffer Zones to Bank within the Town of Shirley.

HW followed wetland resource area identification and on-site delineation procedure guidelines described in the Massachusetts *Wetlands Protection Act* (M.G.L. Ch. 131 § 40), and its implementing Regulations (310 CMR 10.00), including those described in the Massachusetts Department of Environmental Protection (MassDEP) handbook, entitled *Massachusetts Handbook for Delineation of Bordering Vegetated Wetlands* (September, 2022), the Town of Groton Wetlands Bylaw (Chapter 215), the Town of Shirley Wetlands Bylaw, and their respective regulations and/or policies.

Prior to conducting field delineations, HW reviewed existing source data, including USGS Geological Survey 7.5 minute topographic maps, Massachusetts Department of Environmental Protection (MassDEP) wetlands source data available through the Massachusetts Geographic Information System (MassGIS), USDA Natural Resources Conservation Service (NRCS) soils survey, U.S. Fish and Wildlife Service National Wetland Inventory (NWI) maps, and other source data to identify the presence of jurisdictional wetlands and waters of the United States within the site. This information was used to compile base mapping to assist in the understanding of the hydrologic variables, soils conditions, and vegetation communities (where applicable).



A brief description of the regulatory definitions and the observed resources areas is provided below.

### Bank

Bank is defined at 310 CMR 10.54(2)(a) as “*the portion of land surface which normally abuts and confines a water body. It occurs between a water body and a vegetated bordering wetland and adjacent floodplain, or, in the absence of these, it occurs between a water body and an upland. A Bank may be partially or totally vegetated, or it may be comprised of exposed soil, gravel or stone. The upper boundary of a Bank is the first observable break in the slope or the mean annual flood level, whichever is lower. The lower boundary of a Bank is the mean annual low flow level*” [310 CMR 10.54(2)(c)].

Bank is defined by the Town of Groton Wetlands Bylaw [§215-9(B)] as, “... *the land area which normally abuts and confines a water body: the lower boundary being the mean annual low flow level, and the upper boundary being the first observable break in slope or the mean annual flood level, whichever is greater.*”

The Town of Shirley Wetlands Bylaw applies the same Bank definition found in 310 CMR, as stated above.

HW observed Bank on both sides of the Squannacook River, within the vicinity of the Dam site:

### Groton Bank

Along the eastern side of the Squannacook River, south of the Dam structure, within the jurisdiction of the Town of Groton, the Bank consists primarily of a sparsely vegetated rock revetment, which rises steeply to the east from the edge of the river and then flattens out to a vegetated strip adjacent to the former mill building at the RiverCourt Residences property (**Figure 13**). Vegetation observed on the bank includes slippery elm (*Ulmus rubra*), red maple (*Acer rubrum*), glossy buckthorn (*Frangula alnus*), silky dogwood (*Cornus amomum*), alder (*Alnus sp.*), poison ivy (*Toxicodendron radicans*), and grape (*Vitis sp.*). Additional species observed directly adjacent to the Bank includes red oak (*Quercus rubra*), white pine (*Pinus strobus*), black cherry (*Prunus serotina*), cherry birch (*Betula lenta*), shrub honeysuckle (*Lonicera sp.*), glossy buckthorn, Japanese barberry (*Berberis thunbergia*), staghorn sumac (*Rhus typhina*), steplebush (*Spiraea tomentosa*), poison ivy, grape, and Asian bittersweet (*Celastrus orbiculatus*). Along this extent of the river, the locally defined (Town of Groton) upper boundary of Bank is distinct from the upper boundary of Bank as defined by the Massachusetts Wetlands Protection Act at 310 CMR 10.54(2)(a). HW delineated the upper boundary of the locally defined Bank at the first break in slope with consecutive bright green flagging stations labeled BANK 100 to BANK 102. HW delineated the upper boundary of the state-defined Bank at the mean annual flood level with consecutive pink flagging stations labeled MA BANK 100 to MA BANK 102.





Figure 13. Looking upstream at the Bank south of the Dam, on the eastern side of the river.

Along the eastern side of the Squannacook River, between the Dam structure and the West Groton Bridge, within the jurisdiction of the Town of Groton, the Bank is primarily defined by a vertical stone wall that confines the river along the west side of the RiverCourt Residences property (**Figure 14**). The adjacent upland area consists of lawn, landscaping, walkway, and parking lot features associated with the RiverCourt Residences. There is a small section of vegetated Bank at the base of the stone wall along this extent, which consists of slippery elm, red maple, common buckthorn (*Rhamnus cathartica*), highbush blueberry (*Vaccinium corymbosum*), Japanese barberry, silky dogwood, poison ivy, and grape. Along this extent of the river, the locally defined (Town of Groton) upper boundary of Bank coincides with the upper boundary of Bank as defined by the Massachusetts Wetlands Protection Act at 310 CMR 10.54(2)(a), due to the presence of the stone wall. HW delineated the upper boundary of the Bank with consecutive pink flagging stations labeled BANK 103 to BANK 106.



Figure 14. Looking upstream at the Bank along the eastern side of the river, between the Dam and bridge.

#### Shirley Bank

Along the western side of the Squannacook River, south of the Dam structure, within the jurisdiction of the Town of Shirley, the Bank is vegetated with a mix of trees and shrubs and represents the edge of an alluvial hardwood flat community present along the low-lying area adjacent to the river (**Figure 15** and **Figure 16**). The slope then rises steeply up to the right of way of West Groton Road and is vegetated with a white pine-oak forest community. From the downstream side of the Dam, a stone wall extends to the south, approximately parallel to West Groton Road. The eastern face of this wall is exposed along the northern section and confines the river at the mean annual flood level; therefore, the wall represents the upper boundary of the Bank along this section. Further to the south, the wall becomes embedded into the slope downgradient of West Groton Road, where the mean annual flood level occurs further to the east, downgradient from the wall. Vegetation observed on the bank includes slippery elm, red maple, river birch (*Betula nigra*), gray birch (*Betula populifolia*), and silky dogwood. Commonly observed species directly adjacent to the Bank include red oak, cherry birch, white pine, ash (*Fraxinus sp.*), slippery elm, and common buckthorn. The extent of the Bank in the section closest to the Dam was delineated along the mean annual flood elevation, where there is no distinct break in slope between the river and the mean annual flood elevation. Further to the south, the slope between the river and the mean annual flood elevation rises steeply from the river's edge before breaking sharply and transitioning into the alluvial hardwood flat community; therefore, the upper boundary of the Bank was delineated at the break in slope along this extent. HW delineated the upper boundary of the Bank with consecutive pink flagging stations labeled BANK 202 to BANK 207.





Figure 15. Looking upstream at the Bank along the western side of river, directly south of the Dam.



Figure 16. Looking downstream at the Bank along the western side of the river, where the upper boundary occurs at the first break in slope.



Along the western side of the Squannacook River, between the Dam structure and the West Groton Bridge, within the jurisdiction of the Town of Shirley, the Bank consists of an open mix of shrub and vine species and is defined by the mean annual flood level. The slope rises steeply between the Bank and the bridge and consists primarily of vines and herbaceous species (**Figure 17**). Commonly observed vegetation along the Bank includes slippery elm, glossy buckthorn, silky dogwood, and Asian bittersweet. Commonly observed species directly upgradient of the Bank include poison ivy, Asian bittersweet, and bush clover (*Lespedeza sp.*). HW delineated the upper boundary of the Bank with consecutive pink flagging stations labeled BANK 200 to BANK 202.



Figure 17. Looking downstream at the Bank between the bridge and Dam.

#### Riverfront Area

Riverfront Area is defined at 310 CMR 10.58(2)(a)3 as *“the area of land between a river’s mean annual high-water line measured horizontally outward from the river and a parallel line located 200 feet away (...)”*

*2. Mean Annual High-water Line of a river is the line that is apparent from visible markings or changes in the character of soils or vegetation due to the prolonged presence of water and that distinguishes between predominantly aquatic and predominantly terrestrial land. (...).*

The Town of Groton Wetland Bylaw and Town of Shirley Wetlands Bylaw both apply the same Riverfront definition found in 310 CMR, as stated above.

Riverfront Area at the Site extends 200 feet landward from the mean high-water line (equivalent to the ordinary high-water line) of the Squannacook River. Riverfront Area overlaps with the

Banks and associated buffer zones. The Riverfront Area begins at the upper boundary of the delineated Bank sections labeled MA BANK 100-102, BANK 103-106, and BANK 200-207 in the Existing Conditions Plan (**Attachment C**, Sheet EX-4).

### Regulatory Designations

#### Wild and Scenic Rivers Designation

The Squannacook River holds a national designation as a Wild and Scenic River for its outstanding natural, recreational, scenic, historic, and cultural resources. Services of the Squannacook River that earned this designation include but are not limited to biological and ecological diversity, scenic vistas, and “some of the best fly-fishing within reach of Boston”.<sup>9</sup> (**Figure 18**)




Figure 18: National Wild and Scenic Rivers Map

<sup>9</sup> Nashua Wild and Scenic Rivers, Massachusetts and New Hampshire. P.L. 116-9. 133 Stat. 690. Enacted Mar. 12, 2019. <https://www.rivers.gov/river/nashua>

## Biomap Core Habitat Aquatic Core Designation and DFW Coldwater Fisheries Resources Designation

According to the Massachusetts Bureau of Geographic Information, (MassGIS), the site is designated as a BioMap Core Habitat Core Aquatic area and a DFW Coldwater Fisheries Resource. Rivers within BioMap Core Habitat Core Aquatic areas encompass segments with the native fish diversity, strongest anadromous fish runs, and occurrences of rare species in all of Massachusetts.<sup>10</sup> As a Coldwater Fish Resource (CFR), the Squannacook River has been identified as a critical resource for maintaining the overall health of cold-water fish species, which hold an ecologically significant role to Massachusetts aquatic habitat.<sup>11</sup> **(Figure 19)**




Figure 19. Coldwater Fish Resource and BioMap Core Map

<sup>10</sup>Massachusetts Division of Fisheries and Wildlife, The Nature Conservancy, "What is BioMap?". July 27, 2023. <https://storymaps.arcgis.com/stories/d8e383e6c651419e88f36f38b4fdc924>

<sup>11</sup> The Nashua River Watershed Association & The Massachusetts Watershed Initiative Nashua Team. 2003. "Nashua River Watershed 5 Year Action Plan 2003-2007". [https://www.nashuariverwatershed.org/5yr\\_plan/subbasins/squannacook.htm](https://www.nashuariverwatershed.org/5yr_plan/subbasins/squannacook.htm)



### FEMA Designation

According to the Federal Emergency Management Agency (FEMA) National Flood Hazard Map (Community Panel No. 25017C0182E, effective June 4, 2010 and No. 25017C0182F, preliminary June 8, 2023), the Site is located within Special Flood Hazard Areas, Regulatory Floodway, and Zone AE (1% annual chance of flooding). Additionally, there are also Other Areas of Flood Hazard at the site, which are categorized as Zone X (0.2% annual chance of flooding, areas of 1% annual chance flood average depth less than one foot or drainage areas of less than one square mile) to the west and northeast of the site (**Figure 20**).




Figure 20. Excerpt from the Federal Emergency Management Agency (FEMA) FIRMette for the site.

### State-listed Rare Species Habitat

According to the most recent version of the *Massachusetts Natural Heritage Atlas* (15<sup>th</sup> Edition, August 1, 2021), the site is located within areas mapped as *Estimated Habitat of Rare Wildlife* (EH 1300) and *Priority Habitat of Rare Species* (PH 2035) as designated by the Massachusetts Natural Heritage and Endangered Species Program (NHESP) (**Figure 21**). There are no *Certified Vernal Pools* or *Potential Vernal Pools* mapped within the vicinity of the project.




Figure 21. Rare species habitat (Source: MassMapper 2024)

### 2.4.4 Upstream Infrastructure

#### Groton Road (Route 225)

Groton Road is a state road that crosses the Squannacook River upstream of the Dam. The east end of Groton Road meets West Groton Center, at which point it transitions into West Main Street. Groton Road crosses the Squannacook River over the West Groton Bridge (see below) and continues along an embankment that separates the downstream and upstream reaches of the Squannacook River. It is unclear whether this embankment is natural or human-made; boring logs in the 1995 reconstruction plans for the West Groton Bridge do not indicate whether soil in the embankment is fill or not. The roadway has a low elevation of 239.6 on its northern side. The only known utilities along this section of Groton Road are overhead wires – no gas, water, sewer, or drainage are understood to run between the Towns.



### West Groton Bridge

The West Groton Bridge (**Figure 22**) is a 20-foot-wide bridge that spans 65 feet of the Squannacook River along Groton Road. The bridge is comprised of concrete and stone masonry. The bridge deck is approximately 19 feet higher than the channel bottom of the Squannacook River at the thalweg, 6 feet higher than the ordinary high water elevation, and 8 feet higher than the Dam spillway. Proposed Bridge Replacement Plans by Luchs Associates, Inc. (Background Document #1) show that prestressed concrete box beams support the bridge under the deck. During the January 31, 2024 site visit, 6 feet of separation was present between the water level and the bridge deck.



Figure 22. West Groton Bridge (Viewed from Downstream)

Based on the 1995 bridge reconstruction plans, the bridge footings of the West Groton Bridge are at least partially exposed to the flow of the river. No riprap is currently in place to protect the footings against scour.

### Hollingsworth & Vose Dam

The Hollingsworth & Vose (H&V) Dam is the next upstream dam along the Squannacook River, located 1.2 miles upstream of the Squannacook River Dam. The H&V Dam is operated by the Hollingsworth & Vose Company, a filtration and battery manufacturer which also operates the Townsend Harbor Dam an additional 4.9 miles upstream. Both dams are managed to control the water level of the Squannacook River Reservoir, the impoundment formed by the H&V Dam, and water is withdrawn from the impoundment for industrial processes at the Hollingsworth & Vose factory before being discharged downstream. Hollingsworth & Vose holds a National Pollutant Discharge Elimination System (NPDES) permit that regulates the water quality and outflow rates of the discharge. In the summer, stop logs are used to raise the dam elevation by up to 12 inches in order to increase the depth of the impoundment. Stop logs are typically



removed in the fall. Coordination with dam operators at Hollingsworth & Vose Company would be necessary prior to any potential construction activities at the Squannacook River Dam in order to ensure no unexpected impoundment release occurs.

#### Private Wells (Shirley)

Groton DPW personnel confirmed that residents of Groton in the vicinity of the Squannacook River Dam impoundment are on Town water, supplied by a well in the Groton Town Forest (downstream of the Dam).

In Shirley, mapping from the Executive Office of Energy and Environmental Affairs (EOEEA) indicates that properties in the vicinity of the impoundment along Groton Road and Squannacook Road receive water from private wells, which was also expressed by members of the public during a public meeting about this study, held on February 26, 2024. Recorded well depths generally range from 30 to 85 feet, with a few wells deeper than 400 feet.

An evaluation of potential impacts to private wells is included within this study in **Section 4.5**.

#### River-Left Retaining Wall

A retaining wall extending from the West Groton Bridge downstream to the penstock of the former mill building supports the earthen base of the RiverCourt Residences parking area. A portion of this retaining wall was exposed in 2013 when the Groton-side of the Dam was repaired in 2013. The wall is comprised of stone masonry from the West Groton Bridge until approximately 60 feet away from the former mill building, at which point it transitions to concrete (**Figure 23**).



Figure 23. River-Left Retaining Wall During 2013 Dam Repairs

#### 2.4.5 Abutters and Access Considerations

Review of tax parcels available through MassGIS indicates that there are at least 3 private parcels that directly abut the Squannacook River Dam impoundment in Groton and at least 6 private parcels that abut the impoundment in Shirley. In Groton, DPW personnel have engaged with one abutter, RiverCourt Residences, when performing dam inspections and repairs in the past. Initial public engagement providing general information about dam removal was conducted by NRWA in both Groton and Shirley, and by DER and the Town of Groton during a public meeting held on February 26, 2024. A follow up presentation summarizing the findings of the Feasibility Study occurred at a Groton Public Hearing on July 26, 2024.

As discussed further below, construction access to the Dam would likely be achieved through the northern driveway on the RiverCourt Residences property. This was the access route used during the 2013 repairs to the Groton side of the Dam (**Figure 24**). During the 2013 repairs, cofferdams were used to control water flow and create areas to work in the dry, and ladders were used to enter and exit the work area.



Figure 24. Access to Squannacook River Dam from RiverCourt Residences

## 3.0 SEDIMENT ASSESSMENT AND MANAGEMENT

### 3.1 Background and Feasibility Study Phase

In January 2024, as part of the prior Feasibility Study project phase completed for DER, HW completed a limited due diligence review of the Squannacook River in the vicinity of the Dam to evaluate potential historical threats to water and sediment quality and to inform sediment sampling. During that Feasibility Study phase, HW collected the following two composite sediment samples in the project reach of the river:

- One composite sample comprised from three locations within the impoundment, along the main river channel, and within the area anticipated to become potentially mobile if the Dam were removed. Discrete samples were 0-to-1-foot depth grabs at each location.
- One composite sample comprised from three locations below the Dam to identify existing downstream background conditions. Discrete samples were 0-to-1-foot depth grabs at each location.

Sediment samples were analyzed for the following parameters:


- Metals (arsenic, cadmium, chromium, copper, lead, mercury, nickel, and zinc)\*;
- Polycyclic Aromatic Hydrocarbons (PAHs);
- Volatile Organic Compounds (VOCs)\*\*;
- Polychlorinated Biphenyls with congeners;
- Extractable Petroleum Hydrocarbons (EPH);
- Total Organic Carbon;
- Percent water; and
- Grain Size Distribution – wet sieve (ASTM D422).

\*Note TCLP analyses were not run as those parameters were not detected above the TCLP 20X rule.

\*\*Discrete sediment samples were field screened prior to compositing.

Sampling locations from the Feasibility phase are shown in **Figure 25** below, reproduced from the 2024 Preliminary Design Assessment Report.





\*Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services

Figure 25: Initial Sediment Sampling Locations

[illegible]

The results of the Feasibility phase sediment analysis are described in detail further below. As part of the current pre-permitting phase, additional sediment sampling was conducted to screen potential sediment quality concerns related to the Thompson Mill Pond area upstream of the Dam and offline from the main river channel.

Squannacook River Dam Removal  
Groton and Shirley, Massachusetts



sediments in the pond that are currently submerged below water but would be likely to become exposed to the surface under low water level conditions if the Dam were removed. As discussed further below, sediment sampling locations were also included along the currently submerged spit separating the pond from the river, which represents the area of Thompson Mill Pond that may potentially become mobilized (though still not predicted to mobilized based on the Feasibility phase H&H modeling) if any sediment transport were to occur in this offline portion of the river.


### 3.2 Updated Due Diligence Review

In January 2024, HW completed an initial limited due diligence review to evaluate potential historical threats to water and sediment quality and to inform sediment sampling to be conducted as part of our initial Feasibility Study for removal of the Dam. The due diligence review has been updated, where relevant, to reflect the most up to date information as of this current pre-permitting phase study.

The limited due diligence review consisted of the following:

- An evaluation of online records available from the Massachusetts Department of Environmental Protection (MassDEP) Waste Site and Reportable Releases Database (the “Database”);
- A review of historical topographical maps, Sanborn Fire Insurance maps, and historical aerial photographs available online from the EDR™ Report, published by Environmental Data Resources Inc. (“EDR”);
- A screening of regulatory records for environmental conditions at and abutting the Site from the EDR Radius Map™ Report, published by EDR;
- A visual field assessment of the Site for evidence of a release of oil and/or hazardous materials (OHM).

HW utilized historical information along with a review of regulatory records for environmental conditions at and abutting the Site from the EDR Radius Map™ Report as well as online records available from the MassDEP Waste Site and Reportable Releases Database to determine and research known “Release Sites” at and abutting the site. Based on a review of the EDR Report, four release sites were identified within a half-mile of the site shown below in **Figure 27**. Details on the release sites and a map of release sites are provided below.



\*Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services

Figure 27: Nearby Release Sites and Sampling Locations



**Nielson Moulding**  
**8 West Main Street RTE 225**

**Release Tracking Number (RTN) 2-55**  
**Immediately east of Squannacook River Dam**

**Leatherboard Mill Former**  
**6 West Main Street**

**Release Tracking Number (RTN) 2-13033**  
**Immediately east of Squannacook River Dam**

According to the report titled *Class A-2 Response Action Outcome (RAO) Report and Statement* prepared by ENVIRON International Corporation and dated February 2011, two releases have occurred at this property. A release of metals and volatile organic compounds (VOCs) were identified in soil and groundwater, RTN 2-55, during an environmental site assessment. The second release, RTN 2-13033, was identified as a result of observed non-aqueous phase liquid (NAPL) fuel oil in a monitoring well on the property.

Various investigations have occurred at the property including a due diligence assessment wherein concentrations of polycyclic aromatic hydrocarbons (PAHs) and tetrachloroethene (PCE) were detected in groundwater. Response actions included installation of monitoring wells, soil sampling, and surface water sampling of the Squannacook River.

According to the report titled *Immediate Response Action Plan Completion* prepared by Leggette, Brashears & Graham, Inc. (LBG) and dated July 10, 2000, a release of NAPL oil was observed in a monitoring well near a former 25,000-gallon No. 6 fuel oil underground storage tank (UST). The release was identified to have impacted soil and groundwater at the property. Response actions included the excavation and removal of approximately 200 cubic yards of visually impacted soil and 72 gallons of groundwater via a vacuum truck. A 15,000-gallon AST, as well as 4,460 gallons of oil, was removed from the property, and during cleanup, a total of 2,370 pounds of drummed oil, oil solids, paint solids, acid, and caustic solution were removed from the property for off-site disposal. A total of 584.24 tons of impacted soils were disposed of off-site. Soil samples were collected from the tank grave areas, and monitoring wells were installed on property.

Based on a Method 3 Risk Characterization, a condition of No Significant Risk had been achieved on the property in regard to groundwater. Additionally, a Temporary Solution under a Class-C Response Action Outcome (RAO) for natural attenuation as concentrations of contaminants in groundwater (Extractable Petroleum Hydrocarbons, VOCs, and/or PAHs) were detected at low levels slightly exceeding GW-1 concentrations. After various additional rounds of groundwater sampling and the installation and/or replacement of monitoring wells as response actions as a result of additional MassDEP audits, a Method 3 Risk Characterization statement was presented, and a condition of No Significant Risk had been achieved for the site. Considering the regulatory status, the releases associated with RTN 2-55 and RTN 2-13033 are **unlikely to significantly impact the Site**.

**Hollingsworth & Vose Co.**  
**219 Townsend Road**

**Release Tracking Number (RTN) 2-54**  
**Approximately 2,703 feet northwest/upstream**

According to the letter report titled *Final Screening Site Investigation* prepared by NUS Corporation and dated May 29, 1991, a release was observed on the property as an overflow of raw waste directly into the Squannacook River. This property operated as a manufacturer of industrial and technical papers and landfill, and paper sludge and wastewater are disposed of into two sludge beds on the property. The release was attributed to an issue with the facility's wet well

pump, and the untreated water consisted of “an acrylic latex mix and paper machine white water containing cellulosic fibers”. Response actions included groundwater and surface water monitoring as well as soil samples on the property.

According to the *LSP Evaluation Opinion* prepared by Goldman Environmental Consultants (GEC), Inc. and dated February 6, 1995, a site investigation including surface water and groundwater monitoring was conducted. As a result of the monitoring, no evidence indicated a significant release of oil or hazardous materials to the sampled media. GEC also sampled the three sludge drying beds on the property, and the results also indicated no evidence of a significant release of oil or hazardous materials. As a result of GEC’s evaluation, the site was not considered a disposal site under the MCP, and therefore, the release associated with RTN 2-54 is **unlikely to significantly impact the Site**.

**Hollingsworth & Vose Co.**  
**219 Townsend Road**

**Release Tracking Number (RTN) 2-19346**  
**Approximately 2,703 feet northwest/upstream**

According to the report titled *Immediate Response Action Completion Report and Permanent Solution Statement* prepared by Clean Harbors Environmental Services, Inc. and dated April 21, 2015, a historical release of No. 6 fuel oil was discovered during a subsurface investigation and boring advancement. The location of the release was observed in the vicinity of an existing fuel storage building and two buried concrete 50,000-gallon underground storage tanks (USTs) that were closed in place. Response actions included the advancement of additional soil borings and soil sampling. Groundwater was encountered at approximately nine feet below grade while contaminated soils were identified as deep as 10.5 feet below grade. Groundwater monitoring wells were installed and sampled. According to the report, groundwater was minimally but measurably impacted with detections slightly above the applicable Method 1 GW-1 standard. An Activity and Use Limitation exists at the property regarding the contaminated soil and groundwater on the property. Approximately 20 cubic yards of oily soil exist 7 feet below grade and is isolated beneath pavement or a building. As a result of the AUL, a Permanent Solution with Conditions has been established on site. Considering the regulatory status, the release associated with RTN 2-19346 is **unlikely to significantly impact the Site**.

### 3.2.1 Additional Considerations

A Groton resident whose property abuts the Thompson Mill Pond area of the impoundment told HW that the upstream Hollingsworth & Vose Co. previously manufactured cigarette filters containing asbestos, as recently as the 1950s. In our due diligence review, HW found no records of a known release associated with asbestos products. The abutter’s statement about potential asbestos concerns was provided to HW after our initial January 2024 due diligence review, the sampling plan, the sampling itself, and all laboratory analyses were completed. In order to address the potential presence of this additional contaminant, sampling and analysis for asbestos was included in the current pre-permitting phase sediment sampling plan, described below.



### 3.3 Pre-Permitting Phase Sediment Sampling Plan

The known contaminant source at the historic mills and industrial land along the Dam and closely surrounding the Site suggests the potential presence of polychlorinated biphenyls (PCBs), metals, polycyclic aromatic hydrocarbons (PAHs), volatile organic compounds (VOCs), and asbestos to impact sediment quality.

Based upon the above-discussed updated due diligence review, and in consideration of the 401 Water Quality Certification (WQC) requirements (314 CMR 9.00), HW prepared the following Pre-permitting Phase Sediment Sampling Plan, including all of the standard WQC parameters. Asbestos was also included in the Sediment Sampling Plan in order to investigate the concerns raised by an abutter of the Thompson Mill Pond. A draft of this Pre-permitting Phase Sediment Sampling Plan was shared with MassDEP in November 2024, and personnel from the 401 WQC Unit indicated that the draft plan would be appropriate for a future 401 WQC application submission.


The Pre-permitting Sediment Sampling Plan included laboratory analyses as follows:

- Metals (arsenic, cadmium, chromium, copper, lead, mercury, nickel, and zinc);
- Polycyclic Aromatic Hydrocarbons (PAHs);
- Volatile Organic Compounds (VOCs);
- Polychlorinated Biphenyls with congeners;
- Extractable Petroleum Hydrocarbons (EPH);
- Total Organic Carbon;
- Percent water;
- Grain Size Distribution – wet sieve (ASTM D422); and
- Asbestos.

Sediment sampling locations included the following:

- One composite sample comprised from three locations within areas of accumulated sediment in Thompson Mill Pond. Though mobilization is not indicated by H&H modeling, these locations are closer to the main river channel and therefore have higher potential to mobilize than other areas of Thompson Mill Pond, if any mobilization from the pond were to occur.
- One composite sample comprised from three locations along the banks of Thompson Mill Pond. These locations are more likely to become exposed above the water surface if dam removal occurs.

**Figure 28** below depicts the discrete sampling points and the groupings for each composite sample. All samples were vertically blended from the top several feet of sediment (as could be effectively reached with sampling equipment) likely to be potentially mobilized in a dam removal scenario.



\*Bureau of Geographic Information (MassGIS), Commonwealth of Massachusetts, Executive Office of Technology and Security Services

Figure 28: Impoundment Sampling Locations



### 3.4 Sediment Sampling Results

HW conducted sediment sampling on two occasions; first on January 31, 2024, as part of the initial Feasibility Study and then on November 19, 2024 during this current Pre-permitting Project phase.. All sediment sampling was completed following the above referenced sediment sampling plans (one for each of the two Project phases), which were established as a result of the due diligence review of potential contamination sources.

All samples were collected in appropriate laboratory delivered containers, stored on ice, and picked up the next day by ESS Laboratories from Cranston, Rhode Island. During field sampling, visual and olfactory observations were made for evidence of release of oil and hazardous materials (OHM), and none were noted. Soil samples were field screened for TOV with a PID using the jar headspace method. TOV PID values ranged from less than the detection limit of the equipment (<0.1 ppmv) to a maximum of 0.4 ppmv.

Laboratory sediment quality results from both sampling events were entered into the standard DER sediment quality spreadsheet for comparison to the Massachusetts Contingency Plan (MCP) S-1/GW-1 standards for human health as well as the key ecological thresholds Threshold Effects Concentrations (TEC) and Probable Effects Concentrations (PEC) for freshwater. The full laboratory results from both sampling events are included here as **Attachment A**.

#### 3.4.1 Feasibility Study Phase – January 2024

Key observations from the Feasibility Study sediment sampling are as follows:

- Most results were below laboratory detection limits and are shown in green font on the MADER Sediment Quality Table with values equal to half of the laboratory reporting limit. Black font values are results in excess of reporting limits for MA DEP Soil Standards and Guidance Values, orange highlighted values are results in excess of Sediment Threshold Effects Concentrations, and yellow highlighted values are actual results in excess of Sediment Probable Effects Concentrations.
- Metals were detected above laboratory reporting limits, but most metals were detected below both MCP standards and sediment thresholds. One metal, arsenic, was detected in the downstream sample (Groton DS) at concentrations greater than the sediment threshold TEC values. There were no metals detections above MCP S1 standards.
- Polycyclic aromatic hydrocarbons (PAHs) were detected in both the upstream and downstream samples. Both upstream and downstream, individual concentrations were below TEC values with the exception of Anthracene, Benzo[a]anthracene, Benzo[a]pyrene, Benzo[b]fluoranthene, Benzo[g,h,i]perylene, Benzo[k]fluoranthene, Chrysene, Dibenz[a,h]anthracene, Fluoranthene, Fluorene, Indeno[1,2,3-cd]pyrene, Naphthalene, Phenanthrene, and total PAHs, which were detected in the upstream sample at a concentration greater than the Sediment Thresholds TEC values but below values listed in MCP S1 standards.
- Volatile Organic Compounds (VOCs) were not detected over reporting limits in either upstream or downstream sample.

- Polychlorinated Biphenyls (PCBs) were detected upstream and downstream in both samples above reporting limits but below sediment threshold TEC standard values and below MCP S1 standards. PCBs were anticipated to be detected due to the historical use in the vicinity of the site.
- Extractable Petroleum Hydrocarbons (EPH) were not detected above reporting limits at either upstream or downstream samples.
- Sediment for all composite samples consisted of mostly brown poorly graded sand. Upstream samples consisted of 9.9% gravel, 85.5% sand, and 4.6% fines. Downstream samples consisted of 5.5% gravel, 91.7% sand, and 2.8% fines.

Based on these initial findings, dam removal would not be expected to result in threats to water or sediment quality due to transport of moveable sediments from upstream to downstream. It is likely that few contaminants were retained within the sediment due to its coarse nature and associated interstitial spaces, which are larger and allow more space for water to flush contaminants out of the sediment.

### 3.4.2 Pre-Permitting Phase – November 2024

Key observations from the Pre-permitting Project phase sediment sampling in the Thomson Mill Pond area are as follows:

- Consistent with the Feasibility phase upstream sample, no analytes were detected above MCP standards in either the impoundment center sample or the impoundment edge sample.
- Both impoundment samples are consistent with previous upstream and downstream sample results for VOCs and PCBs. No VOCs were detected in either impoundment sample, while several PCBs were detected in both samples below TEC thresholds.
- The impoundment samples had fewer detections of PAHs than the previous upstream sample, and all detections were below TEC thresholds.
- EPH results were generally consistent with previous samples results, with the exception of two detections in the impoundment center sample, both of which were below TEC thresholds.
- The impoundment samples had several detections of metals above TEC thresholds not seen in the previous upstream sample, but none were detected above MCP standards.
- Asbestos was not detected in either impoundment sample.
- Sediment in the impoundment samples is considerably finer, consisting of mostly dark brown organic silty sand. The impoundment center sample consisted of 62.7% sand and 37.3% fines. The impoundment edge sample consisted of 70.6% sand and 29.4% fines.

Based on these initial findings, dam removal would not be expected to result in threats to water or sediment quality due to possible transport of moveable sediments or exposure of sediments due to lower water levels. Consultation with the Massachusetts Department of Environmental



Protection (MassDEP) will be needed to determine if further sampling will be needed, and whether dam removal planning may continue as determined through the 401 WQC process.

## 4.0 HYDROLOGIC AND HYDRAULIC ANALYSIS

HW developed a hydrologic and hydraulic (H&H) model of the subject reach of the Squannacook River to provide an understanding of how the Dam affects water levels, flow velocities, and sediment transport within the project area. Specifically, this analysis was used to determine the potential future impacts of removing the Dam.

Hydrology, in this context, refers to the volume of precipitation-derived water from the watershed conveyed to the river under different storm and flow conditions, while hydraulics refers to the flow characteristics of the river resulting from those hydrologic inputs under the same set of flow conditions.

### 4.1 Model Development

For this project phase, HW built upon the H&H model previously developed during the 2024 Feasibility Study. The 2024 H&H model utilized the U.S. Army Corps of Engineers (USACE) Hydraulic Engineering Center River Analysis System (HEC-RAS, v. 6.6) software, a one-dimensional, steady-state flow model. One-dimensional HEC-RAS models are well-suited for situations like the current study where hydraulic changes occur predominantly in one dimension (i.e., from upstream to downstream along the centerline of the channel). For this current pre-permit-level design phase of the Project, HW updated the 2024 one-dimensional model to a two-dimensional, unsteady-state flow HEC-RAS model in order to more fully assess sediment mobilization, scour, fish passage, and water elevations under the proposed dam removal design. Two-dimensional models utilize additional data inputs such as 3-D bathymetry in order to produce detailed predictions of hydraulics. Unlike one-dimensional models, two-dimensional models can predict lateral variation in water velocity and shear stress across the full extents of the modeled river.

The 2025 updated H&H analysis was completed to more fully evaluate the following potential impacts from dam removal:

- An evaluation of typical daily water level elevations in the impoundment subsequent to dam removal, with a focus on the Thompson Mill Pond area.
- An analysis of flow velocities through the area upstream of the Dam to assess scour risk to the West Groton Bridge and nearby retaining walls, and to inform potential mitigation via hard armoring (riprap).
- An assessment of potential impacts to nearby wells based on a reduction in impoundment water levels.
- An updated evaluation of likely sediment transport extents and volume.
- An updated assessment of impacts to recreational activities such as paddling and fishing.
- An updated analysis of predicted flooding conditions along the Squannacook River during the annual exceedance probability flood events (e.g., the 2-year and 100-year flows).

#### 4.1.1 Hydrology

In the H&H analysis developed for this project, the hydrologic inputs were determined after evaluating three hydrological estimation methods. Those methods include:

- The Prorated Gage Method uses annual peak flow data from USGS Gage 0109600, which is located on the Squannacook River approximately 3 miles upstream of the Dam. The method prorates gaged flow statistics based on the relative watershed areas of the gauged station and the ungauged location at the Dam. Based on 75 years of available data, peak flow statistics for this gaging station were calculated from the annual peak flow values. Statistics were then prorated by the ratio of the contributing drainage area of the Squannacook River at the Dam (69.5 square miles) to the drainage area at the upstream gage (63.7 square miles).
- The FEMA FIS Method uses peak flow statistics provided by the Federal Emergency Management Agency (FEMA) Flood Insurance Study No. 25017CV001C for the Squannacook River. Peak flow statistics were calculated by FEMA at several points along the Squannacook River based on the same gage used in the Prorated Gage Method described above. Values for the 10-, 2-, 1-, and 0.2-percent-annual-chance discharges at the gage were calculated by FEMA using a Log-Pearson Type III analysis of annual peak flow data and were scaled to estimate flows at the Squannacook River's confluence with the Nashua River. The Natural Resources Conservation Service (NRCS)'s standard methodology for the hydrologic routing of flows was applied by FEMA to define discharge-frequency relationships for the Squannacook River at sections upstream and downstream of the gaging station. In a similar fashion as the Prorated Gage Method, the NRCS method uses the ratio of drainage areas at two different points to find their respective discharges in cubic feet per second per square mile.

Although the Prorated Gage Method and the FEMA FIS Methods follow very similar processes, their results vary due to differences in data. The Prorated Gage Method uses flow statistics from the start of USGS Gage 0109600 in 1949 to 2025 (75 years), while the FEMA FIS Method uses data from 1949 to 2014 (64 years). With a smaller sized data set utilized in the FEMA FIS Method, individual outliers have a greater impact on the calculated hydraulic inputs. Thus, the Prorated Gage Method is predicted to be the more accurate method due to its larger dataset.

- StreamStats is a software program produced by USGS that generates estimates of stream properties such as peak flow rates, low-flow statistics, and bankfull width. To do so, StreamStats uses regression models based on basin characteristics such as drainage area, mean basin slope, basin length and width, and percent of land characterized by water bodies, forest, and sandy/gravelly soils. Different regression



models are developed regionally; peak flow rate estimates for the Squannacook River are based on a hydrological model developed by USGS for Massachusetts.

The estimates of flow rates during peak flood and more frequent daily recurrence intervals using each of the aforementioned hydrologic methods is shown below in **Table 1**. **Table 1** estimates are based on a location in the river immediately upstream of the West Groton Bridge.

**Table 1. Comparison of Peak Flow Estimates (cfs) Upstream of Squannacook River Dam by Different Hydrological Methods**

<b>Recurrence Interval</b>	<b>Prorated Gage</b>	<b>FEMA</b>	<b>StreamStats</b>
<b>95% exceedance</b>	12.0	*	*
<b>50% exceedance</b>	78.1	*	*
<b>5% exceedance</b>	401.5	*	*
<b>2-year</b>	1,542	*	1,370
<b>5-year</b>	2,484	*	2,210
<b>10-year</b>	3,214	3,540	2,860
<b>25-year</b>	4,252	*	3,810
<b>50-year</b>	5,108	6,880	4,610
<b>100-year</b>	6,039	8,840	5,430
<b>200-year</b>	7,051	*	6,350
<b>500-year</b>	8,527	15,160	7,650

\*data not available

As illustrated, different peak flow estimates for all events are generated using the three different methods. Because of its reliance on the most extensive dataset of local-scale field data, the Prorated Gage Method-generated flows are considered the most accurate overall and were therefore used for subsequent modeling and analyses discussed herein.

Further, the Prorated Gage Method offers a reasonable middle estimate as compared to the lower estimated flows from StreamStats and the considerably higher estimated flows produced by FEMA. Based on USGS Gage No. 01096000, the historical record of peak flow is estimated to be 4,820 cfs (in April 2007), which falls between the range of the 25-year and 50-year storm flows of the Prorated Gage hydrology. During the April 2007 peak flow, DPW personnel confirmed that water levels were well below the bottom of the West Groton Bridge. By contrast, FEMA's Flood Insurance Rate Maps (FIRM), which are based on the FEMA flow rates described above, predict that Route 225 would become inundated during the 25- and 50-year events. Based on observed peak flooding, it is likely that the FEMA hydrology is an overestimation of on-site flows.

Potential changes in site hydrology under future climate conditions were assessed using the ResilientMass Action Team's (RMAT's) Climate Resilience Design Standards Tool to generate design flows appropriate for the project setting. The RMAT Project Report (**Attachment B**) recommends that a 25-year storm with a projected 24-hr total precipitation depth of 6.6 inches is used as the design storm for assessing the impacts of climate change at the Project Site. The report also recommends that the extreme precipitation output values are compared to the NOAA+ methodology to calculate total precipitation depth for a 24-hr design storm. Because the 25-year storm is less conservative than the 100-year flow used in the previously discussed H&H

Model, the NOAA+ methodology was used to account for the impacts of climate change at the Project Site.

HW scaled the Prorated Gage Method hydrology by the ratio of the NOAA+ rainfall estimates to the standard NOAA Atlas 14 rainfall estimates in Groton to produce a hydrology that accounts for higher rainfall depths as a result of climate change, per the RMA2 recommendations (**Table 2**). The updated hydrology was used for all H&H analyses in the current pre-permit level design phase as a conservative measure to account for climate change.

**Table 2. Comparison of Peak Flow Estimates (cfs) Upstream of Squannacook River Dam with and without Adjusting for Climate Change**

<b>Recurrence Interval</b>	<b>Prorated Gage</b>	<b>NOAA+ Adjustment</b>
<b>95% exceedance</b>	12.0	13.1
<b>50% exceedance</b>	78.1	85.2
<b>5% exceedance</b>	402	438
<b>2-year</b>	1,542	1,677
<b>5-year</b>	2,484	2,722
<b>10-year</b>	3,214	3,522
<b>25-year</b>	4,252	4,865
<b>50-year</b>	5,108	5,965
<b>100-year</b>	6,039	7,325
<b>200-year</b>	7,051	8,572
<b>500-year</b>	8,527	10,667

#### 4.1.2 Existing Conditions Model

To develop the Project's original 1D existing conditions HEC-RAS model, HW incorporated topographic and bathymetric field data collected from 15 transects along the Squannacook River, including two additional transects that were collected during the November 2024 bathymetric survey. The locations and number of cross sections collected by HW were chosen based on where the most detail along the length of the stream was needed for the model to perform an accurate representation of flow dynamics resulting from changes in topography and hydraulics. Cross sections were extended across the floodplain using available light detection and ranging (LiDAR) data. **Figure 29** shows a schematic plan of the existing 1D HEC-RAS model.




Figure 29. Final HW Existing Conditions HEC-RAS Model Schematic - Project Area

Schematics of the Dam and the West Groton Bridge are shown below as **Figure 30** and **Figure 31**, respectively.




Figure 30. Squannacook River Dam HEC-RAS Model Schematic






Figure 31. West Groton Bridge HEC-RAS Model Schematic

Flow measurements taken by the USGS West Groton Gage on the days of HW's topographic and bathymetric field data collection were used along with measurements of the WSE along the river to calibrate the model. Based on the observed water surface measurements during the HW survey, variables such as channel roughness and downstream boundary conditions were adjusted to match HEC-RAS predictions of water surface elevations with observed elevation measurements.

### 2D Model Development

HW used the existing bathymetric and topographic data collected to create the original 1D model during the Feasibility Study phase combined with new bathymetric data collected in the offline Thompson Mill Pond section of the river during the current Pre-permitting Project phase to develop a 2D HEC-RAS model of the Squannacook River. Survey and LiDAR data were combined to create a digital elevation model (DEM), which served as the geometric basis for the 2D model (**Figure 32**).

The Dam and West Groton Bridge are represented in the 2D model as shown in **Figure 33**. Structure geometry was input using the most up to date data collected during the November 2024 survey.




Figure 32. Digital Elevation Model (DEM) of Squannacook River




Figure 33. Squannacook River Dam and West Groton Bridge 2D Representations

## 4.2 Model Results

The 2D existing conditions model was modified incrementally to create a 2D proposed conditions model. The proposed conditions Dam-out model includes the following:

- Removal of the full vertical and horizontal extent of the Dam; and
- Sediment mobilization and transport, assumed to occur via instream sediment management.

The proposed conditions model was developed with the assumption that bedrock immediately downstream of (and perhaps underneath) the Dam would not be removed or mobilized by dam removal. The location and elevation of bedrock at the Dam was modeled using survey data collected by HW during the November 2024 site visits and by referencing the Construction Completion Report of the Squannacook River Dam by Haley & Aldrich, Inc. on January 10<sup>th</sup>, 2014.

Model results relative to sediment transport and fish passage are discussed in the section below.

### 4.2.1 Dam Removal and Sediment Transport

**Table 2** presents the water surface elevations for the median daily flow, the 2-year flow, and the 100-year flow at two points upstream of the Dam, under existing conditions and proposed conditions.

Table 3. Modeled Water Surface Elevations

	Downstream of Squannacook River Dam (Transect 1)	Downstream of Squannacook River Dam (Transect 5)	Upstream of Squannacook River Dam (Transect 7)	Upstream of West Groton Bridge (Transect 10)
<b>50% Flow (78.1 cfs)</b>				
Existing Conditions Elevation (feet)	211.12	216.92	228.60	228.60
Dam Removed Elevation (feet)	210.79	216.36	218.49	218.96
<b>Difference</b>	<b>-0.33</b>	<b>-0.56</b>	<b>-10.11</b>	<b>-9.64</b>
<b>2-Year Flow (1,542 cfs)</b>				
Existing Conditions Elevation (feet)	214.95	219.46	230.74	230.79
Dam Removed Elevation (feet)	214.83	219.17	221.30	223.28
<b>Difference</b>	<b>-0.12</b>	<b>-0.29</b>	<b>-9.34</b>	<b>-7.51</b>
<b>100-Year Flow (6,039 cfs)</b>				
Existing Conditions Elevation (feet)	219.64	223.25	234.05	234.32
Dam Removed Elevation (feet)	219.57	223.09	224.24	227.63
<b>Difference</b>	<b>-0.07</b>	<b>-0.16</b>	<b>-9.81</b>	<b>-6.69</b>



Removal of the Dam is predicted to reduce impoundment water levels by as much as 10.11 feet during median flows. During the 100-year flow, water levels are predicted to be reduced by up to 9.81 feet. **Table 3** shows the friction slope, which represents the energy available to transport sediment along the length of the channel. Under proposed conditions, the friction slope is expected to increase upstream relative to existing conditions. These increases in friction slope values do not exceed existing downstream value at Transect 2; therefore, the existing channel slope at Transect 2 is likely to be the maximum slope of the channel bottom upstream of the Dam in post-dam removal conditions.

Table 4. Friction Slope During 100-Year Flow

Position	Transect Number	Friction Slope (ft/ft) under Existing Conditions	Friction Slope (ft/ft) under Proposed Conditions
Upstream of Dam	14	0.000805	0.005594
	13	0.000552	0.002669
	12	0.000164	0.001740
	11	0.000138	0.001702
	10	0.000254	0.001384
	9	0.000720	0.005158
	8	0.000623	0.004701
	7	-	0.007173
Dam			-
Downstream of Dam	6	0.003593	0.003378
	5A	0.002160	0.002028
	5	0.004006	0.004006
	4	0.004594	0.004594
	3	0.004616	0.004616
	2	0.010360	0.010360
	1	-	-

While some sediment immediately upstream of the Dam is expected to transport soon after the Dam is removed, long-term sediment transport as a result of the proposed dam removal is expected to be negligible. It is likely that much of the soft sediment loading received by the Squannacook River is intercepted by the H&V Dam farther upstream, resulting in the small amount of sediment observed within the Squannacook River Dam impoundment. It is also possible that the 2003 dredging of the Thompson Mill Pond area of the impoundment has reduced the total sediment accumulation upstream of the Dam, although minimal transport is expected to occur in this relatively static backwater area.

Channel velocities and shear stress values upstream of the Dam under the 2-year flow are shown for existing and proposed conditions in **Table 4**. Velocities under proposed conditions are expected to reach a peak of 9.08 feet per second (fps) upstream of the Dam, with a corresponding shear stress of 3.04 pounds per square foot (psf). These values exceed the

transport thresholds for up to and including 2-inch diameter gravel and cobbles, indicating that particles with diameters equal to or less than 2-inches have the potential to mobilize during or soon after the dam removal process. However, consideration of the energy grade line, which is equivalent to the friction slope or slope at which sediment transport is expected to occur, indicates that there are only two main locations where the river would have the energy required for transport post-removal: immediately upstream of the Dam and approximately 200-400 feet upstream of the Dam. At the upstream limit of the H&H model, the energy grade line approaches the grade of the river bottom, indicating that minimal upstream sediment transport would be expected.

The position of the stream bed below the presumed energy grade line downstream of the Dam (**Figure 34**) is used as a reference for the maximum slope at which sediment transport would be expected to occur.




Figure 34. Profile of Energy Grade Line in the vicinity of the Squannacook River Dam

Table 5. Velocity and Shear Immediately Upstream of Squannacook River Dam Under the 2-Year Flow

Condition	Main Channel Velocity (feet/sec)	Main Channel Shear Stress (lb/sq ft)
Existing	1.93	0.14
Proposed	9.08	3.04

Instream sediment management is estimated to result in a total sediment transport volume of ~2,630 cubic yards. The expected depth and lateral extents of sediment transport are shown in **Figure 35** and **Figure 36**. Due to the high velocity required to prevent coarse grained material from settling, coarse-grained sediment is not predicted to remain suspended for as long as fine-grained sediment and thus will not be carried as far downstream. Still, it is likely that the initial release of impounded sediment will result in the transport of larger sediment sizes downstream of the former Dam. This transport is likely to be beneficial for river health, as the area downstream of the Dam is probably sediment starved due to the presence of the Dam. The deposition of sediment downstream could replenish these areas and help to prevent erosion in the future.




Figure 35. Profile of Anticipated Sediment Mobilization in the Vicinity of the Squannacook River Dam




Figure 36. Approximate Extents of Anticipated Mobilized Sediment

**Table 5** shows the comparison of potentially mobile impounded sediment to watershed-wide sediment loads. The potential sediment load induced by dam removal is predicted to be approximately 29% of the total annual sediment load estimated to occur in the Squannacook River. Despite this increase, transport of impounded sediment would most likely occur over several years, meaning that the increase to annual sediment loading in the river will be gradually redistributed at a smaller proportion of the annual load than 29%.



Table 6. Comparison of Potentially Mobile Impounded Sediment vs. Watershed Sediment Loads

Parameter	Volume (cy)	Avg. Dry Unit Weight (kg/cy) <sup>12</sup>	Sediment Load (kg, dry )
Estimated Potentially Mobile Sediment Impounded by Squannacook River Dam	2,631 <sup>13</sup>	600	1,578,600
Mean Annual Modeled Sediment Loads for Squannacook River Watershed Upstream of the Dam <sup>14</sup>			5,351,914
<b>Percent of annual mean sediment load that may mobilize due to dam removal<sup>15</sup></b>			<b>29%</b>

#### 4.2.2 Post-Removal Impoundment

As discussed above, water levels in the impoundment are predicted to decrease by over 10 feet during typical, median flow conditions post-dam removal, indicating that the Thompson Mill Pond area of the river may become hydraulically disconnected from the main body of the river.

Based on the bathymetric survey of Thompson Mill Pond and its connection to the Squannacook River, there is a buildup of sediment that forms a ridge between the main river channel and the pond. Soft, potentially mobile sediment along the ridge ranges in thickness from 0.5-2.0 feet, with underlying coarse sediment that is unlikely to mobilize. While sediment mobilization in this area is possible, limited soft sediment depths and low predicted velocities across the buildup following dam removal make significant sediment transport unlikely, and the ridge would not be expected to become lower than elevation 224.3, based on the underlying coarse sediment.

HW evaluated a range of flow conditions in the 2D model to investigate the interaction between the main river channel and the pond. **Figure 37**, below, shows water surface elevations in the river under proposed conditions during the 2-year flow. During the 2-year flow, water surface elevations adjacent to the ridge are only predicted to reach a maximum elevation of 223.9, just below the elevation that would cause flow to spill over into the pond. As the 2-year flow is approximately equal to (and, in fact, slightly higher than) the typical bank-forming flow event, it is likely that the buildup of sediment would revegetate and stabilize, minimizing the likelihood of transport occurring in the future.

<sup>12</sup> Calculated based on standard average soil bulk density, HEC-RAS 2D Sediment Technical Reference Manual. <https://www.hec.usace.army.mil/confluence/rasdocs/d2sd/ras2dsedtr/latest/model-description/water-and-sediment-properties/sediment-properties>

<sup>13</sup> Calculated from sediment probing data collected in January and November 2024 within the main flow path

<sup>14</sup> Simulated by the EPA Model My Watershed – Watershed Multi-Year Model (simulates 30-years of daily data by the GWLF-E (MapShed) model).

<sup>15</sup> Total of likely + potentially mobile sediment divided by the modeled mean annual sediment load for the watershed.




Figure 37. Predicted Water Surface Elevations under Dam Removal Conditions During the 2-Year Flow

Proposed water levels are not predicted to reach elevations high enough to overtop the ridge and spill into the pond until the 10-year flow. Even then, predicted water elevations in the river are only high enough to allow flow into the existing pond basin for a brief period during the height of the flow event (**Figure 38**). Given the infrequency of flow entering the post dam removal Thompson Mill Pond, what is currently a pond would be expected to convert into primarily a vegetated wetland with perhaps some areas of open water during higher water periods. The converted wetland area would be closer to natural, pre-industrial conditions and would provide additional benefits of flood storage and improved water quality.




Figure 38. Predicted Water Surface Elevations under Dam Removal Conditions During the 10-Year Flow

### 4.3 Fish Passage

The existing Dam represents a significant barrier to the passage of aquatic organisms. The proposed condition dam removal eliminates this obstacle, increasing stream connectivity and flow velocities at the former Dam site. The impacts of dam removal and sediment transport on water depths and velocities are displayed in **Table 7**.

The Squannacook River subbasin includes multiple priority habitat areas which were designated for their role in supporting native brook trout populations.<sup>16</sup> Due to its presence in the Squannacook River and its ecological role as an indicator species of relatively healthy riverine environments<sup>17</sup>, the Eastern Brook Trout was selected as a target species used to evaluate the impacts of proposed dam removal activities. Fish passage is assessed in terms of brook trout navigability during low (95% exceedance) and high (5% exceedance) flow events. Brook trout have a maximum burst speed of approximately 3.0 fps<sup>18</sup> and require a minimum water depth of 0.3 feet<sup>19</sup> for successful passage. In some cases, brook trout passage has been observed in water velocities up to 5 fps<sup>20</sup>, although this depends on channel substrate roughness and fish life stage. In rough channel beds, like those found downstream of the Dam, brook trout have

<sup>16</sup> Nashua River Watershed Association, *Nashua River Watershed 5 Year Action Plan 2003-2007*, 2003.

<sup>17</sup> Massachusetts Division of Fisheries and Wildlife, *Brook Trout Fact Sheet*, 2015

<sup>18</sup> Kondratieff, M.C. and Myrick, C.A. 2006. Brook Trout Jumping Performance. American Fisheries Society.

<sup>19</sup> Ibid.

<sup>20</sup> Goerig, E. et al. 2015. Brook Trout Passage Performance Through Culverts. Canadian Journal of Fisheries and Aquatic Sciences.



been observed to successfully navigate short segments of rivers with water velocities up to 5 fps at a roughly 50% success rate<sup>21</sup>.

1D modeling results from the Feasibility Study indicate that dam removal would not worsen fish passage conditions, as velocities upstream of the Dam are not expected to exceed those that currently occur in the reach downstream of the Dam. Assuming that brook trout are currently able to migrate up to the base of the Dam, the proposed dam removal is not predicted to introduce any new limitation to the passage of brook trout. Removal does however eliminate the major obstacle to fish passage posed by the dam itself. Additionally, 1D modeling indicated that main channel depths may occur post dam removal that are more favorable for brook trout navigation during low flows.

As discussed above, a 2D HEC-RAS model was developed for this current Pre-permit Level study in order to better evaluate the impacts of dam removal on fish passage across the study area by providing a more detailed view of river depth and velocity across potential routes for brook trout passage. The 2D model simulated low (95% exceedance), median (50% exceedance), and high (5% exceedance) daily flow conditions in order to assess a wide range of flow conditions at which upstream passage could potentially occur.

#### Low Flow Passage

Low flow conditions were assessed based on the flow path shown on **Figure 39** and **Figure 40**. Depth and velocity along this flow path are shown graphically on **Figure 41** and **Figure 42**, respectively. During low flow conditions, both depth and velocity may be outside of target criteria for brook trout at one location downstream of the former Dam. This area would be monitored for fish passage after removal, and boulders could be added to increase channel complexity. In the vicinity of the Dam itself, water depth and velocity are well within the target criteria for brook trout passage, indicating that dam removal would allow successful passage at the former location of the Dam for brook trout that are able to reach that point in the river. The 2D model results also indicate that downstream depths are generally deeper under proposed conditions than existing conditions, offering a greater potential chance for brook trout to reach the Site.

---

<sup>21</sup> Ibid.




Figure 39. 95% Daily Exceedance Flow Depth  
**Light blue** indicates **shallower** than target criteria (0-0.3 feet).  
**Dark blue** indicates **deeper** (0.3 feet +).




Figure 40. 95% Daily Exceedance Flow Velocity  
**Navy blue** indicates **within** target criteria (0-3 fps).  
**Purple** indicates **potential passage** per target criteria (3-5 fps).  
**Red** indicates **unlikely passage** per target criteria (5 fps +).






Figure 41. 95% Daily Exceedance Flow Depth




Figure 42. 95% Daily Exceedance Flow Velocity

### Median Flow Passage

Median flow conditions were assessed based on the flow path shown on **Figure 43** and **Figure 44**. Depth and velocity along this flow path are shown graphically on **Figure 45** and **Figure 46**, respectively. During median flow conditions, minimum depth criteria are predicted to be met across the full flow path, while target velocity criteria are exceeded for short distances. Where velocity criteria are exceeded, velocities are predicted to remain under 5 fps, indicating that upstream passage by brook trout is potentially achievable for a majority of individuals. Channel depths throughout the flow path are expected to increase from existing to proposed conditions, improving the overall likelihood that brook trout could achieve passage through the Site.




Figure 43. 50% Daily Exceedance Flow Depth  
Light blue indicates shallower than target criteria (0-0.3 feet).  
Dark blue indicates deeper (0.3 feet +).






Figure 44. 50% Daily Exceedance Flow Velocity  
**Navy blue** indicates **within** target criteria (0-3 fps).  
**Purple** indicates **potential passage** per target criteria (3-5 fps).  
**Red** indicates **unlikely passage** per target criteria (5 fps +).




Figure 45. 50% Daily Exceedance Flow Depth




Figure 46. 50% Daily Exceedance Flow Velocity



### High Flow Passage

High flow conditions were assessed based on the flow path shown on **Figure 47** and **Figure 48**. Depth and velocity along this flow path are shown graphically on **Figure 49** and **Figure 50**, respectively. During high flow conditions, minimum depth criteria are predicted to be met across the full flow path, while target velocity criteria are exceeded for short distances. Where velocity criteria are exceeded, velocities are predicted to remain under 5 fps, indicating that upstream passage by brook trout is potentially achievable for a majority of individuals. Channel depths for portions of the flow path are expected to increase from existing to proposed conditions, generally improving the overall likelihood that brook trout could achieve passage through the Site.




Figure 47. 5% Daily Exceedance Flow Depth  
Light blue indicates shallower than target criteria (0-0.3 feet).  
Dark blue indicates deeper (0.3 feet +).




Figure 48. 5% Daily Exceedance Flow Velocity  
**Navy blue** indicates **within** target criteria (0-3 fps).  
**Purple** indicates **potential passage** per target criteria (3-5 fps).  
**Red** indicates **unlikely passage** per target criteria (5 fps +).




Figure 49. 5% Daily Exceedance Flow Depth






Figure 50. 5% Daily Exceedance Flow Velocity

## 4.4 Scour Assessment

The Feasibility Study identified the potential for increased scour risk upstream of the Dam along existing riverbanks, retaining walls, and the West Groton Bridge abutments. Increased water velocity was predicted to occur post-dam removal from 40 feet downstream of the Dam (Transect 5) to the upstream limits of the model, 650 feet upstream of the Dam (Transect 13), as shown on **Figure 51**. For this Pre-permit-Level Design phase, more detailed scour analyses were conducted for the modeled extent of the river. Scour potential was evaluated at the 100-year return interval flow, as is typical practice for designing to protect against scour along structures. Estimates of maximum scour depth are proportional to total water depth, so the 100-year flow offers a high (and therefore conservative) estimate of scour potential.




Figure 51. Existing (Left) and Proposed (Right) Velocity During 100-Year Flow

### 4.4.1 Retaining Wall and Embankment Scour Analysis

In order to assess the risk of scour along existing retaining walls and embankments following dam removal, HW utilized the HEC-23 methodology for determining “Scour with Flow Parallel to a Vertical Wall” and “Scour with Flow Impinging at an Angle on a Vertical Wall.”<sup>22</sup> HEC-23 uses inputs such as water depth, “angle of attack” between flow and the wall, and the Froude Number of the channel cross section in order to determine maximum **scour depth** along a retaining wall or embankment at a given point. Scour depth represents the theoretical depth at which native

<sup>22</sup> National Highway Institute, “Bridge Scour and Stream Instability Countermeasures: Experience, Selection, and Design Guidance – Third Edition, Volume 1,” Publication No. FHWA-NHI-09-1111, September 1009

river sediment (typically sand or finer) should be removed and replaced with hard armor (i.e., riprap) when in-stream infrastructure is constructed. The greater the scour depth predicted, the more scour potential at a proposed location along the river. If scour depth is predicted to decrease, proposed conditions are expected to have equal or less scour than existing conditions.

Two areas of potential concern were identified for this scour analysis: (1) the river-left retaining wall, north of RiverCourt Residences and (2) the western embankment of Groton Road where the Squannacook River first meets it (**Figure 52**).



Figure 52. Retaining Wall and Embankment Scour Assessment Areas

Estimates of maximum scour depth under the 100-year flow are presented below in **Table 7**. Scour depth at the retaining wall along RiverCourt Residences is expected to be lower under proposed conditions, indicating that bank armoring and stabilization are not necessary. Scour depth along the western embankment of Groton Road is also expected to decrease under proposed conditions, indicating that additional bank armoring and protections are not necessary. These decreases in scour depth are likely due to the predicted decreases in water elevations following dam removal. Water depth has a significant impact on predicted maximum scour depth, with deeper water correlating to higher scour depths.

Table 7. Maximum Scour Depth Along Study Points During 100-year Flow

Location	Existing Maximum Scour Depth (ft)	Proposed Maximum Scour Depth (ft)
Retaining Wall	19.17	14.68
Groton Road Embankment	29.21	20.89



#### 4.4.2 West Groton Bridge Scour Analysis

In order to assess the risk of scour at the West Groton Bridge, HW used the Bridge Scour extension of HEC-RAS, which utilizes the HEC-18 methodology to assess scour potential under bridges<sup>23</sup>. HEC-18 uses inputs such as flow rate, channel velocity, bridge geometry, and sediment particle diameter in order to estimate the potential **scour depth** of non-armored channels.

The HEC-18 analysis estimates scour depth in terms of three main components:

- **Contraction Scour:** scour caused by the narrowing of a channel's flow as it is restricted by passing through narrowed natural landforms or a bridge.
- **Local Pier Scour:** scour caused by the flow of water around piers. This may vary based on pier shape and dimensions.
- **Abutment Scour:** scour caused by the process of an abutment obstructing a channel's flow. This may be associated with contraction scour or may occur as a stream naturally widens or laterally migrates over time.

The sum of these components results in the total scour adjacent to a bridge element. For construction of a new bridge, total scour may be the depth to which river sediment should be removed and replaced with hard armor. In the case of an existing bridge like the West Groton Bridge, total scour offers a comparison point of the relative erosion potential under different flood flows. Based on field observations and sediment sampling conducted during previous project phases, the areas directly upstream and downstream of the West Groton Bridge are currently comprised primarily of brown poorly graded sand (median diameter (d<sub>50</sub>) = 0.5 mm).

The West Groton Bridge is comprised of left and right abutments and no piers. The abutments are vertical without wingwalls on the upstream or downstream sides, and no riprap was apparent during field observations. Using HEC-18 methodology within the HEC-RAS Bridge Scour extension, HW calculated the total scour depths shown in **Table 8**.

Table 8. Estimated Scour Depths

Condition	Existing Maximum Scour Depth (ft)	Proposed Maximum Scour Depth (ft)
Left Abutment	2.35	0
Channel Center	8.08	1.64
Right Abutment	0.89	0
Total	11.50	1.64

Based on the scour analysis, total scour depth is modeled to decrease at the West Groton Bridge under the design 100-year flow event following removal of the Dam. This is likely due to lower water elevations and narrower channel and flood extents predicted to occur following dam removal, which would reduce river flow width and, therefore, contact with the abutments. Since

<sup>23</sup> Federal Highway Administration, "Evaluating Scour at Bridges, Fifth Edition," Publication No. FHWA-HIF-12-003, April 2012


total scour depths are not expected to increase for higher flow events like the 100-year flow, additional scour protection measures are not needed to be installed at the West Groton Bridge to counteract any additional scour potential that may occur post dam removal. Despite this fact, additional scour protection is included at this location in our proposed design as an additional protective measure (see **Section 5.0** below).

#### 4.5 Estimated Change in Average Groundwater Elevation Post Dam Removal Well

In typical New England hydrogeological conditions, groundwater elevations surrounding rivers occur at levels close to, but slightly higher than, adjacent river water surface elevations. This slight gradient is what allows groundwater to flow into the river. Along dam-impounded stretches of river, that gradient is frequently inverted when the impounded river levels are high enough to create a localized reversed gradient from the river to adjacent groundwater. Downstream of dams, the naturalized gradient from groundwater to the river generally resumes. Groundwater fluctuations caused by changes in river levels are also generally most significant in immediate proximity to rivers and become progressively muted with increased distance from the river.

In order to evaluate the potential for impacts to private drinking water wells from dam removal at the Site, HW first evaluated the likely potential for the presence of private drinking water wells in the vicinity of the Dam impoundment, and then evaluated how far away from the impoundment significant groundwater level declines would be likely to occur relative to the distance of residences with the potential to be served by private drinking water wells.

As noted in **Section 2.4.4**, Groton residents abutting the impoundment have access to town water, while Shirley residents near the impoundment depend on private drinking water wells on their properties. Based on mapping from the EOEEA, private wells are located as close as 100 feet to the impoundment, with well depths generally between 85 and 705 feet. With bedrock encountered generally between 25-60 feet below ground surface, the private wells along the Shirley side of the impoundment appear to be bedrock wells, which would likely be unaffected by potential small groundwater level reductions for the surficial aquifer overlying the bedrock in which the private wells are located. **Figure 53**, below, identifies various wells within the vicinity of the impoundment.



**Squannacook River Dam**  
Shirley and Groton, MA

**Well Locations**  
Squannacook River

Figure 53. Well Locations in the Vicinity of the Squannacook River Dam Impoundment



HW calculated the distance-variable change in average groundwater elevation likely to occur as a result of the proposed dam removal. To do this, HW utilized standard pumping test evaluation techniques – specifically, the Theis distance drawdown method. This approach requires first conceptualizing the anticipated river level decline at the impoundment because of dam removal as if the river level decline were caused by a conceptual pumping well located adjacent to the impoundment and using the Theis method to calculate the conceptual pumping rate necessary to produce that anticipated river level decline (i.e., the conceptual drawdown). Next, that conceptual pumping rate is incorporated into the same Theis method equations to solve for the groundwater drawdown that would occur in the aquifer at specified distances from the impoundment under the conceptualized pumping withdrawal condition.

To estimate the conceptual groundwater drawdown associated with the water level reduction in the post dam removal impoundment, HW used an online calculator version of the Theis methodology (New Mexico Office of the State Engineer, 2017.

<https://www.ose.nm.gov/Hydrology/Theis/index.html>). Input factors for the Theis method estimation are as follows:

- Hydraulic conductivity (or “K”) is a factor that defines the ability of the aquifer materials to transmit water. It is generally associated with permeability, but is presented in units of velocity (e.g., feet per day), even though it technically does not define the groundwater velocity of any given location. Higher values of K indicate higher capacity to transmit water. K values were estimated for sand and gravel deposits which predominantly make up the surficial geology that exists around the Squannacook River. These values were estimated based on local data obtained from EOEEA well completion reports and from surficial geological mapping obtained from MassGIS.
- Aquifer thickness (“b”) was estimated based on the EOEEA well database of groundwater wells nearby.
- Transmissivity (“T”) is the product of K and b.
- Storage coefficient (“S”) represents the percentage of unit aquifer volume that is open pore spaces between aquifer sediment grains available to store and transmit water.
- Pumping rate in gallons per minute (gpm).
- Distance in feet from the river to nearby residences and potential wells for which drawdown is calculated.
- The modeled average drawdown behind the Dam site post dam removal as predicted by the H&H model.

**Table 9** lists the range of input factor values utilized in our assessment.

**Table 9. Input Factors for Theis Drawdown Calculations**

Factor	Min.	Likely	Max.	Comments
<b>K Sand and Gravel</b>	37 ft/day	214 ft/day	675 ft/day	From MassGIS
<b>b</b>	15 ft	20 ft	35 ft	From well database
<b>T Sand and Gravel</b>	555 ft <sup>2</sup> /day	4,280 ft <sup>2</sup> /day	23,625 ft <sup>2</sup> /day	= K * b
<b>S aquifer</b>	0.1	0.2	0.25	Estimate for Unconfined Aquifer
<b>S river</b>	0.99	0.99	0.99	Open water, high S
<b>Time</b>	30 days	60 days	120 days	For avg. steady state
<b>Distance</b>	50 ft	100 ft	1,000 ft	Residences affected nearby

Based on the H&H model, an average water level reduction of 10.11 feet was predicted to occur in the impoundment immediately upstream of the Dam during median flow conditions post dam removal. This value was used as the simulated drawdown for the conceptual groundwater well withdrawal assessment rate.

Based on MassGIS mapping, surficial geology within 1,500 feet of the Squannacook River at the Site consists of sand and gravel. Therefore, aquifer properties associated with sand and gravel were used in the Theis method conceptual drawdown calculations (**Table 9**). The hypothetical groundwater pumping rate necessary to create the 10.11 feet of “conceptual drawdown” in the impoundment is approximately 213 gpm (**Table 10**).

Using the range of calculated conceptual pumping rate and the other **Table 9** values, HW used the same Theis method calculator in reverse (i.e., we solved for drawdown at variable distance based on the previously estimated pumping rate) to estimate the potential groundwater drawdown at 50 feet, 100 feet, and 1,000 feet away from the impoundment. Those evaluation distances were selected to bracket the distances to the closest residences (estimated to be at least 100 feet from the impoundment, based on MassGIS mapping).

**Table 10. Results for Theis Drawdown Calculations**

Factor	Min. Combo of Factors	Likely Combo of Factors	Max. Combo of Factors
<b>Conceptual Pumping Rate to Produce Dam-Out River Drawdown</b>	34.75 gpm	212.75 gpm	994.46 gpm
<b>Avg. Groundwater Decline at Residences from Simulated Dam-Out River Drawdown</b>	3.49 ft	4.32 ft	5.06 ft

As shown in **Table 10**, the potential groundwater drawdown that may occur at the nearest residence following dam removal is approximately 3.5-5.1 feet. Based upon the publicly available well completion reports, the private wells in Shirley were completed at least 85 feet below grade in bedrock (and generally hundreds of feet deeper) and have a depth to static water level of 40 feet below grade or less. With saturated material at least 45 feet thick, even the moderate groundwater level declines estimated to occur because of the proposed dam

removal (less than 10% of the total thickness of saturated material, at most) are unlikely to impact the actual performance of any private wells that exist in this proximity.

Further to this point, the groundwater inputs to the private wells in Shirley are derived from the bedrock stratum underlying the saturated material of the aquifer. While water in the bedrock stratum is ultimately derived from downward percolation of water from the overlying aquifer, the area of overlying aquifer contributing water to any given bedrock well can be vast depending on the network of interconnected fractures transmitting water within the bedrock aquifer. Small changes in water elevation for the overlying surficial aquifer are unlikely to affect the yield of wells completed deep in the underlying bedrock with water conveyed by numerous fractures.

**Figure 54** visualizes the potential groundwater drawdown relative to well depths and depth to bedrock. The graphic portrays a conservative scenario in which the greatest expected drawdown occurs at the shallowest well with the thinnest saturated bedrock layer.

Existing Conditions		Proposed Conditions	
	Feet bgs		Feet bgs
Surface	0	Surface	0
	5		5
	10		10
	15		15
	20		20
	25		25
	30		30
	35		35
Water table	40		40
	45	Water table	45
	50		50
Deepest Start of Bedrock	55	Deepest Start of Bedrock	55
	60		60
	65		65
	70		70
	75		75
Shallowest Well Bottom	80	Shallowest Well Bottom	80
	85		85

Figure 54. Change to Groundwater Elevations Relative to Well and Bedrock Depths

Note that some combinations of factors that produce a high simulated pumping rate (i.e., high T and low time to steady state) are inverted from those to produce maximum drawdown distance (i.e., low T and longer pumping duration). Therefore, the maximum and minimum factor combinations are not the absolute maximums and minimums, but the maximum and minimum combinations of factors that might reasonably occur.

Also note that the groundwater impact evaluations discussed above are likely conservative overestimates of the potential groundwater level declines surrounding the Dam site resulting



from estimated post dam removal river level changes. While the approach of simulating the potential water surface elevation changes as a well withdrawal allows for the use of pumping test analytical equations to estimate drawdown, it is an oversimplification of actual site conditions. Natural climatic and hydrologic conditions continuously vary for river level and groundwater level at the site and would continue to do so under potential dam-out conditions. Therefore, the post dam removal river levels are unlikely to remain 10.11 feet lower than current impoundment water levels for the multiple months' time period simulated in the steady state analysis described above. Altogether, the analysis described above provides a reasonable maximum range of potential groundwater level changes adjacent to the Dam.

## 5.0 PRELIMINARY DAM REMOVAL DESIGN

Pre-permit Level (approximately 60%) Design plans and cost estimate are included herein as **Attachments C and D**. The preliminary design is presented as a 11-sheet plan that includes existing conditions, construction access, site preparation, demolition plan, site layout, restoration and stabilization plan, and typical details. Plan view and perspective renderings of the proposed conditions are included as **Attachment E**.

The Pre-permit-Level Design was based on publicly available GIS data, information acquired during site visits, and conversations with project partners. This coordination informed the conditions that the design would need to accommodate. The following are key components of the Pre-permit-Level design:

- Construction access would be through the RiverCourt Residences parking lot. A stabilized construction entrance will be required to minimize sediment tracking out of the construction zone and erosion of the existing areas. Parking lot features will be protected in place during construction or removed and reset as necessary. Any damage to parking lot features will be repaired at the end of construction.
- Construction equipment and materials staging will occur adjacent to the site entrance within the RiverCourt Residences parking lot as well as the lot at the corner of Route 225 and Townsend Road (Carol G. Wheeler Park).
- Dam removal is recommended to occur during the driest season of the year (August-October). The Dam's low level outlet will be used to lower the impoundment and enable work to occur "in the dry." Additional dewatering activities may be approved as appropriate. The Dam will be demolished incrementally, such that impoundment water levels are able to lower gradually and outflow velocities from the impoundment are minimized.
- Dam operators at the Hollingsworth & Vose Company will be coordinated with to ensure that maximum water is retained upstream during the dam removal and that no upstream dam releases occur throughout the duration of construction.
- The potential elevation of the upstream stream channel hard bottom post-dam removal is uncertain. To the extent practicable, the Dam should be demolished until the entire concrete structure and any footing materials have been removed from the stream channel. Consideration should also be given to creating a low-flow channel or channels where deeper water can concentrate during low flow conditions to facilitate fish passage.
- The concrete footings at the raceway and concrete splashpads should be left in place adjacent to retaining walls, in order to protect their structural stability.
- The river left sluice wall – adjacent to the RiverCourt Residences retaining wall – will be left in place, and the area between the sluice wall and retaining wall will be filled with earth and soil and planted with native vegetation to provide structural stability.

Note that, as an alternative to filling the area between the sluice wall and the river left retaining wall, the Town could conduct an evaluation of the retaining wall's structural stability to determine whether complete removal of the sluice wall and installation of

constructed banks and or other bank stabilization practices is a feasible alternative that would not compromise the stability of the retaining wall for RiverCourt Residences. A structural engineer is needed to perform this evaluation.

- Once the Dam is fully demolished, the banks in the vicinity of the Dam will be stabilized using constructed banks made from stone redistributed from the Dam demolition. Impounded coarse material will be reused as possible and otherwise will be allowed to passively transport.
- At elevations above the predicted top of banks, plantable walls (geotextile casings filled with soil that are designed with structural strength) will be installed that will provide earth retainage while also vegetating the banks.
- Provided that MassDEP concurs during the permitting process, most sediment is proposed to be managed through instream management techniques, thereby allowing accumulated materials to naturally transport and redistribute to sediment-starved areas downstream of the Dam. Note that some sediment will be manually redistributed to construct banks.



## 6.0 DISCUSSION

### 6.1 Potential Ecological Impacts and Benefits

An immediate impact of removing the Dam would be the release of mobile sediment that has accumulated behind the structure. Downstream sediment transport is a natural riverine process, which has been altered by the presence of the Dam. Long-term sediment transport is expected to be negligible, and it is expected that a new equilibrium will be reached within one to two years, pending the types of storms and flow events experienced post dam removal.

The impact on aquatic species depends on the concentration, exposure time, and time of year. Sessile communities are more susceptible to sediment impacts than fish (which can move upstream or downstream of the impact zone and thus avoid many of the negative impacts). Coordination with the Massachusetts Division of Fisheries and Wildlife (Mass Wildlife) Natural Heritage Endangered Species Program (NHESP) will need to occur prior to dam removal to avoid impacting any state listed sessile species, such as Creeper mussels. This may require a sediment monitoring and rare species relocation plan, if applicable. Timing the dam removal so that sediment is released well ahead of fish migration periods (likely October-November) will help to minimize the impacts to migratory fish such as brook trout. Final determination of fish migration periods will need to be verified with Mass Wildlife during the project permitting phase. It is recommended that potential impacts associated with deposition downstream of the Dam are monitored following dam removal. As discussed above, the amount of sediment that is expected to be mobilized relative to the size of the river will not be significant.

The above-mentioned potential minimal and temporary impacts can be easily mitigated and are largely outweighed by the significant and long-term ecological benefits resulting from dam removal. For most small dams, removal results in the restoration of a river's natural water temperature regime along the former impoundment area and downstream of the Dam.<sup>24</sup>

Removal of a dam will encourage active flow, help reduce water temperatures, and support higher dissolved oxygen concentrations, making the part of the river currently upstream of the Dam more hospitable to cold water species. As a designated coldwater fish resource (CFR), the potential of lowering water temperatures and improving water quality through dam removal is especially valuable. Removal of the Dam will also allow free movement of motile aquatic and terrestrial organisms upstream and downstream.

In general, following dam removal, overall lotic macroinvertebrate abundance and diversity tends to increase relative to that of impoundment communities as a new channel is formed and

---

<sup>24</sup> Pawloski, J.T. and Cook, L.A., 1993, Sallings Dam drawdown and removal. In *Unpublished manuscript presented at The Midwest Region Technical Seminar on Removal of Dams, Association of State Dam Safety Officials* (Vol. 30), September 1993.

more heterogenous in-channel habitat becomes available for both invertebrates and fish.<sup>25, 26, 27</sup> Such a change is anticipated following removal of the Dam. Restoration of sediment continuity through this reach would be beneficial over the long term, not only for restoring habitat locally, but also for replenishment of sediment to downstream habitats and floodplains.

Model results indicate that predicted water surface profiles and flow velocities through the former Dam location may sometimes be unfavorable to fish passage, although maximum predicted velocities post-removal are not expected to exceed those that currently occur in the reach downstream of the Dam, and passage may be achievable for some individuals. Additionally, some modeled lower flow events resulted in water column depths that may become too shallow for brook trout passage. HW recommends that during construction, care be given to create a suitable low-flow channel in the vicinity of the former concrete splashpads where flow can concentrate to accommodate fish passage.

## 6.2 Potential Impacts and Benefits for Flooding, Infrastructure, and Recreation

The results of the 2D unsteady modeling indicate that downstream flood elevations are expected to remain equal to existing flood elevations as a result of dam removal. Further, dam removal eliminates a significant hazard that currently exists in the event of dam failure. The Inspection Report completed by Haley & Aldrich, Inc. in 2023 states that failure of the Dam “may cause loss of life and temporary flooding to the lowest level of the mill building.” H&H modeling and examination of aerial photography and available topographic data indicates that structures surrounding the Dam impoundment are generally outside of the current flood plain extents. Infrastructure adjacent to the floodplain is limited to the West Groton Bridge, RiverCourt Residences, an abandoned structure on the North side of Route 225, and the Carver’s Guild Mirror Shop building. Hydrologic and hydraulic analysis under existing conditions indicates that none of these structures are currently at risk of inundation during flood flows with return intervals of 100 years or less. Still, removal of the Dam is expected to reduce impoundment water levels, further reducing the minimal risk of flooding to these structures.

Existing infrastructure along the river channel including the West Groton Bridge and the retaining walls adjacent to the river are predicted to have reduced risk of scour as a result of the narrowing of the river channel predicted to occur upstream of the current location of the Dam subsequent to removal. Despite the modeled improvement of scour potential, riprap armoring and bank construction are conservatively included in the proposed design to further mitigate potential scour risk. Controlled dam removal also eliminates the potential scour concerns posed by sudden dam failure were the dam to remain in place and fail at a later date. The sudden

---

<sup>25</sup> Bushaw-Newton, K.L., Hart, D.D., Pizzuto, J.E., Thomson, J.R., Egan, J., Ashley, J.T., Johnson, T.E., Horwitz, R.J., Keeley, M., Lawrence, J., Charles, D., Gatenby, C., Kreeger, D.A., Nightengale, T., Thomas, R.L. and D.J. Velinsky. 2002. An integrative approach towards understanding ecological responses to dam removal: The Manatawny Creek Study. *J. Am. Wat. Res. Assoc.* 38(6) 1581-1599.

<sup>26</sup> Calaman, H. and C.P. Ferreri. 2002. *Effects of dam removal on benthic macroinvertebrate diversity*. Pennsylvania State University School of Forest Resources.

<sup>27</sup> Pollard, A.I. and Reed-Anderson, T. 2001. Benthic invertebrate community change following dam removal in a small Wisconsin stream. *Bulletin of the North American Benthological Society* 18: 173.

release of water in the event of dam failure would result in deep, fast-moving flow with a greater risk of scour and undercutting at the West Groton Bridge.

Downstream of the Dam, velocities are not predicted to increase and water levels are not predicted to change, so scour risk is not predicted to increase along the retaining wall adjacent to the former mill building. The former mill building and current structure of RiverCourt Residences is not anticipated to be impacted by dam removal.

Recreation along the Squannacook River currently includes paddling (generally downstream of the Dam<sup>28</sup>) and ice fishing (on Thompson Mill Pond), as well as fly fishing (generally for brook trout, bass, pickerel, and blue gills; access is available from a boat launch just west of the West Groton Bridge and upstream of the Hollingsworth and Vose Dam<sup>29</sup>). Paddling downstream of the Dam is not expected to be affected by dam removal, since velocities and water depths are not modeled to change post-removal. Removal of the Dam would restore continuity of paddling along a portion of the Squannacook River, although conditions are expected to shift from calm, lake-like paddling to faster, river-like paddling. Restoration of river continuity and potentially aquatic passage would be beneficial to brook trout populations and range, potentially improving fly fishing opportunities. Ice fishing would be less feasible at the Thompson Mill Pond as a result of dam removal.

### 6.3 Environmental Permitting

A detailed permitting evaluation was not conducted as part of this project. However, based on experience, **Table 11** below lists the environmental permits that are anticipated to be required for this project. Actual permitting may vary depending on funding sources and other factors to be determined in subsequent project phases. It should also be noted that this project is likely to qualify as an ecological restoration project and therefore may be exempt from MEPA review.

---

<sup>28</sup> Brettal, Squannacook River in Massachusetts, <https://paddling.com/paddle/trips/squannacook-river-in-massachusetts>

<sup>29</sup> Tango, J., (2016). Overview: the Squannacook River, <https://blogflyfish.com/2016/03/overview-squannacook-river.html>



Table 11. Potential Permitting Requirements

<b>Permits, Reviews, or Authorizations Required</b>	
<b>Local</b>	
Groton Conservation Commission Restoration Order of Conditions	
Shirley Conservation Commission Restoration Order of Conditions	
<b>State</b>	
Massachusetts Environmental Policy Act (MEPA) Review / Secretary's Certificate	
Massachusetts Dept. of Environmental Protection (DEP) 401 Water Quality Certification	
Massachusetts Dept. of Environmental Protection (DEP) Chapter 91 License	
Massachusetts Historical Commission (MHC) Comment	
Natural Heritage and Endangered Species Program Comment	
Massachusetts Division of Fish and Wildlife Coordination Regarding a Potential Time of Year Restriction	
<b>Federal</b>	
United States Army Corps of Engineers (USACE) Section 404 / Section 10 Permit	

## 7.0 ESTIMATED PROJECT COSTS AND FUTURE PHASING

If the findings of this study result in approval for advancing the project, the recommended next step is to incorporate public input into the proposed design and advance to permitting. The overall timeline for permitting is typically 1 year, and construction may occur in the following 1-2 years after receiving permitting approval.

Approximate pre-permit-level project costs are provided in **Table 12** below. A detailed concept-level opinion of probable construction cost is included as **Attachment D**. As is typical, construction costs are estimated to be the largest overall portion of future project phases. Primary contributors to the estimated construction cost include dewatering and access costs, bank stabilization and restoration, and excavation of the reinforced concrete structures of the Dam, sluice wall, and concrete splashpads. Estimated costs utilize the most recently available median unit bid prices provided by the Massachusetts Department of Transportation (MassDOT).

Table 12. Pre-Permit-Level Project Costs and Future Phases

Project Phase	Approximate Cost Estimate
Permit Level Design	\$50 – 90K
75% Design	
Permitting	
Final Design	\$30– 50K
Additional Field Work and Analysis	
100% Design	
Specifications	
Construction Administration	\$30 – 50K
Bid Documents	
Bidding Assistance	
Construction Inspections & Submittal Reviews	
As-built Survey and Plans	
Construction ( <b>Attachment D</b> )	\$1.1 – 1.4M
Post-Construction Monitoring	\$25 – 50K
Water Levels	
Habitat/Ecology	
<b>Total</b>	<b>\$1.2 – 1.7M</b>



# ATTACHMENT A

---

## *Sediment Quality Laboratory Results*

# DER Sediment Quality Results Table

Parameters	Units	"Natural Soil" Background	"Urban Soil" Background	Ecological Thresholds (aquatic)		Human Exposure Thresholds (upland/floodplain) <i>(for comparison)</i>	Downstream Samples Results	Upstream Samples	Thompson Mill Pond Center Results	Thompson Mill Pond Edge Results
				Freshwater		Method 1 Soil Standards S-1/GW-1	Groton DS	Groton US		
				TEC/TEL	PEC/PEL		1/31/2024	1/31/2024	11/19/2024	11/19/2024
Metals (mg/kg)										
Arsenic	mg/kg (ppm)	20	20	9.79	33.0	20	13.5	6.17	12.3	10.7
Cadmium	mg/kg (ppm)	2	3	0.99	4.98	80	0.44	0.17	0.32	0.12
Chromium (TOTAL)	mg/kg (ppm)	30	40	43.4	111	100	6.24	5.7	14.2	8.37
Chromium III	mg/kg (ppm)	30	40			1,000	-	-	-	-
Chromium VI (Hexavalent)	mg/kg (ppm)	30	40			100	-	-	-	-
Copper	mg/kg (ppm)	40	200	31.6	149		6	6.46	30.2	8.34
Lead	mg/kg (ppm)	100	600	35.8	128	200	13.5	31.5	71.9	17.7
Mercury	mg/kg (ppm)	0	1	0.18	1.06	20	0.029	0.024	0.303	0.074
Nickel	mg/kg (ppm)	20	30	22.7	48.6	700	5.87	7.01	10	6.42
Zinc	mg/kg (ppm)	100	300	121	459	1,000	35.8	22.9	104	43.6
PAHs (ug/kg)										
Acenaphthene	ug/kg (ppb)	500	2,000	6.71	88.9	4,000	5.5	44	9	9
Acenaphthylene	ug/kg (ppb)	500	1,000	5.87	128	2,000	5.5	5	9	9
Anthracene	ug/kg (ppb)	1,000	4,000	57.2	845	1,000,000	5.5	179	9	9
Benzo(a)anthracene	ug/kg (ppb)	2,000	9,000	108	1,050	20,000	14	361	71	9
Benzo(a)pyrene	ug/kg (ppb)	2,000	7,000	150	1,450	2,000	15	419	56	9
Benzo(b)fluoranthene	ug/kg (ppb)	2,000	8,000			20,000	16	340	58	9
Benzo(g,h,i)perylene	ug/kg (ppb)	1,000	3,000			1,000,000	12	291	51	9
Benzo(k)fluoranthene	ug/kg (ppb)	1,000	4,000			200,000	13	290	51	9
Chrysene	ug/kg (ppb)	2,000	7,000	166	1,290	200,000	17	360	90	9
Dibenzo(a,h)anthracene	ug/kg (ppb)	500	1,000	33.0	135	2,000	5.5	118	26	9
Fluoranthene	ug/kg (ppb)	4,000	10,000	423	2,230	1,000,000	31	1010	124	9
Fluorene	ug/kg (ppb)	1,000	2,000	77.4	536	1,000,000	5.5	62	9	9
Indeno(1,2,3-cd)pyrene	ug/kg (ppb)	1,000	3,000			20,000	5.5	233	39	9
2-Methylnaphthalene	ug/kg (ppb)	500	1,000			700	5.5	11	9	9
Naphthalene	ug/kg (ppb)	500	1,000	176	561	4,000	5.5	16	9	9
Phenanthrene	ug/kg (ppb)	3,000	20,000	204	1,170	10,000	20	677	69	19
Pyrene	ug/kg (ppb)	4,000	20,000	195	1,520	1,000,000	28	813	137	9
Total PAHs	ug/kg (ppb)	26,500	103,000	1,610	22,800		210	5229	826	163

# DER Sediment Quality Results Table

Parameters	Units	"Natural Soil" Background	"Urban Soil" Background	Ecological Thresholds (aquatic)		Human Exposure Thresholds (upland/floodplain) (for comparison) Method 1 Soil Standards S-1/GW-1	Downstream Samples	Upstream	Thompson Mill Pond	Thompson Mill Pond
							Results	Samples	Center Results	Edge Results
				Freshwater			Groton DS	Groton US		
				TEC/TEL	PEC/PEL		1/31/2024	1/31/2024	11/19/2024	11/19/2024
<b>PCBs (mg/kg or ppm)</b>										
Total PCBs (mg/kg)	mg/kg (ppm)			0.0598	0.676	1.00	0.003755	0.00709	0.00815	0.00917
PCB-8							0.000185	0.000175	0.000355	0.00032
PCB-18							0.000185	0.000175	0.000355	0.00032
PCB-28							0.000185	0.000175	0.000355	0.00032
PCB-44							0.000185	0.000175	0.000355	0.00032
PCB-52							0.000185	0.000175	0.00144	0.00032
PCB-66							0.000185	0.000175	0.00103	0.00032
PCB-77							-	-	-	-
PCB-101							0.000185	0.00061	0.000355	0.00099
PCB-105							0.000185	0.000175	0.000355	0.00032
PCB-118							0.000185	0.000175	0.000355	0.00085
PCB-128							0.000185	0.000175	0.000355	0.00032
PCB-138							0.00061	0.00111	0.000355	0.00146
PCB-153							0.000185	0.00085	0.000355	0.00139
PCB-170							0.000185	0.0007	0.000355	0.00032
PCB-180							0.000185	0.00117	0.000355	0.00032
PCB-187							0.000185	0.00055	0.000355	0.00032
Hexachlorobenzene	ug/kg (ppb)					700				
Methoxychlor	ug/kg (ppb)					300,000				
Toxaphene	ug/kg (ppb)			0.1						
<b>TPH and EPH (mg/kg or ppm)</b>										
TPH	mg/kg (ppm)					1,000	-	-	-	-
C9-C18 Aliphatic Hydrocarbons	mg/kg (ppm)					1,000	10.4	9.75	11.05	11.5
C19-C36 Aliphatic Hydrocarbons	mg/kg (ppm)					3,000	10.4	9.75	246	11.5
C11-C22 Aromatic Hydrocarbons	mg/kg (ppm)					1,000	10.5	9.45	84.3	11.7
<b>Physical Characteristics</b>										
Total Organic Carbon (%)	%						2.87	1.24	3.58	2.72
Percent Water (%)	%						27	23	62.00	58.00
Sieve No. 4 (% passing)	% passing						90.1	94.5	100.00	100.00
Sieve No. 10 (% passing)	% passing						85.5	92.1	99.30	99.00
Sieve No. 40 (% passing)	% passing						52.7	39.2	93.40	93.80
Sieve No. 60 (% passing)	% passing						30.8	15.9	78.80	79.00
Sieve No. 200 (% passing)	% passing						4.6	2.8	37.30	29.40



# DER Sediment Quality Results Table

Parameters	Units	"Natural Soil" Background	"Urban Soil" Background	Ecological Thresholds (aquatic)		Human Exposure Thresholds (upland/floodplain)	Downstream Samples	Upstream Samples	Thompson Mill Pond Center Results	Thompson Mill Pond Edge Results
				Freshwater		Method 1 Soil Standards S-1/GW-1	Results			
				TEC/TEL	PEC/PEL		Groton DS	Groton US		
							1/31/2024	1/31/2024	11/19/2024	11/19/2024
<b>Volatile Organic Compounds (VOCs)</b>										
Acetone	mg/kg (ppm)					6.00	0.01385	0.0128	0.0467	0.04455
Acrylonitrile							-	-	-	-
Amyl Methyl Ether (TAME)							0.0014	0.0013	0.00465	0.00445
Benzene	mg/kg (ppm)					2.00	0.0014	0.0013	0.00465	0.00445
Bromobenzene							0.0014	0.0013	0.00465	0.00445
Bromochloromethane							0.0014	0.0013	0.00465	0.00445
Bromodichloromethane	mg/kg (ppm)					0.10	0.0014	0.0013	0.00465	0.00445
Bromoform	mg/kg (ppm)					0.10	0.0014	0.0013	0.00465	0.00445
Bromomethane	mg/kg (ppm)					0.50	0.00275	0.00255	0.00935	0.0089
sec-Butylbenzene							0.0014	0.0013	0.00465	0.00445
n-Butylbenzene							0.0014	0.0013	0.00465	0.00445
tert-Butylbenzene							0.0014	0.0013	0.00465	0.00445
Carbon Disulfide							0.0014	0.0013	0.00465	0.00445
Carbon Tetrachloride	mg/kg (ppm)					10.00	0.0014	0.0013	0.00465	0.00445
Chlorobenzene	mg/kg (ppm)					1.00	0.0014	0.0013	0.00465	0.00445
Chlorodibromomethane							0.0014	0.0013	0.00465	0.00445
Chloroethane							0.00275	0.00255	0.00935	0.0089
Chloroform	mg/kg (ppm)					0.40	0.0014	0.0013	0.00465	0.00445
Chloromethane							0.00275	0.00255	0.00935	0.0089
Chlorotoluene, 2-							0.0014	0.0013	0.00465	0.00445
Chlorotoluene, 4-							0.0014	0.0013	0.00465	0.00445
1,2-Dibromo-3-chloropropane PP							0.0014	0.0013	0.00465	0.00445
Dibromoethane, 1,2- (EDB)							0.0014	0.0013	0.00465	0.00445
Dibromomethane							0.0014	0.0013	0.00465	0.00445
Dichlorobenzene, 1,3- (m-DCB)	mg/kg (ppm)					3.00	0.0014	0.0013	0.00465	0.00445
Dichlorobenzene, 1,2- (o-DCB)	mg/kg (ppm)					9.00	0.0014	0.0013	0.00465	0.00445
Dichlorobenzene, 1,4- (p-DCB)	mg/kg (ppm)					0.70	0.0014	0.0013	0.00465	0.00445
Dichlorodifluoromethane (Freon 12)							0.00275	0.00255	0.00935	0.0089
Dichloroethane, 1,1-	mg/kg (ppm)					0.40	0.0014	0.0013	0.00465	0.00445
Dichloroethane, 1,2-	mg/kg (ppm)					0.10	0.0014	0.0013	0.00465	0.00445
Dichloroethylene, 1,1-	mg/kg (ppm)					3.00	0.0014	0.0013	0.00465	0.00445
Dichloroethylene, cis-1,2	mg/kg (ppm)					0.30	0.0014	0.0013	0.00465	0.00445
Dichloroethylene, trans-1,2	mg/kg (ppm)					1.00	0.0014	0.0013	0.00465	0.00445
Dichloropropane, 1,2-	mg/kg (ppm)					0.10	0.0014	0.0013	0.00465	0.00445
Dichloropropane, 1,3-	mg/kg (ppm)						0.0014	0.0013	0.00465	0.00445
Dichloropropane, 2,2-							0.0014	0.0013	0.00465	0.00445
Dichloropropene, 1,1-							0.0014	0.0013	0.00465	0.00445
Dichloropropene, cis-1,3-3							0.0014	0.0013	0.00465	0.00445
Dichloropropene, trans-1,3- 3							0.0014	0.0013	0.00465	0.00445
Diethyl Ether OXY							0.0014	0.0013	0.00465	0.00445
Diisopropyl Ether (DIPE) OXY							0.0014	0.0013	0.00465	0.00445

## DER Sediment Quality Results Table

Dioxane, 1,4- PP, 1	mg/kg (ppm)					0.20	0.0277	0.02565	0.0935	0.089
Ethylbenzene	mg/kg (ppm)					40.00	0.0014	0.0013	0.00465	0.00445
Hexachlorobutadiene	mg/kg (ppm)					30.00	0.0014	0.0013	0.00465	0.00445
Hexanone (MNBK), 2- PP							0.01385	0.0128	0.0467	0.04455
Isopropylbenzene (Cumene)2							0.0014	0.0013	0.00465	0.00445
Isopropyltoluene, p-2							0.0014	0.0013	0.00465	0.00445
m+p Xylene							0.00275	0.00255	0.00935	0.0089
Methyl Acetate							-	-	-	-
Methyl Cyclohexane							-	-	-	-
Methyl Isobutyl Ketone (MIBK) PP	mg/kg (ppm)					4.00	0.01385	0.0128	0.0467	0.04455
Methyl Tertiary Butyl Ether (MTBE) OXY	mg/kg (ppm)					0.40	0.0014	0.0013	0.00465	0.00445
Methylene Chloride							0.0069	0.0064	0.02335	0.02225
Naphthalene	mg/kg (ppm)	500	1,000	176.00	561.00	4,000.00	0.0014	0.0013	0.00465	0.00445
2-Nitampme (MEK)							0.01385	0.0128	0.0467	0.04455
o-Xylene							0.0014	0.0013	0.00465	0.00445
Propylbenzene, n-2							0.0014	0.0013	0.00465	0.00445
Styrene	mg/kg (ppm)					3.00	0.0014	0.0013	0.00465	0.00445
tert-Butyl Alcohol (TBA)							-	-	-	-
tert-Butyl Ethyl Ether (TBEE)							0.0014	0.0013	0.00465	0.00445
Tetrachloroethane, 1,1,1,2-	mg/kg (ppm)					0.10	0.0014	0.0013	0.00465	0.00445
Tetrachloroethane, 1,1,2,2-	mg/kg (ppm)					0.01	0.0014	0.0013	0.00465	0.00445
Tetrachloroethylene	mg/kg (ppm)					1.00	0.0014	0.0013	0.00465	0.00445
Tetrahydrofuran (THF)							0.00555	0.00515	0.0187	0.0178
Toluene	mg/kg (ppm)					30.00	0.0014	0.0013	0.00465	0.00445
trans-1,4 Dichloro-2-butene							-	-	-	-
1,1,2-Trichloro-1,2,2-trifluoroethane (Freon 113)							-	-	-	-
Trichlorobenzene, 1,2,4-	mg/kg (ppm)					2.00	0.0014	0.0013	0.00465	0.00445
Trichlorobenzene, 1,2,3-							0.0014	0.0013	0.00465	0.00445
1,3,5-Trichlorobenzene							-	-	-	-
Trichloroethane, 1,1,1-	mg/kg (ppm)					30.00	0.0014	0.0013	0.00465	0.00445
Trichloroethane, 1,1,2-	mg/kg (ppm)					0.10	0.0014	0.0013	0.00465	0.00445
Trichloroethylene (TCE)	mg/kg (ppm)					0.30	0.0014	0.0013	0.00465	0.00445
Trichlorofluoromethane (Freon 11)							0.0014	0.0013	0.00465	0.00445
Trichloropropane, 1,2,3-							0.0014	0.0013	0.00465	0.00445
1,2,4-Trimethylbenzene							0.0014	0.0013	0.00465	0.00445
1,3,5-Trimethylbenzene							0.0014	0.0013	0.00465	0.00445
Vinyl Chloride	mg/kg (ppm)					0.30	0.00275	0.00255	0.00935	0.0089
Xylenes	mg/kg (ppm)					400	0.00275	0.00255	0.00935	0.0089

# DER Sediment Quality Results Table

Parameters	Units	"Natural Soil" Background	"Urban Soil" Background	Ecological Thresholds (aquatic)		Human Exposure Thresholds	Downstream Samples	Upstream Samples	Thompson Mill Pond	Thompson Mill Pond
				Freshwater		(upland/floodplain)	Results		Center Results	Edge Results
				TEC/TEL	PEC/PEL	(for comparison)	Groton DS	Groton US		
					Method 1 Soil Standards	S-1/GW-1	1/31/2024	1/31/2024	11/19/2024	11/19/2024
Other Analyses - Asbestos										
Chrysolite	% of sample						-	-	0.00	0.00
Amosite	% of sample						-	-	0.00	0.00
Crocidolite	% of sample						-	-	0.00	0.00
Actinolite	% of sample						-	-	0.00	0.00
Tremolite	% of sample						-	-	0.00	0.00
Anthophyllite	% of sample						-	-	0.00	0.00
Fiberglass	% of sample						-	-	0.00	0.00
Mineral Wool	% of sample						-	-	5.00	2.00
Cellulose	% of sample						-	-	5.00	2.00
Hair	% of sample						-	-	0.00	0.00
Synthetic	% of sample						-	-	0.00	0.00
Other	% of sample						-	-	0.00	0.00
Non-Fibrous Materials	% of sample						-	-	90.00	96.00

*CERTIFICATE OF ANALYSIS*

Jonas Procton  
Horsley & Witten  
90 Route 6A  
Sandwich, MA 02563

**RE: Squannacook River Dam (23144B)**  
**ESS Laboratory Work Order Number: 24K0950**

This signed Certificate of Analysis is our approved release of your analytical results. These results are only representative of sample aliquots received at the laboratory. ESS Laboratory expects its clients to follow all regulatory sampling guidelines. Beginning with this page, the entire report has been paginated. This report should not be copied except in full without the approval of the laboratory. Samples will be disposed of thirty days after the final report has been delivered. If you have any questions or concerns, please feel free to call our Customer Service Department.



Laurel Stoddard  
Laboratory Director

**REVIEWED**

**By ESS Laboratory at 5:57 pm, Nov 26, 2024**

**Analytical Summary**

The project as described above has been analyzed in accordance with the ESS Quality Assurance Plan. This plan utilizes the following methodologies: US EPA SW-846, US EPA Methods for Chemical Analysis of Water and Wastes per 40 CFR Part 136, APHA Standard Methods for the Examination of Water and Wastewater, American Society for Testing and Materials (ASTM), and other recognized methodologies. The analyses with these noted observations are in conformance to the Quality Assurance Plan. In chromatographic analysis, manual integration is frequently used instead of automated integration because it produces more accurate results.

The test results present in this report are in compliance with TNI and relative state standards, and/or client Quality Assurance Project Plans (QAPP). The laboratory has reviewed the following: Sample Preservations, Hold Times, Initial Calibrations, Continuing Calibrations, Method Blanks, Blank Spikes, Blank Spike Duplicates, Duplicates, Matrix Spikes, Matrix Spike Duplicates, Surrogates and Internal Standards. Any results which were found to be outside of the recommended ranges stated in our SOPs will be noted in the Project Narrative.

**Subcontracted Analyses**

Aerobiology Boston - Woburn, MA  
CTS - Cranston, RI

Asbestos  
Grain Size Analysis



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**SAMPLE RECEIPT**

The following samples were received on November 21, 2024 for the analyses specified on the enclosed Chain of Custody Record.

**Low Level VOA vials were frozen by the client within 20 hrs. of sampling.**

**Sample ID(s) 24K0950-01 and 24K0950-02 for Metals were oven dried at 60 degrees Celsius prior to digestion and relogged in as Sample ID(s) 24K0950-03 and 24K0950-04. This was done to increase the dry weight of the sample digested which decreases variability of results and lowers the detection limits for samples with high water content.**

<u>Lab Number</u>	<u>Sample Name</u>	<u>Matrix</u>	<u>Analysis</u>
24K0950-01	DS	Sediment	2540G, 8082A Cong, 8260D Low, EPH8270, EPH8270SIM, LK, MADEP-EPH, SUB
24K0950-02	US	Sediment	2540G, 8082A Cong, 8260D Low, EPH8270, EPH8270SIM, LK, MADEP-EPH, SUB
24K0950-03	DS - Oven Dried	Sediment	6010D, 7471B
24K0950-04	US - Oven Dried	Sediment	6010D, 7471B

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**PROJECT NARRATIVE**

**8082 Polychlorinated Biphenyls (PCB) / Congeners**

24K0950-01 Lower value is used due to matrix interferences (LC).  
BZ#52 [2C] , BZ#66  
24K0950-01 Percent difference between primary and confirmation results exceeds 40% (P).  
BZ#52 [2C] , BZ#66  
24K0950-02 Percent difference between primary and confirmation results exceeds 40% (P).  
BZ#153

**MADEP-EPH Extractable Petroleum Hydrocarbons**

24K0950-01 Present in Method Blank (B).  
Phenanthrene  
24K0950-02 Present in Method Blank (B).  
Phenanthrene  
D4K0442-CCV1 Continuing Calibration %Diff/Drift is above control limit (CD+).  
Acenaphthylene (23% @ 20%)

**Volatile Organics Low Level**

D4K0424-CCV1 Calibration required quadratic regression (Q).  
1,4-Dioxane (106% @ 80-120%), Bromoform (108% @ 40-160%), Tertiary-amyl methyl ether (111% @ 80-120%)  
D4K0424-CCV1 Continuing Calibration %Diff/Drift is above control limit (CD+).  
2,2-Dichloropropane (22% @ 20%)  
D4K0471-CCV1 Calibration required quadratic regression (Q).  
1,4-Dioxane (119% @ 80-120%), Bromoform (111% @ 40-160%), Tertiary-amyl methyl ether (111% @ 80-120%)  
D4K0471-CCV1 Continuing Calibration %Diff/Drift is above control limit (CD+).  
2,2-Dichloropropane (22% @ 20%)  
DK42219-BS1 Blank Spike recovery is above upper control limit (B+).  
2,2-Dichloropropane (139% @ 70-130%), Ethyl tertiary-butyl ether (132% @ 70-130%)  
DK42219-BSD1 Blank Spike recovery is above upper control limit (B+).  
2,2-Dichloropropane (139% @ 70-130%), Ethyl tertiary-butyl ether (132% @ 70-130%)  
DK42542-BS1 Blank Spike recovery is above upper control limit (B+).  
2,2-Dichloropropane (136% @ 70-130%)  
DK42542-BSD1 Blank Spike recovery is above upper control limit (B+).  
2,2-Dichloropropane (134% @ 70-130%)

No other observations noted.

End of Project Narrative.

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**DATA USABILITY LINKS**

*To ensure you are viewing the most current version of the documents below, please clear your internet cookies for [www.ESSLaboratory.com](http://www.ESSLaboratory.com). Consult your IT Support personnel for information on how to clear your internet cookies.*

[Definitions of Quality Control Parameters](#)

[Semivolatile Organics Internal Standard Information](#)

[Semivolatile Organics Surrogate Information](#)

[Volatile Organics Internal Standard Information](#)

[Volatile Organics Surrogate Information](#)

[EPH and VPH Alkane Lists](#)

**CURRENT SW-846 METHODOLOGY VERSIONS**

**Analytical Methods**

1010A - Flashpoint  
6010D - ICP  
6020B - ICP MS  
7010 - Graphite Furnace  
7196A - Hexavalent Chromium  
7470A - Aqueous Mercury  
7471B - Solid Mercury  
8011 - EDB/DBCP/TCP  
8015C - GRO/DRO  
8081B - Pesticides  
8082A - PCB  
8100M - TPH  
8151A - Herbicides  
8260D - VOA  
8270E - SVOA  
8270E SIM - SVOA Low Level  
9014 - Cyanide  
9038 - Sulfate  
9040C - Aqueous pH  
9045D - Solid pH (Corrosivity)  
9050A - Specific Conductance  
9056A - Anions (IC)  
9060A - TOC  
9095B - Paint Filter  
MADEP 19-2.1 - EPH  
MADEP 18-2.1 - VPH

**Prep Methods**

3005A - Aqueous ICP Digestion  
3020A - Aqueous Graphite Furnace / ICP MS Digestion  
3050B - Solid ICP / Graphite Furnace / ICP MS Digestion  
3060A - Solid Hexavalent Chromium Digestion  
3510C - Separatory Funnel Extraction  
3520C - Liquid / Liquid Extraction  
3540C - Manual Soxhlet Extraction  
3546 - Microwave Extraction  
3580A - Waste Dilution  
5030B - Aqueous Purge and Trap  
5030C - Aqueous Purge and Trap  
5035A - Solid Purge and Trap

SW846 Reactivity Methods 7.3.3.2 (Reactive Cyanide) and 7.3.4.1 (Reactive Sulfide) have been withdrawn by EPA. These methods are reported per client request and are not NELAP accredited.

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS  
Date Sampled: 11/19/24 09:30  
Percent Solids: 38  
Initial Volume: 7.1g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-01  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 11/22/24 8:00

**Volatile Organics Low Level**

<b>Analyte</b>	<b>Results (MRL)</b>	<b>MDL</b>	<b>Method</b>	<b>Limit</b>	<b>DF</b>	<b>Analyst</b>	<b>Analyzed</b>	<b>Sequence</b>	<b>Batch</b>
1,1,1,2-Tetrachloroethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,1,1-Trichloroethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,1,2,2-Tetrachloroethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,1,2-Trichloroethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,1-Dichloroethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,1-Dichloroethene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,1-Dichloropropene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2,3-Trichlorobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2,3-Trichloropropane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2,4-Trichlorobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2,4-Trimethylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2-Dibromo-3-Chloropropane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2-Dibromoethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2-Dichlorobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2-Dichloroethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,2-Dichloropropane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,3,5-Trimethylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,3-Dichlorobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,3-Dichloropropane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,4-Dichlorobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
1,4-Dioxane	ND (0.187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
2,2-Dichloropropane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
2-Butanone	ND (0.0934)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
2-Chlorotoluene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
2-Hexanone	ND (0.0934)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
4-Chlorotoluene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
4-Isopropyltoluene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS  
Date Sampled: 11/19/24 09:30  
Percent Solids: 38  
Initial Volume: 7.1g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-01  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 11/22/24 8:00

**Volatile Organics Low Level**

<b>Analyte</b>	<b>Results (MRL)</b>	<b>MDL</b>	<b>Method</b>	<b>Limit</b>	<b>DF</b>	<b>Analyst</b>	<b>Analyzed</b>	<b>Sequence</b>	<b>Batch</b>
4-Methyl-2-Pentanone	ND (0.0934)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Acetone	ND (0.0934)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Benzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Bromobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Bromochloromethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Bromodichloromethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Bromoform	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Bromomethane	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Carbon Disulfide	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Carbon Tetrachloride	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Chlorobenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Chloroethane	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Chloroform	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Chloromethane	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
cis-1,2-Dichloroethene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
cis-1,3-Dichloropropene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Dibromochloromethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Dibromomethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Dichlorodifluoromethane	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Diethyl Ether	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Di-isopropyl ether	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Ethyl tertiary-butyl ether	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Ethylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Hexachlorobutadiene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Isopropylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Methyl tert-Butyl Ether	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Methylene Chloride	ND (0.0467)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS  
Date Sampled: 11/19/24 09:30  
Percent Solids: 38  
Initial Volume: 7.1g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-01  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 11/22/24 8:00

**Volatile Organics Low Level**

<b>Analyte</b>	<b>Results (MRL)</b>	<b>MDL</b>	<b>Method</b>	<b>Limit</b>	<b>DF</b>	<b>Analyst</b>	<b>Analyzed</b>	<b>Sequence</b>	<b>Batch</b>
Naphthalene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
n-Butylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
n-Propylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
sec-Butylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Styrene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
tert-Butylbenzene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Tertiary-amyl methyl ether	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Tetrachloroethene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Tetrahydrofuran	ND (0.0374)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Toluene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
trans-1,2-Dichloroethene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
trans-1,3-Dichloropropene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Trichloroethene	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Trichlorofluoromethane	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Vinyl Chloride	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Xylene O	ND (0.0093)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Xylene P,M	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219
Xylenes (Total)	ND (0.0187)	---	8260D Low	---	1	MEK	11/22/24 19:05	D4K0424	DK42219

	<i>%Recovery</i>	<i>Qualifier</i>	<i>Limits</i>
<i>Surrogate: 1,2-Dichloroethane-d4</i>	105 %		70-130
<i>Surrogate: 4-Bromofluorobenzene</i>	92 %		70-130
<i>Surrogate: Dibromofluoromethane</i>	107 %		70-130
<i>Surrogate: Toluene-d8</i>	100 %		70-130

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: DS  
 Date Sampled: 11/19/24 09:30  
 Percent Solids: 38  
 Initial Volume: 30g  
 Final Volume: 1ml  
 Extraction Method: 3546

ESS Laboratory Work Order: 24K0950  
 ESS Laboratory Sample ID: 24K0950-01  
 Sample Matrix: Sediment  
 Units: mg/kg dry

Prepared: 11/22/24 11:35

**MADEP-EPH Extractable Petroleum Hydrocarbons**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
C9-C18 Aliphatics1	ND (22.1)	---	MADEP-EPH	---	1	JDN	11/22/24 18:25	D4K0434	DK42206
<b>C19-C36 Aliphatics1</b>	<b>246</b> (22.1)	---	MADEP-EPH	---	1	JDN	11/22/24 18:25	D4K0434	DK42206
<b>C11-C22 Unadjusted Aromatics1</b>	<b>85.1</b> (22.1)	---	EPH8270	---	1	IBM	11/22/24 18:23	D4K0433	DK42206
<b>C11-C22 Aromatics1,2</b>	<b>84.3</b> (22.4)	---	EPH8270	---		TJ	11/22/24 18:59	---	[CALC]
2-Methylnaphthalene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
Acenaphthene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
Naphthalene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Phenanthrene</b>	<b>B 0.069</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
Acenaphthylene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
Anthracene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Benzo(a)anthracene</b>	<b>0.071</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Benzo(a)pyrene</b>	<b>0.056</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Benzo(b)fluoranthene</b>	<b>0.058</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Benzo(g,h,i)perylene</b>	<b>0.051</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Benzo(k)fluoranthene</b>	<b>0.051</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Chrysene</b>	<b>0.090</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Dibenzo(a,h)Anthracene</b>	<b>0.026</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Fluoranthene</b>	<b>0.124</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
Fluorene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Indeno(1,2,3-cd)Pyrene</b>	<b>0.039</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206
<b>Pyrene</b>	<b>0.137</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 18:59	D4K0442	DK42206

	<i>%Recovery</i>	<i>Qualifier</i>	<i>Limits</i>
<i>Surrogate: 1-Chlorooctadecane</i>	69 %		40-140
<i>Surrogate: 2-Bromonaphthalene</i>	78 %		40-140
<i>Surrogate: 2-Fluorobiphenyl</i>	74 %		40-140
<i>Surrogate: O-Terphenyl</i>	75 %		40-140

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS  
Date Sampled: 11/19/24 09:30  
Percent Solids: 38

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-01  
Sample Matrix: Sediment

**Classical Chemistry**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Percent Moisture	62 (1)	---	2540G	---	1	EAM	11/21/24 19:08	%	DK42116
Total Organic Carbon (Average)	35800 (500)	---	LK	---	1	CCP	11/25/24 14:53	mg/kg	[CALC]



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS  
Date Sampled: 11/19/24 09:30

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-01  
Sample Matrix: Sediment

**Subcontracted Analysis**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Asbestos	See Attached (N/A)	---		---				%	
Grain Size	See Attached (N/A)	---		---				%	

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS  
Date Sampled: 11/19/24 09:30  
Percent Solids: 38  
Initial Volume: 30.2g  
Final Volume: 2ml  
Extraction Method: 3540C

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-01  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: DMC  
Prepared: 11/22/24 10:45

**8082 Polychlorinated Biphenyls (PCB) / Congeners**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
BZ#8	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#18	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#28 [2C]	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#44 [2C]	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
<b>BZ#52 [2C]</b>	<b>P, LC 0.00144</b> (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
<b>BZ#66</b>	<b>P, LC 0.00103</b> (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#101	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#105	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#118	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#128	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#138	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#153	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#170	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#180	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#187	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#195	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#206	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205
BZ#209	ND (0.00071)	---	8082A Cong	---	1	11/25/24 12:43	D4K0445	DK42205

	<i>%Recovery</i>	<i>Qualifier</i>	<i>Limits</i>
<i>Surrogate: Tetrachloro-m-xylene</i>	63 %		30-150

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: US  
Date Sampled: 11/19/24 10:30  
Percent Solids: 42  
Initial Volume: 6.7g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-02  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 11/25/24 8:00

**Volatile Organics Low Level**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
1,1,1,2-Tetrachloroethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,1,1-Trichloroethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,1,2,2-Tetrachloroethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,1,2-Trichloroethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,1-Dichloroethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,1-Dichloroethene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,1-Dichloropropene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2,3-Trichlorobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2,3-Trichloropropane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2,4-Trichlorobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2,4-Trimethylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2-Dibromo-3-Chloropropane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2-Dibromoethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2-Dichlorobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2-Dichloroethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,2-Dichloropropane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,3,5-Trimethylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,3-Dichlorobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,3-Dichloropropane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,4-Dichlorobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
1,4-Dioxane	ND (0.178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
2,2-Dichloropropane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
2-Butanone	ND (0.0891)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
2-Chlorotoluene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
2-Hexanone	ND (0.0891)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
4-Chlorotoluene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
4-Isopropyltoluene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: US  
Date Sampled: 11/19/24 10:30  
Percent Solids: 42  
Initial Volume: 6.7g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-02  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 11/25/24 8:00

**Volatile Organics Low Level**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
4-Methyl-2-Pentanone	ND (0.0891)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Acetone	ND (0.0891)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Benzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Bromobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Bromochloromethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Bromodichloromethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Bromoform	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Bromomethane	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Carbon Disulfide	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Carbon Tetrachloride	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Chlorobenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Chloroethane	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Chloroform	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Chloromethane	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
cis-1,2-Dichloroethene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
cis-1,3-Dichloropropene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Dibromochloromethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Dibromomethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Dichlorodifluoromethane	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Diethyl Ether	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Di-isopropyl ether	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Ethyl tertiary-butyl ether	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Ethylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Hexachlorobutadiene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Isopropylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Methyl tert-Butyl Ether	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Methylene Chloride	ND (0.0445)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: US  
Date Sampled: 11/19/24 10:30  
Percent Solids: 42  
Initial Volume: 6.7g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-02  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 11/25/24 8:00

**Volatile Organics Low Level**

<b>Analyte</b>	<b>Results (MRL)</b>	<b>MDL</b>	<b>Method</b>	<b>Limit</b>	<b>DF</b>	<b>Analyst</b>	<b>Analyzed</b>	<b>Sequence</b>	<b>Batch</b>
Naphthalene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
n-Butylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
n-Propylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
sec-Butylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Styrene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
tert-Butylbenzene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Tertiary-amyl methyl ether	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Tetrachloroethene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Tetrahydrofuran	ND (0.0356)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Toluene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
trans-1,2-Dichloroethene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
trans-1,3-Dichloropropene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Trichloroethene	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Trichlorofluoromethane	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Vinyl Chloride	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Xylene O	ND (0.0089)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Xylene P,M	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542
Xylenes (Total)	ND (0.0178)	---	8260D Low	---	1	MEK	11/25/24 12:26	D4K0471	DK42542

	<i>%Recovery</i>	<i>Qualifier</i>	<i>Limits</i>
<i>Surrogate: 1,2-Dichloroethane-d4</i>	102 %		70-130
<i>Surrogate: 4-Bromofluorobenzene</i>	84 %		70-130
<i>Surrogate: Dibromofluoromethane</i>	104 %		70-130
<i>Surrogate: Toluene-d8</i>	105 %		70-130

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: US  
 Date Sampled: 11/19/24 10:30  
 Percent Solids: 42  
 Initial Volume: 25.9g  
 Final Volume: 1ml  
 Extraction Method: 3546

ESS Laboratory Work Order: 24K0950  
 ESS Laboratory Sample ID: 24K0950-02  
 Sample Matrix: Sediment  
 Units: mg/kg dry

Prepared: 11/22/24 11:35

**MADEP-EPH Extractable Petroleum Hydrocarbons**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
C9-C18 Aliphatics1	ND (23.0)	---	MADEP-EPH	---	1	JDN	11/22/24 19:00	D4K0434	DK42206
C19-C36 Aliphatics1	ND (23.0)	---	MADEP-EPH	---	1	JDN	11/22/24 19:00	D4K0434	DK42206
C11-C22 Unadjusted Aromatics1	ND (23.0)	---	EPH8270	---	1	IBM	11/22/24 18:59	D4K0433	DK42206
C11-C22 Aromatics1,2	ND (23.4)	---	EPH8270	---		TJ	11/22/24 19:28	---	[CALC]
2-Methylnaphthalene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Acenaphthene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Naphthalene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
<b>Phenanthrene</b>	<b>B 0.019</b> (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Acenaphthylene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Anthracene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Benzo(a)anthracene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Benzo(a)pyrene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Benzo(b)fluoranthene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Benzo(g,h,i)perylene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Benzo(k)fluoranthene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Chrysene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Dibenzo(a,h)Anthracene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Fluoranthene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Fluorene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Indeno(1,2,3-cd)Pyrene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206
Pyrene	ND (0.018)	---	EPH8270SIM	---	1	TJ	11/22/24 19:28	D4K0442	DK42206

	<i>%Recovery</i>	<i>Qualifier</i>	<i>Limits</i>
<i>Surrogate: 1-Chlorooctadecane</i>	66 %		40-140
<i>Surrogate: 2-Bromonaphthalene</i>	79 %		40-140
<i>Surrogate: 2-Fluorobiphenyl</i>	74 %		40-140
<i>Surrogate: O-Terphenyl</i>	76 %		40-140

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: US  
 Date Sampled: 11/19/24 10:30  
 Percent Solids: 42

ESS Laboratory Work Order: 24K0950  
 ESS Laboratory Sample ID: 24K0950-02  
 Sample Matrix: Sediment

**Classical Chemistry**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Percent Moisture	58 (1)	---	2540G	---	1	EAM	11/21/24 19:08	%	DK42116
Total Organic Carbon (Average)	27200 (500)	---	LK	---	1	CCP	11/25/24 15:10	mg/kg	[CALC]

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: US  
Date Sampled: 11/19/24 10:30

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-02  
Sample Matrix: Sediment

**Subcontracted Analysis**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Asbestos	See Attached (N/A)	---		---				%	
Grain Size	See Attached (N/A)	---		---				%	



### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: US  
 Date Sampled: 11/19/24 10:30  
 Percent Solids: 42  
 Initial Volume: 30.4g  
 Final Volume: 2ml  
 Extraction Method: 3540C

ESS Laboratory Work Order: 24K0950  
 ESS Laboratory Sample ID: 24K0950-02  
 Sample Matrix: Sediment  
 Units: mg/kg dry  
 Analyst: DMC  
 Prepared: 11/22/24 10:45

### 8082 Polychlorinated Biphenyls (PCB) / Congeners

Analyte	Results (MRL)	MDL	Method	Limit	DF	Analyzed	Sequence	Batch
BZ#8	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#18	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#28	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#44	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#52	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#66	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
<b>BZ#101</b>	<b>0.00099</b> (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#105	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
<b>BZ#118</b>	<b>0.00085</b> (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#128	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
<b>BZ#138 [2C]</b>	<b>0.00146</b> (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
<b>BZ#153</b>	<b>P 0.00139</b> (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#170	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#180 [2C]	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#187	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#195	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#206	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205
BZ#209	ND (0.00064)	---	8082A Cong	---	1	11/25/24 13:13	D4K0445	DK42205

Surrogate: Tetrachloro-m-xylene

%Recovery	Qualifier	Limits
70 %		30-150

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: DS - Oven Dried  
Date Sampled: 11/19/24 09:30  
Percent Solids: 93

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-03  
Sample Matrix: Sediment  
Units: mg/kg dry

Extraction Method: 3050B

**Total Metals**

<b><u>Analyte</u></b>	<b><u>Results (MRL)</u></b>	<b><u>MDL</u></b>	<b><u>Method</u></b>	<b><u>Limit</u></b>	<b><u>DF</u></b>	<b><u>Analyst</u></b>	<b><u>Analyzed</u></b>	<b><u>IV / FV</u></b>	<b><u>Batch</u></b>
Arsenic	12.3 (0.42)	---	6010D	---	1	KJB	11/25/24 15:31	5.15 100	DK42217
Cadmium	0.32 (0.10)	---	6010D	---	1	KJB	11/22/24 19:03	5.15 100	DK42217
Chromium	14.2 (0.42)	---	6010D	---	1	KJB	11/22/24 19:03	5.15 100	DK42217
Copper	30.2 (1.04)	---	6010D	---	1	KJB	11/22/24 19:03	5.15 100	DK42217
Lead	71.9 (2.09)	---	6010D	---	1	KJB	11/22/24 19:03	5.15 100	DK42217
Mercury	0.303 (0.047)	---	7471B	---	5	AFV	11/25/24 18:51	2.28 40	DK42529
Nickel	10.0 (1.04)	---	6010D	---	1	KJB	11/22/24 19:03	5.15 100	DK42217
Zinc	104 (1.04)	---	6010D	---	1	KJB	11/22/24 19:03	5.15 100	DK42217

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: US - Oven Dried  
Date Sampled: 11/19/24 10:30  
Percent Solids: 96

ESS Laboratory Work Order: 24K0950  
ESS Laboratory Sample ID: 24K0950-04  
Sample Matrix: Sediment  
Units: mg/kg dry

Extraction Method: 3050B

**Total Metals**

<b><u>Analyte</u></b>	<b><u>Results (MRL)</u></b>	<b><u>MDL</u></b>	<b><u>Method</u></b>	<b><u>Limit</u></b>	<b><u>DF</u></b>	<b><u>Analyst</u></b>	<b><u>Analyzed</u></b>	<b><u>IV / FV</u></b>	<b><u>Batch</u></b>
<b>Arsenic</b>	<b>10.7</b> (0.41)	---	6010D	---	1	KJB	11/25/24 15:33	5.15 100	DK42217
<b>Cadmium</b>	<b>0.12</b> (0.10)	---	6010D	---	1	KJB	11/22/24 19:05	5.15 100	DK42217
<b>Chromium</b>	<b>8.37</b> (0.41)	---	6010D	---	1	KJB	11/22/24 19:05	5.15 100	DK42217
<b>Copper</b>	<b>8.34</b> (1.02)	---	6010D	---	1	KJB	11/22/24 19:05	5.15 100	DK42217
<b>Lead</b>	<b>17.7</b> (2.03)	---	6010D	---	1	KJB	11/22/24 19:05	5.15 100	DK42217
<b>Mercury</b>	<b>0.074</b> (0.010)	---	7471B	---	1	AFV	11/25/24 18:24	2.04 40	DK42529
<b>Nickel</b>	<b>6.42</b> (1.02)	---	6010D	---	1	KJB	11/22/24 19:05	5.15 100	DK42217
<b>Zinc</b>	<b>43.6</b> (1.02)	---	6010D	---	1	KJB	11/22/24 19:05	5.15 100	DK42217

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Total Metals

#### Batch DK42217 - 3050B

##### Blank

Arsenic	ND	0.97	mg/kg wet
Cadmium	ND	0.24	mg/kg wet
Chromium	ND	0.97	mg/kg wet
Copper	ND	2.42	mg/kg wet
Lead	ND	4.83	mg/kg wet
Nickel	ND	2.42	mg/kg wet
Zinc	ND	2.42	mg/kg wet

##### LCS

Arsenic	108	3.28	mg/kg wet	280.0	38	32-110
Cadmium	78.3	0.82	mg/kg wet	210.0	37	33-110
Chromium	133	3.28	mg/kg wet	225.0	59	50-110
Copper	122	8.20	mg/kg wet	290.0	42	33-110
Lead	145	16.4	mg/kg wet	350.0	42	31-110
Nickel	56.8	8.20	mg/kg wet	95.00	60	48-111
Zinc	210	8.20	mg/kg wet	500.0	42	30-110

##### LCS Dup

Arsenic	113	3.12	mg/kg wet	280.0	41	32-110	5	30
Cadmium	79.9	0.78	mg/kg wet	210.0	38	33-110	2	30
Chromium	140	3.12	mg/kg wet	225.0	62	50-110	5	30
Copper	126	7.81	mg/kg wet	290.0	43	33-110	3	30
Lead	153	15.6	mg/kg wet	350.0	44	31-110	5	30
Nickel	60.0	7.81	mg/kg wet	95.00	63	48-111	5	30
Zinc	216	7.81	mg/kg wet	500.0	43	30-110	3	30

##### Reference

Lead	4200	79.4	mg/kg wet	4490	94	81-120
------	------	------	-----------	------	----	--------

#### Batch DK42529 - 7471B

##### Blank

Mercury	ND	0.032	mg/kg wet
---------	----	-------	-----------

##### LCS

Mercury	23.0	2.96	mg/kg wet	24.90	92	80-120
---------	------	------	-----------	-------	----	--------

##### LCS Dup

Mercury	20.3	3.09	mg/kg wet	24.90	82	80-120	12	30
---------	------	------	-----------	-------	----	--------	----	----

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

##### Blank

1,1,1,2-Tetrachloroethane	ND	0.0050	mg/kg wet
1,1,1-Trichloroethane	ND	0.0050	mg/kg wet
1,1,2,2-Tetrachloroethane	ND	0.0050	mg/kg wet
1,1,2-Trichloroethane	ND	0.0050	mg/kg wet



### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

1,1-Dichloroethane	ND	0.0050	mg/kg wet
1,1-Dichloroethene	ND	0.0050	mg/kg wet
1,1-Dichloropropene	ND	0.0050	mg/kg wet
1,2,3-Trichlorobenzene	ND	0.0050	mg/kg wet
1,2,3-Trichloropropane	ND	0.0050	mg/kg wet
1,2,4-Trichlorobenzene	ND	0.0050	mg/kg wet
1,2,4-Trimethylbenzene	ND	0.0050	mg/kg wet
1,2-Dibromo-3-Chloropropane	ND	0.0050	mg/kg wet
1,2-Dibromoethane	ND	0.0050	mg/kg wet
1,2-Dichlorobenzene	ND	0.0050	mg/kg wet
1,2-Dichloroethane	ND	0.0050	mg/kg wet
1,2-Dichloropropane	ND	0.0050	mg/kg wet
1,3,5-Trimethylbenzene	ND	0.0050	mg/kg wet
1,3-Dichlorobenzene	ND	0.0050	mg/kg wet
1,3-Dichloropropane	ND	0.0050	mg/kg wet
1,4-Dichlorobenzene	ND	0.0050	mg/kg wet
1,4-Dioxane	ND	0.100	mg/kg wet
2,2-Dichloropropane	ND	0.0050	mg/kg wet
2-Butanone	ND	0.0500	mg/kg wet
2-Chlorotoluene	ND	0.0050	mg/kg wet
2-Hexanone	ND	0.0500	mg/kg wet
4-Chlorotoluene	ND	0.0050	mg/kg wet
4-Isopropyltoluene	ND	0.0050	mg/kg wet
4-Methyl-2-Pentanone	ND	0.0500	mg/kg wet
Acetone	ND	0.0500	mg/kg wet
Benzene	ND	0.0050	mg/kg wet
Bromobenzene	ND	0.0050	mg/kg wet
Bromochloromethane	ND	0.0050	mg/kg wet
Bromodichloromethane	ND	0.0050	mg/kg wet
Bromoform	ND	0.0050	mg/kg wet
Bromomethane	ND	0.0100	mg/kg wet
Carbon Disulfide	ND	0.0050	mg/kg wet
Carbon Tetrachloride	ND	0.0050	mg/kg wet
Chlorobenzene	ND	0.0050	mg/kg wet
Chloroethane	ND	0.0100	mg/kg wet
Chloroform	ND	0.0050	mg/kg wet
Chloromethane	ND	0.0100	mg/kg wet
cis-1,2-Dichloroethene	ND	0.0050	mg/kg wet
cis-1,3-Dichloropropene	ND	0.0050	mg/kg wet
Dibromochloromethane	ND	0.0050	mg/kg wet
Dibromomethane	ND	0.0050	mg/kg wet
Dichlorodifluoromethane	ND	0.0100	mg/kg wet
Diethyl Ether	ND	0.0050	mg/kg wet
Di-isopropyl ether	ND	0.0050	mg/kg wet

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

Ethyl tertiary-butyl ether	ND	0.0050	mg/kg wet							
Ethylbenzene	ND	0.0050	mg/kg wet							
Hexachlorobutadiene	ND	0.0050	mg/kg wet							
Isopropylbenzene	ND	0.0050	mg/kg wet							
Methyl tert-Butyl Ether	ND	0.0050	mg/kg wet							
Methylene Chloride	ND	0.0250	mg/kg wet							
Naphthalene	ND	0.0050	mg/kg wet							
n-Butylbenzene	ND	0.0050	mg/kg wet							
n-Propylbenzene	ND	0.0050	mg/kg wet							
sec-Butylbenzene	ND	0.0050	mg/kg wet							
Styrene	ND	0.0050	mg/kg wet							
tert-Butylbenzene	ND	0.0050	mg/kg wet							
Tertiary-amyl methyl ether	ND	0.0050	mg/kg wet							
Tetrachloroethene	ND	0.0050	mg/kg wet							
Tetrahydrofuran	ND	0.0200	mg/kg wet							
Toluene	ND	0.0050	mg/kg wet							
trans-1,2-Dichloroethene	ND	0.0050	mg/kg wet							
trans-1,3-Dichloropropene	ND	0.0050	mg/kg wet							
Trichloroethene	ND	0.0050	mg/kg wet							
Trichlorofluoromethane	ND	0.0050	mg/kg wet							
Vinyl Chloride	ND	0.0100	mg/kg wet							
Xylene O	ND	0.0050	mg/kg wet							
Xylene P,M	ND	0.0100	mg/kg wet							

Surrogate: 1,2-Dichloroethane-d4	0.0520		mg/kg wet	0.05000		104	70-130
Surrogate: 4-Bromofluorobenzene	0.0465		mg/kg wet	0.05000		93	70-130
Surrogate: Dibromofluoromethane	0.0511		mg/kg wet	0.05000		102	70-130
Surrogate: Toluene-d8	0.0496		mg/kg wet	0.05000		99	70-130

#### LCS

1,1,1,2-Tetrachloroethane	0.0630	0.0050	mg/kg wet	0.05000		126	70-130
1,1,1-Trichloroethane	0.0620	0.0050	mg/kg wet	0.05000		124	70-130
1,1,2,2-Tetrachloroethane	0.0540	0.0050	mg/kg wet	0.05000		108	40-160
1,1,2-Trichloroethane	0.0554	0.0050	mg/kg wet	0.05000		111	70-130
1,1-Dichloroethane	0.0565	0.0050	mg/kg wet	0.05000		113	70-130
1,1-Dichloroethene	0.0590	0.0050	mg/kg wet	0.05000		118	70-130
1,1-Dichloropropene	0.0555	0.0050	mg/kg wet	0.05000		111	70-130
1,2,3-Trichlorobenzene	0.0567	0.0050	mg/kg wet	0.05000		113	70-130
1,2,3-Trichloropropane	0.0513	0.0050	mg/kg wet	0.05000		103	70-130
1,2,4-Trichlorobenzene	0.0581	0.0050	mg/kg wet	0.05000		116	70-130
1,2,4-Trimethylbenzene	0.0554	0.0050	mg/kg wet	0.05000		111	70-130
1,2-Dibromo-3-Chloropropane	0.0498	0.0050	mg/kg wet	0.05000		100	70-130
1,2-Dibromoethane	0.0580	0.0050	mg/kg wet	0.05000		116	70-130
1,2-Dichlorobenzene	0.0535	0.0050	mg/kg wet	0.05000		107	70-130
1,2-Dichloroethane	0.0545	0.0050	mg/kg wet	0.05000		109	70-130

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

1,2-Dichloropropane	0.0563	0.0050	mg/kg wet	0.05000		113	70-130			
1,3,5-Trimethylbenzene	0.0561	0.0050	mg/kg wet	0.05000		112	70-130			
1,3-Dichlorobenzene	0.0542	0.0050	mg/kg wet	0.05000		108	70-130			
1,3-Dichloropropane	0.0550	0.0050	mg/kg wet	0.05000		110	70-130			
1,4-Dichlorobenzene	0.0538	0.0050	mg/kg wet	0.05000		108	70-130			
1,4-Dioxane	1.21	0.100	mg/kg wet	1.000		121	70-130			
2,2-Dichloropropane	0.0695	0.0050	mg/kg wet	0.05000		139	70-130			B+
2-Butanone	0.298	0.0500	mg/kg wet	0.2500		119	40-160			
2-Chlorotoluene	0.0538	0.0050	mg/kg wet	0.05000		108	70-130			
2-Hexanone	0.300	0.0500	mg/kg wet	0.2500		120	40-160			
4-Chlorotoluene	0.0537	0.0050	mg/kg wet	0.05000		107	70-130			
4-Isopropyltoluene	0.0538	0.0050	mg/kg wet	0.05000		108	70-130			
4-Methyl-2-Pentanone	0.288	0.0500	mg/kg wet	0.2500		115	40-160			
Acetone	0.311	0.0500	mg/kg wet	0.2500		124	40-160			
Benzene	0.0551	0.0050	mg/kg wet	0.05000		110	70-130			
Bromobenzene	0.0549	0.0050	mg/kg wet	0.05000		110	70-130			
Bromochloromethane	0.0562	0.0050	mg/kg wet	0.05000		112	70-130			
Bromodichloromethane	0.0589	0.0050	mg/kg wet	0.05000		118	70-130			
Bromoform	0.0624	0.0050	mg/kg wet	0.05000		125	40-160			
Bromomethane	0.0625	0.0100	mg/kg wet	0.05000		125	40-160			
Carbon Disulfide	0.0585	0.0050	mg/kg wet	0.05000		117	70-130			
Carbon Tetrachloride	0.0645	0.0050	mg/kg wet	0.05000		129	70-130			
Chlorobenzene	0.0548	0.0050	mg/kg wet	0.05000		110	70-130			
Chloroethane	0.0641	0.0100	mg/kg wet	0.05000		128	40-160			
Chloroform	0.0548	0.0050	mg/kg wet	0.05000		110	70-130			
Chloromethane	0.0473	0.0100	mg/kg wet	0.05000		95	40-160			
cis-1,2-Dichloroethene	0.0560	0.0050	mg/kg wet	0.05000		112	70-130			
cis-1,3-Dichloropropene	0.0615	0.0050	mg/kg wet	0.05000		123	40-160			
Dibromochloromethane	0.0624	0.0050	mg/kg wet	0.05000		125	40-160			
Dibromomethane	0.0554	0.0050	mg/kg wet	0.05000		111	70-130			
Dichlorodifluoromethane	0.0381	0.0100	mg/kg wet	0.05000		76	40-160			
Diethyl Ether	0.0571	0.0050	mg/kg wet	0.05000		114	70-130			
Di-isopropyl ether	0.0574	0.0050	mg/kg wet	0.05000		115	70-130			
Ethyl tertiary-butyl ether	0.0659	0.0050	mg/kg wet	0.05000		132	70-130			B+
Ethylbenzene	0.0559	0.0050	mg/kg wet	0.05000		112	70-130			
Hexachlorobutadiene	0.0551	0.0050	mg/kg wet	0.05000		110	40-160			
Isopropylbenzene	0.0622	0.0050	mg/kg wet	0.05000		124	70-130			
Methyl tert-Butyl Ether	0.0588	0.0050	mg/kg wet	0.05000		118	70-130			
Methylene Chloride	0.0573	0.0250	mg/kg wet	0.05000		115	70-130			
Naphthalene	0.0591	0.0050	mg/kg wet	0.05000		118	40-160			
n-Butylbenzene	0.0557	0.0050	mg/kg wet	0.05000		111	70-130			
n-Propylbenzene	0.0544	0.0050	mg/kg wet	0.05000		109	70-130			
sec-Butylbenzene	0.0528	0.0050	mg/kg wet	0.05000		106	70-130			
Styrene	0.0567	0.0050	mg/kg wet	0.05000		113	40-160			

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

tert-Butylbenzene	0.0553	0.0050	mg/kg wet	0.05000		111	70-130			
Tertiary-amyl methyl ether	0.0635	0.0050	mg/kg wet	0.05000		127	70-130			
Tetrachloroethene	0.0524	0.0050	mg/kg wet	0.05000		105	70-130			
Tetrahydrofuran	0.0581	0.0200	mg/kg wet	0.05000		116	70-130			
Toluene	0.0568	0.0050	mg/kg wet	0.05000		114	70-130			
trans-1,2-Dichloroethene	0.0579	0.0050	mg/kg wet	0.05000		116	70-130			
trans-1,3-Dichloropropene	0.0531	0.0050	mg/kg wet	0.05000		106	70-130			
Trichloroethene	0.0556	0.0050	mg/kg wet	0.05000		111	70-130			
Trichlorofluoromethane	0.0543	0.0050	mg/kg wet	0.05000		109	40-160			
Vinyl Chloride	0.0604	0.0100	mg/kg wet	0.05000		121	70-130			
Xylene O	0.0570	0.0050	mg/kg wet	0.05000		114	70-130			
Xylene P,M	0.115	0.0100	mg/kg wet	0.1000		115	70-130			

Surrogate: 1,2-Dichloroethane-d4	0.0496		mg/kg wet	0.05000		99	70-130			
Surrogate: 4-Bromofluorobenzene	0.0493		mg/kg wet	0.05000		99	70-130			
Surrogate: Dibromofluoromethane	0.0506		mg/kg wet	0.05000		101	70-130			
Surrogate: Toluene-d8	0.0493		mg/kg wet	0.05000		99	70-130			

#### LCS Dup

1,1,1,2-Tetrachloroethane	0.0626	0.0050	mg/kg wet	0.05000		125	70-130	0.7	20	
1,1,1-Trichloroethane	0.0620	0.0050	mg/kg wet	0.05000		124	70-130	0	20	
1,1,2,2-Tetrachloroethane	0.0540	0.0050	mg/kg wet	0.05000		108	40-160	0.04	20	
1,1,2-Trichloroethane	0.0551	0.0050	mg/kg wet	0.05000		110	70-130	0.6	20	
1,1-Dichloroethane	0.0566	0.0050	mg/kg wet	0.05000		113	70-130	0.3	20	
1,1-Dichloroethene	0.0586	0.0050	mg/kg wet	0.05000		117	70-130	0.7	20	
1,1-Dichloropropene	0.0547	0.0050	mg/kg wet	0.05000		109	70-130	2	20	
1,2,3-Trichlorobenzene	0.0561	0.0050	mg/kg wet	0.05000		112	70-130	1	20	
1,2,3-Trichloropropane	0.0515	0.0050	mg/kg wet	0.05000		103	70-130	0.4	20	
1,2,4-Trichlorobenzene	0.0571	0.0050	mg/kg wet	0.05000		114	70-130	2	20	
1,2,4-Trimethylbenzene	0.0562	0.0050	mg/kg wet	0.05000		112	70-130	2	20	
1,2-Dibromo-3-Chloropropane	0.0497	0.0050	mg/kg wet	0.05000		99	70-130	0.2	20	
1,2-Dibromoethane	0.0577	0.0050	mg/kg wet	0.05000		115	70-130	0.5	20	
1,2-Dichlorobenzene	0.0541	0.0050	mg/kg wet	0.05000		108	70-130	1	20	
1,2-Dichloroethane	0.0539	0.0050	mg/kg wet	0.05000		108	70-130	1	20	
1,2-Dichloropropane	0.0553	0.0050	mg/kg wet	0.05000		111	70-130	2	20	
1,3,5-Trimethylbenzene	0.0570	0.0050	mg/kg wet	0.05000		114	70-130	2	20	
1,3-Dichlorobenzene	0.0539	0.0050	mg/kg wet	0.05000		108	70-130	0.6	20	
1,3-Dichloropropane	0.0541	0.0050	mg/kg wet	0.05000		108	70-130	2	20	
1,4-Dichlorobenzene	0.0549	0.0050	mg/kg wet	0.05000		110	70-130	2	20	
1,4-Dioxane	1.26	0.100	mg/kg wet	1.000		126	70-130	4	20	
2,2-Dichloropropane	0.0693	0.0050	mg/kg wet	0.05000		139	70-130	0.4	20	B+
2-Butanone	0.295	0.0500	mg/kg wet	0.2500		118	40-160	1	20	
2-Chlorotoluene	0.0543	0.0050	mg/kg wet	0.05000		109	70-130	1	20	
2-Hexanone	0.297	0.0500	mg/kg wet	0.2500		119	40-160	1	20	
4-Chlorotoluene	0.0539	0.0050	mg/kg wet	0.05000		108	70-130	0.4	20	



### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

4-Isopropyltoluene	0.0537	0.0050	mg/kg wet	0.05000		107	70-130	0.07	20	
4-Methyl-2-Pentanone	0.286	0.0500	mg/kg wet	0.2500		114	40-160	0.8	20	
Acetone	0.305	0.0500	mg/kg wet	0.2500		122	40-160	2	20	
Benzene	0.0546	0.0050	mg/kg wet	0.05000		109	70-130	0.9	20	
Bromobenzene	0.0553	0.0050	mg/kg wet	0.05000		111	70-130	0.8	20	
Bromochloromethane	0.0556	0.0050	mg/kg wet	0.05000		111	70-130	0.9	20	
Bromodichloromethane	0.0591	0.0050	mg/kg wet	0.05000		118	70-130	0.3	20	
Bromoform	0.0619	0.0050	mg/kg wet	0.05000		124	40-160	0.8	20	
Bromomethane	0.0623	0.0100	mg/kg wet	0.05000		125	40-160	0.3	20	
Carbon Disulfide	0.0578	0.0050	mg/kg wet	0.05000		116	70-130	1	20	
Carbon Tetrachloride	0.0645	0.0050	mg/kg wet	0.05000		129	70-130	0.1	20	
Chlorobenzene	0.0546	0.0050	mg/kg wet	0.05000		109	70-130	0.4	20	
Chloroethane	0.0628	0.0100	mg/kg wet	0.05000		126	40-160	2	20	
Chloroform	0.0549	0.0050	mg/kg wet	0.05000		110	70-130	0.2	20	
Chloromethane	0.0465	0.0100	mg/kg wet	0.05000		93	40-160	2	20	
cis-1,2-Dichloroethene	0.0555	0.0050	mg/kg wet	0.05000		111	70-130	0.9	20	
cis-1,3-Dichloropropene	0.0614	0.0050	mg/kg wet	0.05000		123	40-160	0.07	20	
Dibromochloromethane	0.0620	0.0050	mg/kg wet	0.05000		124	40-160	0.7	20	
Dibromomethane	0.0541	0.0050	mg/kg wet	0.05000		108	70-130	2	20	
Dichlorodifluoromethane	0.0370	0.0100	mg/kg wet	0.05000		74	40-160	3	20	
Diethyl Ether	0.0567	0.0050	mg/kg wet	0.05000		113	70-130	0.7	20	
Di-isopropyl ether	0.0569	0.0050	mg/kg wet	0.05000		114	70-130	0.9	20	
Ethyl tertiary-butyl ether	0.0661	0.0050	mg/kg wet	0.05000		132	70-130	0.3	20	B+
Ethylbenzene	0.0556	0.0050	mg/kg wet	0.05000		111	70-130	0.6	20	
Hexachlorobutadiene	0.0562	0.0050	mg/kg wet	0.05000		112	40-160	2	20	
Isopropylbenzene	0.0634	0.0050	mg/kg wet	0.05000		127	70-130	2	20	
Methyl tert-Butyl Ether	0.0586	0.0050	mg/kg wet	0.05000		117	70-130	0.3	20	
Methylene Chloride	0.0574	0.0250	mg/kg wet	0.05000		115	70-130	0.2	20	
Naphthalene	0.0579	0.0050	mg/kg wet	0.05000		116	40-160	2	20	
n-Butylbenzene	0.0558	0.0050	mg/kg wet	0.05000		112	70-130	0.2	20	
n-Propylbenzene	0.0553	0.0050	mg/kg wet	0.05000		111	70-130	2	20	
sec-Butylbenzene	0.0530	0.0050	mg/kg wet	0.05000		106	70-130	0.5	20	
Styrene	0.0568	0.0050	mg/kg wet	0.05000		114	40-160	0.1	20	
tert-Butylbenzene	0.0559	0.0050	mg/kg wet	0.05000		112	70-130	1	20	
Tertiary-amyl methyl ether	0.0634	0.0050	mg/kg wet	0.05000		127	70-130	0.3	20	
Tetrachloroethene	0.0525	0.0050	mg/kg wet	0.05000		105	70-130	0.3	20	
Tetrahydrofuran	0.0582	0.0200	mg/kg wet	0.05000		116	70-130	0.2	20	
Toluene	0.0563	0.0050	mg/kg wet	0.05000		113	70-130	1	20	
trans-1,2-Dichloroethene	0.0573	0.0050	mg/kg wet	0.05000		115	70-130	1	20	
trans-1,3-Dichloropropene	0.0524	0.0050	mg/kg wet	0.05000		105	70-130	1	20	
Trichloroethene	0.0553	0.0050	mg/kg wet	0.05000		111	70-130	0.7	20	
Trichlorofluoromethane	0.0538	0.0050	mg/kg wet	0.05000		108	40-160	1	20	
Vinyl Chloride	0.0599	0.0100	mg/kg wet	0.05000		120	70-130	0.9	20	
Xylene O	0.0566	0.0050	mg/kg wet	0.05000		113	70-130	0.7	20	

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42219 - 5035

Xylene P,M	0.115	0.0100	mg/kg wet	0.1000		115	70-130	0.6	20	
Surrogate: 1,2-Dichloroethane-d4	0.0497		mg/kg wet	0.05000		99	70-130			
Surrogate: 4-Bromofluorobenzene	0.0501		mg/kg wet	0.05000		100	70-130			
Surrogate: Dibromofluoromethane	0.0508		mg/kg wet	0.05000		102	70-130			
Surrogate: Toluene-d8	0.0497		mg/kg wet	0.05000		99	70-130			

#### Batch DK42542 - 5035

#### Blank

1,1,1,2-Tetrachloroethane	ND	0.0050	mg/kg wet
1,1,1-Trichloroethane	ND	0.0050	mg/kg wet
1,1,2,2-Tetrachloroethane	ND	0.0050	mg/kg wet
1,1,2-Trichloroethane	ND	0.0050	mg/kg wet
1,1-Dichloroethane	ND	0.0050	mg/kg wet
1,1-Dichloroethene	ND	0.0050	mg/kg wet
1,1-Dichloropropene	ND	0.0050	mg/kg wet
1,2,3-Trichlorobenzene	ND	0.0050	mg/kg wet
1,2,3-Trichloropropane	ND	0.0050	mg/kg wet
1,2,4-Trichlorobenzene	ND	0.0050	mg/kg wet
1,2,4-Trimethylbenzene	ND	0.0050	mg/kg wet
1,2-Dibromo-3-Chloropropane	ND	0.0050	mg/kg wet
1,2-Dibromoethane	ND	0.0050	mg/kg wet
1,2-Dichlorobenzene	ND	0.0050	mg/kg wet
1,2-Dichloroethane	ND	0.0050	mg/kg wet
1,2-Dichloropropane	ND	0.0050	mg/kg wet
1,3,5-Trimethylbenzene	ND	0.0050	mg/kg wet
1,3-Dichlorobenzene	ND	0.0050	mg/kg wet
1,3-Dichloropropane	ND	0.0050	mg/kg wet
1,4-Dichlorobenzene	ND	0.0050	mg/kg wet
1,4-Dioxane	ND	0.100	mg/kg wet
2,2-Dichloropropane	ND	0.0050	mg/kg wet
2-Butanone	ND	0.0500	mg/kg wet
2-Chlorotoluene	ND	0.0050	mg/kg wet
2-Hexanone	ND	0.0500	mg/kg wet
4-Chlorotoluene	ND	0.0050	mg/kg wet
4-Isopropyltoluene	ND	0.0050	mg/kg wet
4-Methyl-2-Pentanone	ND	0.0500	mg/kg wet
Acetone	ND	0.0500	mg/kg wet
Benzene	ND	0.0050	mg/kg wet
Bromobenzene	ND	0.0050	mg/kg wet
Bromochloromethane	ND	0.0050	mg/kg wet
Bromodichloromethane	ND	0.0050	mg/kg wet
Bromoform	ND	0.0050	mg/kg wet
Bromomethane	ND	0.0100	mg/kg wet
Carbon Disulfide	ND	0.0050	mg/kg wet

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42542 - 5035

Carbon Tetrachloride	ND	0.0050	mg/kg wet							
Chlorobenzene	ND	0.0050	mg/kg wet							
Chloroethane	ND	0.0100	mg/kg wet							
Chloroform	ND	0.0050	mg/kg wet							
Chloromethane	ND	0.0100	mg/kg wet							
cis-1,2-Dichloroethene	ND	0.0050	mg/kg wet							
cis-1,3-Dichloropropene	ND	0.0050	mg/kg wet							
Dibromochloromethane	ND	0.0050	mg/kg wet							
Dibromomethane	ND	0.0050	mg/kg wet							
Dichlorodifluoromethane	ND	0.0100	mg/kg wet							
Diethyl Ether	ND	0.0050	mg/kg wet							
Di-isopropyl ether	ND	0.0050	mg/kg wet							
Ethyl tertiary-butyl ether	ND	0.0050	mg/kg wet							
Ethylbenzene	ND	0.0050	mg/kg wet							
Hexachlorobutadiene	ND	0.0050	mg/kg wet							
Isopropylbenzene	ND	0.0050	mg/kg wet							
Methyl tert-Butyl Ether	ND	0.0050	mg/kg wet							
Methylene Chloride	ND	0.0250	mg/kg wet							
Naphthalene	ND	0.0050	mg/kg wet							
n-Butylbenzene	ND	0.0050	mg/kg wet							
n-Propylbenzene	ND	0.0050	mg/kg wet							
sec-Butylbenzene	ND	0.0050	mg/kg wet							
Styrene	ND	0.0050	mg/kg wet							
tert-Butylbenzene	ND	0.0050	mg/kg wet							
Tertiary-amyl methyl ether	ND	0.0050	mg/kg wet							
Tetrachloroethene	ND	0.0050	mg/kg wet							
Tetrahydrofuran	ND	0.0200	mg/kg wet							
Toluene	ND	0.0050	mg/kg wet							
trans-1,2-Dichloroethene	ND	0.0050	mg/kg wet							
trans-1,3-Dichloropropene	ND	0.0050	mg/kg wet							
Trichloroethene	ND	0.0050	mg/kg wet							
Trichlorofluoromethane	ND	0.0050	mg/kg wet							
Vinyl Chloride	ND	0.0100	mg/kg wet							
Xylene O	ND	0.0050	mg/kg wet							
Xylene P,M	ND	0.0100	mg/kg wet							

Surrogate: 1,2-Dichloroethane-d4	0.0516		mg/kg wet	0.05000		103	70-130
Surrogate: 4-Bromofluorobenzene	0.0432		mg/kg wet	0.05000		86	70-130
Surrogate: Dibromofluoromethane	0.0514		mg/kg wet	0.05000		103	70-130
Surrogate: Toluene-d8	0.0489		mg/kg wet	0.05000		98	70-130

#### LCS

1,1,1,2-Tetrachloroethane	0.0605	0.0050	mg/kg wet	0.05000		121	70-130
1,1,1-Trichloroethane	0.0561	0.0050	mg/kg wet	0.05000		112	70-130
1,1,2,2-Tetrachloroethane	0.0528	0.0050	mg/kg wet	0.05000		106	40-160

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42542 - 5035

1,1,2-Trichloroethane	0.0506	0.0050	mg/kg wet	0.05000		101	70-130			
1,1-Dichloroethane	0.0519	0.0050	mg/kg wet	0.05000		104	70-130			
1,1-Dichloroethene	0.0540	0.0050	mg/kg wet	0.05000		108	70-130			
1,1-Dichloropropene	0.0505	0.0050	mg/kg wet	0.05000		101	70-130			
1,2,3-Trichlorobenzene	0.0586	0.0050	mg/kg wet	0.05000		117	70-130			
1,2,3-Trichloropropane	0.0508	0.0050	mg/kg wet	0.05000		102	70-130			
1,2,4-Trichlorobenzene	0.0607	0.0050	mg/kg wet	0.05000		121	70-130			
1,2,4-Trimethylbenzene	0.0565	0.0050	mg/kg wet	0.05000		113	70-130			
1,2-Dibromo-3-Chloropropane	0.0490	0.0050	mg/kg wet	0.05000		98	70-130			
1,2-Dibromoethane	0.0561	0.0050	mg/kg wet	0.05000		112	70-130			
1,2-Dichlorobenzene	0.0552	0.0050	mg/kg wet	0.05000		110	70-130			
1,2-Dichloroethane	0.0489	0.0050	mg/kg wet	0.05000		98	70-130			
1,2-Dichloropropane	0.0515	0.0050	mg/kg wet	0.05000		103	70-130			
1,3,5-Trimethylbenzene	0.0567	0.0050	mg/kg wet	0.05000		113	70-130			
1,3-Dichlorobenzene	0.0555	0.0050	mg/kg wet	0.05000		111	70-130			
1,3-Dichloropropane	0.0527	0.0050	mg/kg wet	0.05000		105	70-130			
1,4-Dichlorobenzene	0.0543	0.0050	mg/kg wet	0.05000		109	70-130			
1,4-Dioxane	1.16	0.100	mg/kg wet	1.000		116	70-130			
2,2-Dichloropropane	0.0678	0.0050	mg/kg wet	0.05000		136	70-130			B+
2-Butanone	0.268	0.0500	mg/kg wet	0.2500		107	40-160			
2-Chlorotoluene	0.0542	0.0050	mg/kg wet	0.05000		108	70-130			
2-Hexanone	0.286	0.0500	mg/kg wet	0.2500		114	40-160			
4-Chlorotoluene	0.0539	0.0050	mg/kg wet	0.05000		108	70-130			
4-Isopropyltoluene	0.0548	0.0050	mg/kg wet	0.05000		110	70-130			
4-Methyl-2-Pentanone	0.257	0.0500	mg/kg wet	0.2500		103	40-160			
Acetone	0.286	0.0500	mg/kg wet	0.2500		114	40-160			
Benzene	0.0505	0.0050	mg/kg wet	0.05000		101	70-130			
Bromobenzene	0.0558	0.0050	mg/kg wet	0.05000		112	70-130			
Bromochloromethane	0.0523	0.0050	mg/kg wet	0.05000		105	70-130			
Bromodichloromethane	0.0536	0.0050	mg/kg wet	0.05000		107	70-130			
Bromoform	0.0597	0.0050	mg/kg wet	0.05000		119	40-160			
Bromomethane	0.0540	0.0100	mg/kg wet	0.05000		108	40-160			
Carbon Disulfide	0.0527	0.0050	mg/kg wet	0.05000		105	70-130			
Carbon Tetrachloride	0.0593	0.0050	mg/kg wet	0.05000		119	70-130			
Chlorobenzene	0.0532	0.0050	mg/kg wet	0.05000		106	70-130			
Chloroethane	0.0573	0.0100	mg/kg wet	0.05000		115	40-160			
Chloroform	0.0499	0.0050	mg/kg wet	0.05000		100	70-130			
Chloromethane	0.0415	0.0100	mg/kg wet	0.05000		83	40-160			
cis-1,2-Dichloroethene	0.0515	0.0050	mg/kg wet	0.05000		103	70-130			
cis-1,3-Dichloropropene	0.0571	0.0050	mg/kg wet	0.05000		114	40-160			
Dibromochloromethane	0.0601	0.0050	mg/kg wet	0.05000		120	40-160			
Dibromomethane	0.0503	0.0050	mg/kg wet	0.05000		101	70-130			
Dichlorodifluoromethane	0.0336	0.0100	mg/kg wet	0.05000		67	40-160			
Diethyl Ether	0.0524	0.0050	mg/kg wet	0.05000		105	70-130			



### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42542 - 5035

Di-isopropyl ether	0.0525	0.0050	mg/kg wet	0.05000		105	70-130			
Ethyl tertiary-butyl ether	0.0637	0.0050	mg/kg wet	0.05000		127	70-130			
Ethylbenzene	0.0533	0.0050	mg/kg wet	0.05000		107	70-130			
Hexachlorobutadiene	0.0578	0.0050	mg/kg wet	0.05000		116	40-160			
Isopropylbenzene	0.0623	0.0050	mg/kg wet	0.05000		125	70-130			
Methyl tert-Butyl Ether	0.0558	0.0050	mg/kg wet	0.05000		112	70-130			
Methylene Chloride	0.0501	0.0250	mg/kg wet	0.05000		100	70-130			
Naphthalene	0.0581	0.0050	mg/kg wet	0.05000		116	40-160			
n-Butylbenzene	0.0556	0.0050	mg/kg wet	0.05000		111	70-130			
n-Propylbenzene	0.0545	0.0050	mg/kg wet	0.05000		109	70-130			
sec-Butylbenzene	0.0531	0.0050	mg/kg wet	0.05000		106	70-130			
Styrene	0.0546	0.0050	mg/kg wet	0.05000		109	40-160			
tert-Butylbenzene	0.0565	0.0050	mg/kg wet	0.05000		113	70-130			
Tertiary-amyl methyl ether	0.0615	0.0050	mg/kg wet	0.05000		123	70-130			
Tetrachloroethene	0.0541	0.0050	mg/kg wet	0.05000		108	70-130			
Tetrahydrofuran	0.0518	0.0200	mg/kg wet	0.05000		104	70-130			
Toluene	0.0518	0.0050	mg/kg wet	0.05000		104	70-130			
trans-1,2-Dichloroethene	0.0530	0.0050	mg/kg wet	0.05000		106	70-130			
trans-1,3-Dichloropropene	0.0494	0.0050	mg/kg wet	0.05000		99	70-130			
Trichloroethene	0.0510	0.0050	mg/kg wet	0.05000		102	70-130			
Trichlorofluoromethane	0.0489	0.0050	mg/kg wet	0.05000		98	40-160			
Vinyl Chloride	0.0525	0.0100	mg/kg wet	0.05000		105	70-130			
Xylene O	0.0551	0.0050	mg/kg wet	0.05000		110	70-130			
Xylene P,M	0.111	0.0100	mg/kg wet	0.1000		111	70-130			

Surrogate: 1,2-Dichloroethane-d4	0.0493		mg/kg wet	0.05000		99	70-130			
Surrogate: 4-Bromofluorobenzene	0.0468		mg/kg wet	0.05000		94	70-130			
Surrogate: Dibromofluoromethane	0.0503		mg/kg wet	0.05000		101	70-130			
Surrogate: Toluene-d8	0.0500		mg/kg wet	0.05000		100	70-130			

#### LCS Dup

1,1,1,2-Tetrachloroethane	0.0596	0.0050	mg/kg wet	0.05000		119	70-130	1	20	
1,1,1-Trichloroethane	0.0556	0.0050	mg/kg wet	0.05000		111	70-130	0.8	20	
1,1,2,2-Tetrachloroethane	0.0528	0.0050	mg/kg wet	0.05000		106	40-160	0.1	20	
1,1,2-Trichloroethane	0.0501	0.0050	mg/kg wet	0.05000		100	70-130	0.9	20	
1,1-Dichloroethane	0.0508	0.0050	mg/kg wet	0.05000		102	70-130	2	20	
1,1-Dichloroethene	0.0537	0.0050	mg/kg wet	0.05000		107	70-130	0.6	20	
1,1-Dichloropropene	0.0500	0.0050	mg/kg wet	0.05000		100	70-130	0.9	20	
1,2,3-Trichlorobenzene	0.0571	0.0050	mg/kg wet	0.05000		114	70-130	2	20	
1,2,3-Trichloropropane	0.0510	0.0050	mg/kg wet	0.05000		102	70-130	0.3	20	
1,2,4-Trichlorobenzene	0.0587	0.0050	mg/kg wet	0.05000		117	70-130	3	20	
1,2,4-Trimethylbenzene	0.0548	0.0050	mg/kg wet	0.05000		110	70-130	3	20	
1,2-Dibromo-3-Chloropropane	0.0503	0.0050	mg/kg wet	0.05000		101	70-130	3	20	
1,2-Dibromoethane	0.0555	0.0050	mg/kg wet	0.05000		111	70-130	1	20	
1,2-Dichlorobenzene	0.0532	0.0050	mg/kg wet	0.05000		106	70-130	4	20	

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DK42542 - 5035

1,2-Dichloroethane	0.0483	0.0050	mg/kg wet	0.05000		97	70-130	1	20	
1,2-Dichloropropane	0.0503	0.0050	mg/kg wet	0.05000		101	70-130	2	20	
1,3,5-Trimethylbenzene	0.0551	0.0050	mg/kg wet	0.05000		110	70-130	3	20	
1,3-Dichlorobenzene	0.0537	0.0050	mg/kg wet	0.05000		107	70-130	3	20	
1,3-Dichloropropane	0.0515	0.0050	mg/kg wet	0.05000		103	70-130	2	20	
1,4-Dichlorobenzene	0.0528	0.0050	mg/kg wet	0.05000		106	70-130	3	20	
1,4-Dioxane	1.24	0.100	mg/kg wet	1.000		124	70-130	6	20	
2,2-Dichloropropane	0.0670	0.0050	mg/kg wet	0.05000		134	70-130	1	20	B+
2-Butanone	0.268	0.0500	mg/kg wet	0.2500		107	40-160	0.06	20	
2-Chlorotoluene	0.0522	0.0050	mg/kg wet	0.05000		104	70-130	4	20	
2-Hexanone	0.289	0.0500	mg/kg wet	0.2500		116	40-160	1	20	
4-Chlorotoluene	0.0525	0.0050	mg/kg wet	0.05000		105	70-130	3	20	
4-Isopropyltoluene	0.0535	0.0050	mg/kg wet	0.05000		107	70-130	3	20	
4-Methyl-2-Pentanone	0.266	0.0500	mg/kg wet	0.2500		107	40-160	4	20	
Acetone	0.278	0.0500	mg/kg wet	0.2500		111	40-160	3	20	
Benzene	0.0498	0.0050	mg/kg wet	0.05000		100	70-130	1	20	
Bromobenzene	0.0544	0.0050	mg/kg wet	0.05000		109	70-130	2	20	
Bromochloromethane	0.0517	0.0050	mg/kg wet	0.05000		103	70-130	1	20	
Bromodichloromethane	0.0523	0.0050	mg/kg wet	0.05000		105	70-130	2	20	
Bromoform	0.0595	0.0050	mg/kg wet	0.05000		119	40-160	0.3	20	
Bromomethane	0.0523	0.0100	mg/kg wet	0.05000		105	40-160	3	20	
Carbon Disulfide	0.0521	0.0050	mg/kg wet	0.05000		104	70-130	1	20	
Carbon Tetrachloride	0.0586	0.0050	mg/kg wet	0.05000		117	70-130	1	20	
Chlorobenzene	0.0523	0.0050	mg/kg wet	0.05000		105	70-130	2	20	
Chloroethane	0.0547	0.0100	mg/kg wet	0.05000		109	40-160	5	20	
Chloroform	0.0490	0.0050	mg/kg wet	0.05000		98	70-130	2	20	
Chloromethane	0.0396	0.0100	mg/kg wet	0.05000		79	40-160	5	20	
cis-1,2-Dichloroethene	0.0501	0.0050	mg/kg wet	0.05000		100	70-130	3	20	
cis-1,3-Dichloropropene	0.0554	0.0050	mg/kg wet	0.05000		111	40-160	3	20	
Dibromochloromethane	0.0587	0.0050	mg/kg wet	0.05000		117	40-160	2	20	
Dibromomethane	0.0497	0.0050	mg/kg wet	0.05000		99	70-130	1	20	
Dichlorodifluoromethane	0.0317	0.0100	mg/kg wet	0.05000		63	40-160	6	20	
Diethyl Ether	0.0516	0.0050	mg/kg wet	0.05000		103	70-130	2	20	
Di-isopropyl ether	0.0507	0.0050	mg/kg wet	0.05000		101	70-130	3	20	
Ethyl tertiary-butyl ether	0.0627	0.0050	mg/kg wet	0.05000		125	70-130	1	20	
Ethylbenzene	0.0525	0.0050	mg/kg wet	0.05000		105	70-130	2	20	
Hexachlorobutadiene	0.0565	0.0050	mg/kg wet	0.05000		113	40-160	2	20	
Isopropylbenzene	0.0612	0.0050	mg/kg wet	0.05000		122	70-130	2	20	
Methyl tert-Butyl Ether	0.0550	0.0050	mg/kg wet	0.05000		110	70-130	2	20	
Methylene Chloride	0.0491	0.0250	mg/kg wet	0.05000		98	70-130	2	20	
Naphthalene	0.0587	0.0050	mg/kg wet	0.05000		117	40-160	1	20	
n-Butylbenzene	0.0539	0.0050	mg/kg wet	0.05000		108	70-130	3	20	
n-Propylbenzene	0.0534	0.0050	mg/kg wet	0.05000		107	70-130	2	20	
sec-Butylbenzene	0.0514	0.0050	mg/kg wet	0.05000		103	70-130	3	20	

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

##### Batch DK42542 - 5035

Styrene	0.0534	0.0050	mg/kg wet	0.05000		107	40-160	2	20	
tert-Butylbenzene	0.0550	0.0050	mg/kg wet	0.05000		110	70-130	3	20	
Tertiary-amyl methyl ether	0.0606	0.0050	mg/kg wet	0.05000		121	70-130	2	20	
Tetrachloroethene	0.0512	0.0050	mg/kg wet	0.05000		102	70-130	5	20	
Tetrahydrofuran	0.0544	0.0200	mg/kg wet	0.05000		109	70-130	5	20	
Toluene	0.0508	0.0050	mg/kg wet	0.05000		102	70-130	2	20	
trans-1,2-Dichloroethene	0.0525	0.0050	mg/kg wet	0.05000		105	70-130	0.9	20	
trans-1,3-Dichloropropene	0.0483	0.0050	mg/kg wet	0.05000		97	70-130	2	20	
Trichloroethene	0.0503	0.0050	mg/kg wet	0.05000		101	70-130	1	20	
Trichlorofluoromethane	0.0480	0.0050	mg/kg wet	0.05000		96	40-160	2	20	
Vinyl Chloride	0.0511	0.0100	mg/kg wet	0.05000		102	70-130	3	20	
Xylene O	0.0541	0.0050	mg/kg wet	0.05000		108	70-130	2	20	
Xylene P,M	0.110	0.0100	mg/kg wet	0.1000		110	70-130	1	20	

Surrogate: 1,2-Dichloroethane-d4	0.0493		mg/kg wet	0.05000		99	70-130			
Surrogate: 4-Bromofluorobenzene	0.0474		mg/kg wet	0.05000		95	70-130			
Surrogate: Dibromofluoromethane	0.0506		mg/kg wet	0.05000		101	70-130			
Surrogate: Toluene-d8	0.0496		mg/kg wet	0.05000		99	70-130			

#### MADEP-EPH Extractable Petroleum Hydrocarbons

##### Batch DK42206 - 3546

###### Blank

C19-C36 Aliphatics1	ND	10.0	mg/kg wet							
C9-C18 Aliphatics1	ND	10.0	mg/kg wet							

Surrogate: 1-Chlorooctadecane	1.49		mg/kg wet	2.000		75	40-140			
-------------------------------	------	--	-----------	-------	--	----	--------	--	--	--

###### Blank

C11-C22 Unadjusted Aromatics1	ND	10.0	mg/kg wet							
-------------------------------	----	------	-----------	--	--	--	--	--	--	--

Surrogate: 2-Bromonaphthalene	1.58		mg/kg wet	2.000		79	40-140			
Surrogate: 2-Fluorobiphenyl	1.53		mg/kg wet	2.000		76	40-140			
Surrogate: O-Terphenyl	1.71		mg/kg wet	2.000		85	40-140			

###### Blank

2-Methylnaphthalene	ND	0.008	mg/kg wet							
Acenaphthene	ND	0.008	mg/kg wet							
Acenaphthylene	ND	0.008	mg/kg wet							
Anthracene	ND	0.008	mg/kg wet							
Benzo(a)anthracene	ND	0.008	mg/kg wet							
Benzo(a)pyrene	ND	0.008	mg/kg wet							
Benzo(b)fluoranthene	ND	0.008	mg/kg wet							
Benzo(g,h,i)perylene	ND	0.008	mg/kg wet							
Benzo(k)fluoranthene	ND	0.008	mg/kg wet							
Chrysene	ND	0.008	mg/kg wet							
Dibenzo(a,h)Anthracene	ND	0.008	mg/kg wet							

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### MADEP-EPH Extractable Petroleum Hydrocarbons

##### Batch DK42206 - 3546

Fluoranthene	ND	0.008	mg/kg wet							
Fluorene	ND	0.008	mg/kg wet							
Indeno(1,2,3-cd)Pyrene	ND	0.008	mg/kg wet							
Naphthalene	ND	0.008	mg/kg wet							
Phenanthrene	0.008	0.008	mg/kg wet							
Pyrene	ND	0.008	mg/kg wet							

##### LCS

C19-C36 Aliphatics1	15.7	10.0	mg/kg wet	16.00		98	40-140			
C9-C18 Aliphatics1	9.7	10.0	mg/kg wet	12.00		81	40-140			

Surrogate: 1-Chlorooctadecane	1.66		mg/kg wet	2.000		83	40-140			
-------------------------------	------	--	-----------	-------	--	----	--------	--	--	--

##### LCS

C11-C22 Unadjusted Aromatics1	26.6	10.0	mg/kg wet	34.00		78	40-140			
-------------------------------	------	------	-----------	-------	--	----	--------	--	--	--

Surrogate: 2-Bromonaphthalene	1.66		mg/kg wet	2.000		83	40-140			
Surrogate: 2-Fluorobiphenyl	1.72		mg/kg wet	2.000		86	40-140			
Surrogate: O-Terphenyl	1.97		mg/kg wet	2.000		98	40-140			

##### LCS

2-Methylnaphthalene Breakthrough	0.0		%				0-5			
Naphthalene Breakthrough	0.0		%				0-5			

##### LCS

2-Methylnaphthalene	1.58	0.040	mg/kg wet	2.000		79	40-140			
Acenaphthene	1.60	0.040	mg/kg wet	2.000		80	40-140			
Acenaphthylene	1.84	0.040	mg/kg wet	2.000		92	40-140			
Anthracene	1.80	0.040	mg/kg wet	2.000		90	40-140			
Benzo(a)anthracene	1.79	0.040	mg/kg wet	2.000		90	40-140			
Benzo(a)pyrene	1.60	0.040	mg/kg wet	2.000		80	40-140			
Benzo(b)fluoranthene	1.66	0.040	mg/kg wet	2.000		83	40-140			
Benzo(g,h,i)perylene	1.77	0.040	mg/kg wet	2.000		89	40-140			
Benzo(k)fluoranthene	1.81	0.040	mg/kg wet	2.000		91	40-140			
Chrysene	1.79	0.040	mg/kg wet	2.000		90	40-140			
Dibenzo(a,h)Anthracene	1.75	0.040	mg/kg wet	2.000		88	40-140			
Fluoranthene	1.98	0.040	mg/kg wet	2.000		99	40-140			
Fluorene	1.76	0.040	mg/kg wet	2.000		88	40-140			
Indeno(1,2,3-cd)Pyrene	1.71	0.040	mg/kg wet	2.000		86	40-140			
Naphthalene	1.45	0.040	mg/kg wet	2.000		72	40-140			
Phenanthrene	1.65	0.040	mg/kg wet	2.000		82	40-140			
Pyrene	1.88	0.040	mg/kg wet	2.000		94	40-140			

##### LCS Dup

C19-C36 Aliphatics1	15.3	10.0	mg/kg wet	16.00		95	40-140	3	25	
C9-C18 Aliphatics1	9.3	10.0	mg/kg wet	12.00		78	40-140	4	25	

Surrogate: 1-Chlorooctadecane	1.56		mg/kg wet	2.000		78	40-140			
-------------------------------	------	--	-----------	-------	--	----	--------	--	--	--



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**Quality Control Data**

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

**MADEP-EPH Extractable Petroleum Hydrocarbons**

**Batch DK42206 - 3546**

**LCS Dup**

C11-C22 Unadjusted Aromatics1	26.5	10.0	mg/kg wet	34.00		78	40-140	0.2	25	
Surrogate: 2-Bromonaphthalene	1.59		mg/kg wet	2.000		79	40-140			
Surrogate: 2-Fluorobiphenyl	1.64		mg/kg wet	2.000		82	40-140			
Surrogate: O-Terphenyl	1.94		mg/kg wet	2.000		97	40-140			

**LCS Dup**

2-Methylnaphthalene Breakthrough	0.0		%				0-5		200	
Naphthalene Breakthrough	0.0		%				0-5		200	

**LCS Dup**

2-Methylnaphthalene	1.68	0.040	mg/kg wet	2.000		84	40-140	6	30	
Acenaphthene	1.68	0.040	mg/kg wet	2.000		84	40-140	5	30	
Acenaphthylene	1.95	0.040	mg/kg wet	2.000		97	40-140	6	30	
Anthracene	1.92	0.040	mg/kg wet	2.000		96	40-140	7	30	
Benzo(a)anthracene	1.92	0.040	mg/kg wet	2.000		96	40-140	7	30	
Benzo(a)pyrene	1.72	0.040	mg/kg wet	2.000		86	40-140	7	30	
Benzo(b)fluoranthene	1.76	0.040	mg/kg wet	2.000		88	40-140	6	30	
Benzo(g,h,i)perylene	1.85	0.040	mg/kg wet	2.000		92	40-140	4	30	
Benzo(k)fluoranthene	1.99	0.040	mg/kg wet	2.000		100	40-140	9	30	
Chrysene	1.90	0.040	mg/kg wet	2.000		95	40-140	6	30	
Dibenzo(a,h)Anthracene	1.83	0.040	mg/kg wet	2.000		91	40-140	4	30	
Fluoranthene	2.12	0.040	mg/kg wet	2.000		106	40-140	7	30	
Fluorene	1.86	0.040	mg/kg wet	2.000		93	40-140	5	30	
Indeno(1,2,3-cd)Pyrene	1.79	0.040	mg/kg wet	2.000		89	40-140	4	30	
Naphthalene	1.54	0.040	mg/kg wet	2.000		77	40-140	6	30	
Phenanthrene	1.75	0.040	mg/kg wet	2.000		87	40-140	6	30	
Pyrene	1.99	0.040	mg/kg wet	2.000		100	40-140	6	30	

**Classical Chemistry**

**Batch DK42157 - General Preparation**

**Blank**

Total Organic Carbon (1)	ND	500	mg/kg							
Total Organic Carbon (2)	ND	500	mg/kg							

**LCS**

Total Organic Carbon (1)	8720	500	mg/kg	10010		87	80-120			
Total Organic Carbon (2)	9140	500	mg/kg	10010		91	80-120			

**LCS Dup**

Total Organic Carbon (1)	8450	500	mg/kg	10010		84	80-120	3	25	
Total Organic Carbon (2)	9020	500	mg/kg	10010		90	80-120	1	25	

**8082 Polychlorinated Biphenyls (PCB) / Congeners**

**Batch DK42205 - 3540C**

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**Quality Control Data**

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

**8082 Polychlorinated Biphenyls (PCB) / Congeners**

**Batch DK42205 - 3540C**

**Blank**

BZ#101	ND	0.00027	mg/kg wet
BZ#101 [2C]	ND	0.00027	mg/kg wet
BZ#105	ND	0.00027	mg/kg wet
BZ#105 [2C]	ND	0.00027	mg/kg wet
BZ#118	ND	0.00027	mg/kg wet
BZ#118 [2C]	ND	0.00027	mg/kg wet
BZ#128	ND	0.00027	mg/kg wet
BZ#128 [2C]	ND	0.00027	mg/kg wet
BZ#138	ND	0.00027	mg/kg wet
BZ#138 [2C]	ND	0.00027	mg/kg wet
BZ#153	ND	0.00027	mg/kg wet
BZ#153 [2C]	ND	0.00027	mg/kg wet
BZ#170	ND	0.00027	mg/kg wet
BZ#170 [2C]	ND	0.00027	mg/kg wet
BZ#18	ND	0.00027	mg/kg wet
BZ#18 [2C]	ND	0.00027	mg/kg wet
BZ#180	ND	0.00027	mg/kg wet
BZ#180 [2C]	ND	0.00027	mg/kg wet
BZ#187	ND	0.00027	mg/kg wet
BZ#187 [2C]	ND	0.00027	mg/kg wet
BZ#195	ND	0.00027	mg/kg wet
BZ#195 [2C]	ND	0.00027	mg/kg wet
BZ#206	ND	0.00027	mg/kg wet
BZ#206 [2C]	ND	0.00027	mg/kg wet
BZ#209	ND	0.00027	mg/kg wet
BZ#209 [2C]	ND	0.00027	mg/kg wet
BZ#28	ND	0.00027	mg/kg wet
BZ#28 [2C]	ND	0.00027	mg/kg wet
BZ#44	ND	0.00027	mg/kg wet
BZ#44 [2C]	ND	0.00027	mg/kg wet
BZ#52	ND	0.00027	mg/kg wet
BZ#52 [2C]	ND	0.00027	mg/kg wet
BZ#66	ND	0.00027	mg/kg wet
BZ#66 [2C]	ND	0.00027	mg/kg wet
BZ#8	ND	0.00027	mg/kg wet
BZ#8 [2C]	ND	0.00027	mg/kg wet

Surrogate: Tetrachloro-m-xylene	0.00236		mg/kg wet	0.003333	71	30-150
Surrogate: Tetrachloro-m-xylene [2C]	0.00222		mg/kg wet	0.003333	67	30-150

**LCS**

BZ#101	0.00241	0.00027	mg/kg wet	0.003333	72	40-140
BZ#101 [2C]	0.00216	0.00027	mg/kg wet	0.003333	65	40-140
BZ#105	0.00279	0.00027	mg/kg wet	0.003333	84	40-140

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### 8082 Polychlorinated Biphenyls (PCB) / Congeners

##### Batch DK42205 - 3540C

BZ#105 [2C]	0.00239	0.00027	mg/kg wet	0.003333		72	40-140			
BZ#118	0.00248	0.00027	mg/kg wet	0.003333		75	40-140			
BZ#118 [2C]	0.00220	0.00027	mg/kg wet	0.003333		66	40-140			
BZ#128	0.00246	0.00027	mg/kg wet	0.003333		74	40-140			
BZ#128 [2C]	0.00231	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#138	0.00252	0.00027	mg/kg wet	0.003333		76	40-140			
BZ#138 [2C]	0.00227	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#153	0.00238	0.00027	mg/kg wet	0.003333		71	40-140			
BZ#153 [2C]	0.00222	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#170	0.00248	0.00027	mg/kg wet	0.003333		74	40-140			
BZ#170 [2C]	0.00231	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#18	0.00270	0.00027	mg/kg wet	0.003333		81	40-140			
BZ#18 [2C]	0.00258	0.00027	mg/kg wet	0.003333		77	40-140			
BZ#180	0.00248	0.00027	mg/kg wet	0.003333		74	40-140			
BZ#180 [2C]	0.00232	0.00027	mg/kg wet	0.003333		70	40-140			
BZ#187	0.00230	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#187 [2C]	0.00217	0.00027	mg/kg wet	0.003333		65	40-140			
BZ#195	0.00241	0.00027	mg/kg wet	0.003333		72	40-140			
BZ#195 [2C]	0.00229	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#206	0.00237	0.00027	mg/kg wet	0.003333		71	40-140			
BZ#206 [2C]	0.00221	0.00027	mg/kg wet	0.003333		66	40-140			
BZ#209	0.00226	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#209 [2C]	0.00212	0.00027	mg/kg wet	0.003333		64	40-140			
BZ#28	0.00242	0.00027	mg/kg wet	0.003333		73	40-140			
BZ#28 [2C]	0.00259	0.00027	mg/kg wet	0.003333		78	40-140			
BZ#44	0.00234	0.00027	mg/kg wet	0.003333		70	40-140			
BZ#44 [2C]	0.00220	0.00027	mg/kg wet	0.003333		66	40-140			
BZ#52	0.00270	0.00027	mg/kg wet	0.003333		81	40-140			
BZ#52 [2C]	0.00263	0.00027	mg/kg wet	0.003333		79	40-140			
BZ#66	0.00264	0.00027	mg/kg wet	0.003333		79	40-140			
BZ#66 [2C]	0.00222	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#8	0.00243	0.00027	mg/kg wet	0.003333		73	40-140			
BZ#8 [2C]	0.00258	0.00027	mg/kg wet	0.003333		77	40-140			

Surrogate: Tetrachloro-m-xylene	0.00228		mg/kg wet	0.003333		68	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	0.00216		mg/kg wet	0.003333		65	30-150			

##### LCS Dup

BZ#101	0.00246	0.00027	mg/kg wet	0.003333		74	40-140	2	30	
BZ#101 [2C]	0.00240	0.00027	mg/kg wet	0.003333		72	40-140	10	30	
BZ#105	0.00301	0.00027	mg/kg wet	0.003333		90	40-140	7	30	
BZ#105 [2C]	0.00258	0.00027	mg/kg wet	0.003333		77	40-140	8	30	
BZ#118	0.00269	0.00027	mg/kg wet	0.003333		81	40-140	8	30	
BZ#118 [2C]	0.00238	0.00027	mg/kg wet	0.003333		71	40-140	8	30	
BZ#128	0.00274	0.00027	mg/kg wet	0.003333		82	40-140	11	30	

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### 8082 Polychlorinated Biphenyls (PCB) / Congeners

#### Batch DK42205 - 3540C

BZ#128 [2C]	0.00256	0.00027	mg/kg wet	0.003333		77	40-140	10	30	
BZ#138	0.00274	0.00027	mg/kg wet	0.003333		82	40-140	9	30	
BZ#138 [2C]	0.00250	0.00027	mg/kg wet	0.003333		75	40-140	9	30	
BZ#153	0.00259	0.00027	mg/kg wet	0.003333		78	40-140	9	30	
BZ#153 [2C]	0.00242	0.00027	mg/kg wet	0.003333		73	40-140	9	30	
BZ#170	0.00268	0.00027	mg/kg wet	0.003333		80	40-140	8	30	
BZ#170 [2C]	0.00249	0.00027	mg/kg wet	0.003333		75	40-140	7	30	
BZ#18	0.00301	0.00027	mg/kg wet	0.003333		90	40-140	11	30	
BZ#18 [2C]	0.00290	0.00027	mg/kg wet	0.003333		87	40-140	12	30	
BZ#180	0.00268	0.00027	mg/kg wet	0.003333		80	40-140	8	30	
BZ#180 [2C]	0.00253	0.00027	mg/kg wet	0.003333		76	40-140	8	30	
BZ#187	0.00251	0.00027	mg/kg wet	0.003333		75	40-140	9	30	
BZ#187 [2C]	0.00238	0.00027	mg/kg wet	0.003333		72	40-140	10	30	
BZ#195	0.00257	0.00027	mg/kg wet	0.003333		77	40-140	6	30	
BZ#195 [2C]	0.00246	0.00027	mg/kg wet	0.003333		74	40-140	7	30	
BZ#206	0.00252	0.00027	mg/kg wet	0.003333		76	40-140	6	30	
BZ#206 [2C]	0.00240	0.00027	mg/kg wet	0.003333		72	40-140	8	30	
BZ#209	0.00244	0.00027	mg/kg wet	0.003333		73	40-140	7	30	
BZ#209 [2C]	0.00231	0.00027	mg/kg wet	0.003333		69	40-140	9	30	
BZ#28	0.00276	0.00027	mg/kg wet	0.003333		83	40-140	13	30	
BZ#28 [2C]	0.00286	0.00027	mg/kg wet	0.003333		86	40-140	10	30	
BZ#44	0.00267	0.00027	mg/kg wet	0.003333		80	40-140	13	30	
BZ#44 [2C]	0.00246	0.00027	mg/kg wet	0.003333		74	40-140	11	30	
BZ#52	0.00300	0.00027	mg/kg wet	0.003333		90	40-140	10	30	
BZ#52 [2C]	0.00292	0.00027	mg/kg wet	0.003333		88	40-140	11	30	
BZ#66	0.00288	0.00027	mg/kg wet	0.003333		86	40-140	9	30	
BZ#66 [2C]	0.00247	0.00027	mg/kg wet	0.003333		74	40-140	10	30	
BZ#8	0.00275	0.00027	mg/kg wet	0.003333		82	40-140	12	30	
BZ#8 [2C]	0.00283	0.00027	mg/kg wet	0.003333		85	40-140	9	30	

Surrogate: Tetrachloro-m-xylene	0.00259		mg/kg wet	0.003333		78	30-150			
Surrogate: Tetrachloro-m-xylene [2C]	0.00247		mg/kg wet	0.003333		74	30-150			



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten

Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**Notes and Definitions**

Z-08	See Attached
U	Analyte included in the analysis, but not detected
Q	Calibration required quadratic regression (Q).
P	Percent difference between primary and confirmation results exceeds 40% (P).
LC	Lower value is used due to matrix interferences (LC).
D	Diluted.
CD+	Continuing Calibration %Diff/Drift is above control limit (CD+).
B+	Blank Spike recovery is above upper control limit (B+).
B	Present in Method Blank (B).
ND	Analyte NOT DETECTED at or above the MRL (LOQ), LOD for DoD Reports, MDL for J-Flagged Analytes
dry	Sample results reported on a dry weight basis
RPD	Relative Percent Difference
MDL	Method Detection Limit
MRL	Method Reporting Limit
LOD	Limit of Detection
LOQ	Limit of Quantitation
DL	Detection Limit
I/V	Initial Volume
F/V	Final Volume
§	Subcontracted analysis; see attached report
1	Range result excludes concentrations of surrogates and/or internal standards eluting in that range.
2	Range result excludes concentrations of target analytes eluting in that range.
3	Range result excludes the concentration of the C9-C10 aromatic range.
Avg	Results reported as a mathematical average.
NR	No Recovery
[CALC]	Calculated Analyte
SUB	Subcontracted analysis; see attached report
RL	Reporting Limit
EDL	Estimated Detection Limit
MF	Membrane Filtration
MPN	Most Probable Number
TNTC	Too numerous to Count
CFU	Colony Forming Units

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24K0950

**ESS LABORATORY CERTIFICATIONS AND ACCREDITATIONS**

**ENVIRONMENTAL**

Rhode Island Potable and Non Potable Water: LAI00179  
<http://www.health.ri.gov/find/labs/analytical/ESS.pdf>

Connecticut Potable and Non Potable Water, Solid and Hazardous Waste: PH-0750  
[http://www.ct.gov/dph/lib/dph/environmental\\_health/environmental\\_laboratories/pdf/OutOfStateCommercialLaboratories.pdf](http://www.ct.gov/dph/lib/dph/environmental_health/environmental_laboratories/pdf/OutOfStateCommercialLaboratories.pdf)

Maine Potable and Non Potable Water, and Solid and Hazardous Waste: RI00002  
<http://www.maine.gov/dhhs/mecdc/environmental-health/dwp/partners/labCert.shtml>

Massachusetts Potable and Non Potable Water: M-RI002  
<http://public.dep.state.ma.us/Labcert/Labcert.aspx>

New Hampshire (NELAP accredited) Potable and Non Potable Water, Solid and Hazardous Waste: 2424  
<http://des.nh.gov/organization/divisions/water/dwgb/nhelap/index.htm>

New York (NELAP accredited) Non Potable Water, Solid and Hazardous Waste: 11313  
<http://www.wadsworth.org/labcert/elap/comm.html>

New Jersey (NELAP accredited) Non Potable Water, Solid and Hazardous Waste: RI006  
[http://datamine2.state.nj.us/DEP\\_OPRA/OpraMain/pi\\_main?mode=pi\\_by\\_site&sort\\_order=PI\\_NAMEA&Select+a+Site:=58715](http://datamine2.state.nj.us/DEP_OPRA/OpraMain/pi_main?mode=pi_by_site&sort_order=PI_NAMEA&Select+a+Site:=58715)

Pennsylvania: 68-01752  
<http://www.dep.pa.gov/Business/OtherPrograms/Labs/Pages/Laboratory-Accreditation-Program.aspx>

Shawn Morrell  
ESS Laboratory  
185 Frances Ave.  
Cranston, RI 02910

November 26, 2024

Dear Shawn Morrell,

The enclosed analytical results have been obtained using the EPA/600/R-93/116 method. Calibrated Visual Estimate (CVE) is used by Aerobiology for the determination of the percentage of asbestos and other components in the sample. The sample preparation technique used was in accordance with the US EPA office of Environmental Evaluation and Measurement - Region 1 requirements. This technique involves the elimination of interfering particles through the following steps: homogenization of the sample; separation of different fractions and examination under the stereomicroscope.


The quality control data related to the samples analyzed is available upon client's written request. Aerobiology Laboratory Associates, Inc., assumes no responsibility for potential sample contamination that may have occurred during the sample collection process or erroneous data provided by the client. As such, these results apply to the sample(s) as received.

The enclosed results may not be used under any circumstances as product endorsement by any US government agency including NIST/NVLAP.

All Laboratory records are retained for at least three years unless otherwise directed in writing by the client. The actual samples are retained for a period of two months and written request is necessary in order to be retained for a longer period of time. All analytical results and records are considered strictly confidential and will not be released under any circumstances to anyone except the actual client. The analytical results included in this report apply only to the items tested. This report may not be reproduced, except in its entirety, without the permission of Aerobiology Laboratory Associates, Inc., Laboratory Manager.

If you have any questions please contact the Optical Manager or the Laboratory Manager.

Sincerely,



Aimee Cormier, Laboratory Manager

Enclosure:

LAB BATCH ID: S 137373 CLIENT PROJECT ID: 24K0950

Client Ref: MA

CT ID# PH-0209; MA ID# AA000251; ME ID# LB-055; NVLAP Lab Code 200090-0; RI ID # PLM-00150; VT ID# AL254362.

# Aerobiology Laboratory Associates, Inc.

Client #: 2118  
Client Project: 24K0950  
Client Reference: MA  
Client Name: ESS Laboratory  
Method: EPA/600/R-93/116; ENV.EVAL. and MEAS.- REGION 1 Requirements

Batch: S 137373  
Date Sampled: 11/19/2024  
Date Received: 11/25/2024  
Date Analyzed: 11/25/2024  
Date of Report: 11/26/2024

Sample ID	Color	ASBESTOS %						NON-ASBESTOS %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
24K0950-01	Gray	0	0	0	0	0	0	0	5	5	0	0	0	90

Description: Soil

Location: N/A

Comments:

Analyzed: Yes

Sample ID	Color	ASBESTOS %						NON-ASBESTOS %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
24K0950-02	Gray	0	0	0	0	0	0	0	2	2	0	0	0	96

Description: Soil

Location: N/A

Comments:


Analyzed: Yes

Asbestos Codes: CHR = Chrysotile AMO = Amosite CRO = Crocidolite ACT = Actinolite TRE = Tremolite ANT = Anthophyllite

Non-Asbestos Codes: FBG = Fiberglass MNW = Mineral Wool CEL = Cellulose HAR = Hair SYN = Synthetic OTH = Other NON = Non-Fibrous Minerals

Note: To create a unique lab sample ID, use the Batch # and the Sample ID (example: [Batch #] - [Sample ID]).

\* All results are in percentage

  
Dan Pine, Analyst



Client Name: ESS Laboratory

Client Project #: 24K0950

Client Reference: MA

Batch: *SA* 137373

Date Received: 11/25/2024

Date Due: 11/26/2024

Stop on first pos: Yes or No

Batch: *S* 137373

Batch: 137373		Stereo Scope					Optical Properties					RI		Asbestos Percent					Non-Asbestos Percent									
Sample ID	Description	Analyst	SSAPE	Color	Homogeneity	Texture	Friable	Morphology	Extinction	Elongation	Sign of	Birefringence	Pleochroism	Parallel	Perpendicular	Chrysotile	Amosite	Crocidolite	Tremolite	Anthophyllite	Actinolite	Fiberglass	Mineral Wool	Cellulose	Hair	Synthetic	Other	Non-Fibrous
24K0950-01	Soil	DB	06	Y	Y	M	+	Y															H	W				
24K0950-02	Soil	U	06	Y	Y	M	+	Y															5	5				90

Analyzed By / Date:

*Darlene*  
11/25/24  
at station 4

QC By / Date:

*[Signature]*  
11/26/24

Fax, Email, Verbal Results By / Date:

# of Samples:

2

Comments:

**24K0950**

*S137373*

**SENDING LABORATORY**

ESS Laboratory  
185 Frances Avenue  
Cranston, RI 02910  
Phone: (401) 461-7181

**RECEIVING LABORATORY**

Aerobiology Boston  
22 Cummings Park  
Woburn, MA 01801  
Phone: (781) 935-3212

**PROJECT NOTES**

Project Name: 24K0950

Project Location: MA

Project PO Number: 23144B

Due Date ~~2 Day TAT~~ *Due 11/26/24 J.C.*

Send Report To: smorrell@thielsch.com; MDean@thielsch.com; ESSProjectManagement@thielsch.com

Sample ID: 24K0950-01

Sampled: 11/19/24 09:30

Sample Matrix: Sediment

Sample Type: Grab/Composite

Sampled By: Client

Container - Preservation: 1 x 4 oz. Jar - Unpres

Hold Time Expires 11/20/2024

Analysis Asbestos

Analysis Comments: N/A

Sample ID: 24K0950-02

Sampled: 11/19/24 10:30

Sample Matrix: Sediment

Sample Type: Grab/Composite

Sampled By: Client

Container - Preservation: 1 x 4 oz. Jar - Unpres

Hold Time Expires 11/20/2024

Analysis Asbestos

Analysis Comments: N/A

Released By

Date

Received By


Date

Released By

Date

Received By

Date

 <b>Thielsch</b> DIVISION OF THE RISE GROUP	195 Frances Avenue Cranston RI, 02910 Phone: (401)-467-6454 Fax: (401)-467-2398 <a href="http://cts.thielsch.com">cts.thielsch.com</a> <i>Let's Build a Solid Foundation</i>	Client Information:	Project Information:
		ESS Laboratory Cranston, RI 401-467-7181 Project Contact: ESS Project Management Collected By: Client	24K0950  Project Number: 24K0950 Summary Page: 1 of 1 Report Date: 11.26.24

LABORATORY TESTING DATA SHEET, Report No.: 7424-L-274


Material Source	Sample ID	Depth (ft)	Laboratory No.	Identification Tests										Proctor / CBR / Permeability Tests							Laboratory Log and Soil Description
				As Rcvd Moisture Content %	LL %	PL %	OD LL	Gravel %	Sand %	Fines %	Org. %	pH	9 <sub>d</sub> MAX (pcf) W <sub>opt</sub> (%)	9 <sub>d</sub> MAX (pcf) W <sub>opt</sub> (%) (Corr.)	Dry unit wt. (pcf)	Test Moisture Content %	Target Test Setup as % of Proctor	CBR @ 0.1"	CBR @ 0.2"	Permeability cm/sec	
				D2216	D4318			D6913			D2974	D4792	D1557								
Jar	24K0950-01	-	24K0950-01					0.0	62.7	37.3											Dark Brown Organic silty sand
Jar	24K0950-02	-	24K0950-02					0.0	70.6	29.4											Dark Brown Organic silty sand

Date Received: 11.25.24
 Reviewed By: 
 Date Reviewed: 11.26.24

This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.  
This report shall not be reproduced, except in full, without prior written approval from the Agency, as defined in ASTM E329.

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspected and/or tested. No warranty, expressed or implied, is made.

## Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	0.7	5.9	56.1	37.3	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#4	100.0		
#10	99.3		
#20	97.5		
#40	93.4		
#60	78.8		
#100	57.6		
#200	37.3		

\* (no specification provided)

### Soil Description

Dark Brown Organic silty sand

PL= NP      Atterberg Limits      LL= NV      PI= NP  
Coefficients  
D<sub>90</sub>= 0.3615      D<sub>85</sub>= 0.3019      D<sub>60</sub>= 0.1599  
D<sub>50</sub>= 0.1182      D<sub>30</sub>=      D<sub>15</sub>=  
D<sub>10</sub>=      C<sub>u</sub>=      C<sub>c</sub>=

Classification  
USCS= SM      AASHTO= A-4(0)

Remarks  
Sample consisted of Organic material larger than the #200, little to none is considered mineral. Sample received with standing water.

Source of Sample: Jar  
Sample Number: 24K0950-01

Date: 11/26/24

Thielsch Engineering Inc.

Cranston, RI

Client: ESS Laboratory  
Project: 24K0950

Project No: 24K0950


Fig. 24K0950-01

Tested By: AB/MCS

Checked By: Kris Roland

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspected and/or tested. No warranty, expressed or implied, is made.

## Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	1.0	5.2	64.4	29.4	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
#4	100.0		
#10	99.0		
#20	97.4		
#40	93.8		
#60	79.0		
#100	55.8		
#200	29.4		

\* (no specification provided)

### Soil Description

Dark Brown Organic silty sand

PL= NP      Atterberg Limits      LL= NV      PI= NP  
Coefficients  
D<sub>90</sub>= 0.3534      D<sub>85</sub>= 0.2973      D<sub>60</sub>= 0.1648  
D<sub>50</sub>= 0.1298      D<sub>30</sub>= 0.0761      D<sub>15</sub>=  
D<sub>10</sub>=      C<sub>u</sub>=      C<sub>c</sub>=

Classification  
USCS= SM      AASHTO= A-2-4(0)

Remarks  
Sample consisted of Organic material larger than the #200, little to none is considered mineral. Sample received with standing water.

Source of Sample: Jar  
Sample Number: 24K0950-02

Date: 11/26/24

Thielsch Engineering Inc.

Cranston, RI

Client: ESS Laboratory  
Project: 24K0950

Project No: 24K0950

Fig. 24K0950-02

Tested By: AB/MCS

Checked By: Rebecca Roth



# ESS Laboratory Sample and Cooler Receipt Checklist

Client: Horsley Witten Group - TJM

ESS Project ID: 24K0950

Date Received: 11/21/2024

Shipped/Delivered Via: ESS Courier

Project Due Date: 11/25/2024

Days for Project: 2 Day

1. Air bill manifest present? ☐ No

Air No.: NA

2. Were custody seals present? ☐ No

3. Is radiation count <100 CPM? ☐ Yes

4. Is a Cooler Present? ☐ Yes

Temp: 2 Iced with: Ice

5. Was COC signed and dated by client? ☐ Yes

6. Does COC match bottles? ☐ Yes

7. Is COC complete and correct? ☐ Yes

8. Were samples received intact? ☐ Yes

9. Were labs informed about short holds & rushes? ☒ Yes / No / NA

10. Were any analyses received outside of hold time? ☒ Yes / No

11. Any Subcontracting needed? Yes / ☒ No

ESS Sample IDs: \_\_\_\_\_

Analysis: \_\_\_\_\_

TAT: \_\_\_\_\_

12. Were VOAs received? ☒ Yes / No

a. Air bubbles in aqueous VOAs? ☒ Yes / No

b. Does methanol cover soil completely? ☒ Yes / No / NA

13. Are the samples properly preserved? ☒ Yes / No

a. If metals preserved upon receipt: Date: \_\_\_\_\_

b. If dissolved metals are requested, are they: Yes / No Field Filtered

c. Low Level VOA vials frozen: Date: \_\_\_\_\_

Time: \_\_\_\_\_ By/Acid Lot#: \_\_\_\_\_

Yes / No To Be Lab Filtered

Time: \_\_\_\_\_ By: client

"within 20 hours"

Sample Receiving Notes:

DI vial for sample 1 Broken in cooler upon receipt

14. Was there a need to contact Project Manager? Yes / ☒ No

a. Was there a need to contact the client? Yes / ☒ No

Who was contacted? \_\_\_\_\_ Date: \_\_\_\_\_

Time: \_\_\_\_\_ By: \_\_\_\_\_

Resolution: \_\_\_\_\_

Sample Number	Container ID	Proper Container	Air Bubbles Present	Sufficient Volume	Container Type	Preservative	Record pH (Cyanide and 608 Pesticides)
1	618286	Yes	N/A	Yes	VOA Vial	MeOH	
1	618288	Yes	N/A	Yes	VOA Vial	DI Water	
1	<del>618289</del>	<del>Yes</del>	<del>N/A</del>	<del>Yes</del>	<del>VOA Vial</del>	<del>DI Water</del>	
1	618292	Yes	N/A	Yes	4 oz. Jar	NP	
1	618296	Yes	N/A	Yes	8 oz jar	NP	
1	618297	Yes	N/A	Yes	8 oz jar	NP	
1	618298	Yes	N/A	Yes	8 oz jar	NP	
1	618299	Yes	N/A	Yes	8 oz jar	NP	
1	618480	Yes	N/A	Yes	Driller Jar	NP	
2	618287	Yes	N/A	Yes	VOA Vial	MeOH	
2	618290	Yes	N/A	Yes	VOA Vial	DI Water	
2	618291	Yes	N/A	Yes	VOA Vial	DI Water	
2	618294	Yes	N/A	Yes	4 oz. Jar	NP	
2	618300	Yes	N/A	Yes	8 oz jar	NP	
2	618301	Yes	N/A	Yes	8 oz jar	NP	
2	618302	Yes	N/A	Yes	8 oz jar	NP	
2	618303	Yes	N/A	Yes	8 oz jar	NP	
2	618481	Yes	N/A	Yes	Driller Jar	NP	

ESS Laboratory Sample and Cooler Receipt Checklist

Client: Horsley Witten Group - TJM

ESS Project ID: 24K0950  
Date Received: 11/21/2024

2nd Review

Were all containers scanned into storage/lab?

Are barcode labels on correct containers?

Are all Flashpoint stickers attached/container ID # circled?

Are all Hex Chrome stickers attached?

Are all QC stickers attached?

Are VOA stickers attached if bubbles noted?

Initials RB  
Yes / No Yes  
Yes / No / NA NA  
Yes / No / NA NA  
Yes / No / NA NA  
Yes / No / NA NA

Completed

By: [Signature]

Reviewed

By: [Signature]

Date & Time: 11/21/24 18:34  
Date & Time: 11/21/24 18:39

SENDING LABORATORY

ESS Laboratory  
185 Frances Avenue  
Cranston, RI 02910  
Phone: (401) 461-7181

RECEIVING LABORATORY

Aerobiology Boston  
22 Cummings Park  
Woburn, MA 01801  
Phone: (781) 935-3212

PROJECT NOTES

Project Name: 24K0950

Project Location: MA

Project PO Number: 23144B

Due Date ~~2 Day~~ TAT Due 11/26/24 J.C. .

Send Report To: smorrell@thielsch.com; MDean@thielsch.com; ESSProjectManagement@thielsch.com

Sample ID: 24K0950-01

Sample Matrix: Sediment

Sampled: 11/19/24 09:30

Sample Type: Grab/Composite

Sampled By: Client

Container - Preservation: 1 x 4 oz. Jar - Unpres

Analysis Asbestos

Analysis Comments: N/A

Hold Time Expires 11/20/2024

Sample ID: 24K0950-02

Sample Matrix: Sediment

Sampled: 11/19/24 10:30

Sample Type: Grab/Composite

Sampled By: Client

Container - Preservation: 1 x 4 oz. Jar - Unpres

Analysis Asbestos

Analysis Comments: N/A

Hold Time Expires 11/20/2024

Released By

Date

11/25/24 8:40

Received By

Date

11/25/24 8:40 A

Released By

Date

11/25/24 12:37p

Received By

Date

11-25-24 12:37

#### SENDING LABORATORY

ESS Laboratory  
185 Frances Avenue  
Cranston, RI 02910  
Phone: (401) 461-7181

#### RECEIVING LABORATORY

CTS  
195 Frances Avenue  
Cranston, RI 02910  
Phone: (401) 467-6454

#### PROJECT NOTES

**Project Name:** 24K0950

**Project Location:** MA

**Project PO Number:** 23144B

**Due Date** 2 Day TAT

**Send Report To:** smorrell@thielsch.com; MDean@thielsch.com; ESSProjectManagement@thielsch.com

**Sample ID:** 24K0950-01

**Sample Matrix:** Sediment

**Sampled:** 11/19/24 09:30

**Sample Type:** Grab/Composite

**Sampled By:** Client

**Container - Preservation:** 1 x 8 oz. Jar - Unpres

**Analysis** Grain Size Analysis

**Analysis Comments:** N/A

**Hold Time Expires** 12/3/2024

**Sample ID:** 24K0950-02

**Sample Matrix:** Sediment

**Sampled:** 11/19/24 10:30

**Sample Type:** Grab/Composite

**Sampled By:** Client

**Container - Preservation:** 1 x 1L Amber - HCl

**Analysis** Grain Size Analysis

**Analysis Comments:** N/A

**Hold Time Expires** 12/3/2024

Released By

Date

Received By

Date

Released By

Date

Received By

Date



185 Frances Avenue  
Cranston, RI 02921  
Phone: 401-461-7181  
[Redacted]  
[www.esslaboratory.com](http://www.esslaboratory.com)

## CHAIN OF CUSTODY

ESS Lab # 24K 0950 Page      of     

Turn Time ☐ >5 ☐ 5 ☐ 4 ☐ 3 ☒ 2 ☐ 1 ☐ Same Day

Regulatory State:                      Criteria:                     

Is this project for any of the following?:

☐ CT RCP ☐ MA MCP ☐ RGP ☐ Permit ☒ 401 WQ

ELECTRONIC DELIVERABLES (Final Reports are PDF)

☐ Limit Checker ☐ State Forms ☐ EQulS  
☒ Excel ☐ Hard Copy ☐ Enviro Data  
☐ CLP-Like Package ☐ Other (Specify) →

### CLIENT INFORMATION

Client: Horsley Witten Group  
Address: 112 Water St. 6<sup>th</sup>  
Floor, Boston, MA, 02109  
Phone: 857-263-8193  
Email Distribution List: nprice@horsleywitten.com  
jproctor@horsleywitten.com  
carstrong@horsleywitten.com

### PROJECT INFORMATION

Project Name: Squannacook River Dam Removal II  
Project Location: Grafton, MA  
Project Number: 23144B  
Project Manager: Jonas Proctor / HW  
Bill to: torciuch@horsleywitten.com  
PO#:                       
Quote#:                     

Client acknowledges that sampling is compliant with all EPA / State regulatory programs

### REQUESTED ANALYSES

PCBs	EPH	TOC	% Water	PAHs	As	Cd	Cu	Pb	Hg	Ni	Zn	Grain Size	VOCs High	VOCs Low	Asbestos	Total Number of Bottles
✓	✓		✓	✓	✓	✓	✓	✓	✓	✓	✓	✓			✓	4
		✓														1
												✓				1
✓	✓		✓	✓	✓	✓	✓	✓	✓	✓	✓					4
		✓														1
													✓			2
														✓		1
													✓			2
														✓		1

ESS Lab ID	Collection Date	Collection Time	Sample Type	Sample Matrix	Sample ID
1	11/19	9:30	Composite	Sediment	DS
1					DS
1					DS
2		10:30			US
2					US
2					US
2			Grab		DS VOC
1					DS VOC
2					US VOC
2					US VOC

Container Type: AC-Air Cassette AG-Amber Glass B-BOD Bottle C-Cubitainer J-Jar O-Other P-Poly S-Sterile V-Vial

Container Volume: 1-100 mL 2-2.5 gal 3-250 mL 4-300 mL 5-500 mL 6-1L 7-VOA 8-2 oz 9-4 oz 10-8 oz 11-Other\*

Preservation Code: 1-Non Preserved 2-HCl 3-H2SO4 4-HNO3 5-NaOH 6-Methanol 7-Na2S2O3 8-ZnAcc, NaOH 9-NH4Cl 10-DI H2O 11-Other\*

Sampled by: HW

Chain needs to be filled out neatly and completely for on time delivery.

Laboratory Use Only

Comments: \* Please specify "Other" preservative and containers types in this space

Cooler Temperature (°C): 2.0

35 mL Vial - DI preserved VOC samples frozen  
DI water within 20 hours of sampling.  
15 mL methanol - Please make sure analysis meets reporting limits for 400 ppb

All samples submitted are subject to ESS Laboratory's payment terms and conditions.

Dissolved Filtration

☐ Lab Filter

Relinquished by (Signature)	Date	Time	Received by (Signature)	Relinquished by (Signature)	Date	Time	Received by (Signature)
<u>[Signature]</u>	11/21	13:52	<u>AO</u>	<u>AO</u>	11/21/24	16:24	<u>[Signature]</u>
Relinquished by (Signature)	Date	Time	Received by (Signature)	Relinquished by (Signature)	Date	Time	Received by (Signature)



Shawn Morrell  
ESS Laboratory  
185 Frances Ave.  
Cranston, RI 02910

November 26, 2024

Dear Shawn Morrell,

The enclosed analytical results have been obtained using the EPA/600/R-93/116 method. Calibrated Visual Estimate (CVE) is used by Aerobiology for the determination of the percentage of asbestos and other components in the sample. The sample preparation technique used was in accordance with the US EPA office of Environmental Evaluation and Measurement - Region 1 requirements. This technique involves the elimination of interfering particles through the following steps: homogenization of the sample; separation of different fractions and examination under the stereomicroscope.


The quality control data related to the samples analyzed is available upon client's written request. Aerobiology Laboratory Associates, Inc., assumes no responsibility for potential sample contamination that may have occurred during the sample collection process or erroneous data provided by the client. As such, these results apply to the sample(s) as received.

The enclosed results may not be used under any circumstances as product endorsement by any US government agency including NIST/NVLAP.

All Laboratory records are retained for at least three years unless otherwise directed in writing by the client. The actual samples are retained for a period of two months and written request is necessary in order to be retained for a longer period of time. All analytical results and records are considered strictly confidential and will not be released under any circumstances to anyone except the actual client. The analytical results included in this report apply only to the items tested. This report may not be reproduced, except in its entirety, without the permission of Aerobiology Laboratory Associates, Inc., Laboratory Manager.

If you have any questions please contact the Optical Manager or the Laboratory Manager.

Sincerely,



Aimee Cormier, Laboratory Manager

Enclosure:

LAB BATCH ID: S 137373 CLIENT PROJECT ID: 24K0950

Client Ref: MA

CT ID# PH-0209; MA ID# AA000251; ME ID# LB-055; NVLAP Lab Code 200090-0; RI ID # PLM-00150; VT ID# AL254362.

# Aerobiology Laboratory Associates, Inc.

Client #: 2118  
Client Project: 24K0950  
Client Reference: MA  
Client Name: ESS Laboratory  
Method: EPA/600/R-93/116; ENV.EVAL. and MEAS.- REGION 1 Requirements

Batch: S 137373  
Date Sampled: 11/19/2024  
Date Received: 11/25/2024  
Date Analyzed: 11/25/2024  
Date of Report: 11/26/2024

Sample ID	Color	ASBESTOS %						NON-ASBESTOS %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
24K0950-01	Gray	0	0	0	0	0	0	0	5	5	0	0	0	90

Description: Soil

Location: N/A

Comments:

Analyzed: Yes

Sample ID	Color	ASBESTOS %						NON-ASBESTOS %						
		CHR	AMO	CRO	ACT	TRE	ANT	FBG	MNW	CEL	HAR	SYN	OTH	NON
24K0950-02	Gray	0	0	0	0	0	0	0	2	2	0	0	0	96

Description: Soil

Location: N/A

Comments:


Analyzed: Yes

Asbestos Codes: CHR = Chrysotile AMO = Amosite CRO = Crocidolite ACT = Actinolite TRE = Tremolite ANT = Anthophyllite

Non-Asbestos Codes: FBG = Fiberglass MNW = Mineral Wool CEL = Cellulose HAR = Hair SYN = Synthetic OTH = Other NON = Non-Fibrous Minerals

Note: To create a unique lab sample ID, use the Batch # and the Sample ID (example: [Batch #] - [Sample ID]).

\* All results are in percentage

  
Dan Pine, Analyst

Client Name: ESS Laboratory

Client Project #: 24K0950

Client Reference: MA

Batch: *SA* 137373

Date Received: 11/25/2024

Date Due: 11/26/2024

Stop on first pos: Yes or No

Batch: *S* 137373

Batch: 137373		Stereo Scope					Optical Properties					RI		Asbestos Percent					Non-Asbestos Percent									
Sample ID	Description	Analyst	SSAPE	Color	Homogeneity	Texture	Friable	Morphology	Extinction	Elongation	Sign of	Birefringence	Pleochroism	Parallel	Perpendicular	Chrysotile	Amosite	Crocidolite	Tremolite	Anthophyllite	Actinolite	Fiberglass	Mineral Wool	Cellulose	Hair	Synthetic	Other	Non-Fibrous
24K0950-01	Soil	DB	06	Y	Y	M	+	Y															H	W				
24K0950-02	Soil	U	06	Y	Y	M	+	Y															5	5			90	
																							H	W				
																							2	2			96	

Analyzed By / Date:

*Darlene*  
11/25/24  
at station 4

QC By / Date:

*[Signature]*  
11/26/24

Fax, Email, Verbal Results By / Date:

# of Samples:

2

Comments:

**24K0950**

*S137373*

**SENDING LABORATORY**

ESS Laboratory  
185 Frances Avenue  
Cranston, RI 02910  
Phone: (401) 461-7181

**RECEIVING LABORATORY**

Aerobiology Boston  
22 Cummings Park  
Woburn, MA 01801  
Phone: (781) 935-3212

**PROJECT NOTES**

**Project Name:** 24K0950

**Project Location:** MA

**Project PO Number:** 23144B

**Due Date** ~~2 Day TAT~~ *Due 11/26/24 J.C.*

**Send Report To:** smorrell@thielsch.com; MDean@thielsch.com; ESSProjectManagement@thielsch.com

**Sample ID:** 24K0950-01

**Sampled:** 11/19/24 09:30

**Sample Matrix:** Sediment

**Sample Type:** Grab/Composite

**Sampled By:** Client

**Container - Preservation:** 1 x 4 oz. Jar - Unpres

**Hold Time Expires** 11/20/2024

**Analysis** Asbestos

**Analysis Comments:** N/A

**Sample ID:** 24K0950-02

**Sampled:** 11/19/24 10:30

**Sample Matrix:** Sediment

**Sample Type:** Grab/Composite

**Sampled By:** Client

**Container - Preservation:** 1 x 4 oz. Jar - Unpres

**Hold Time Expires** 11/20/2024

**Analysis** Asbestos

**Analysis Comments:** N/A

Released By

Date

Received By

Date

Released By

Date

Received By

Date

*CERTIFICATE OF ANALYSIS*

Jonas Procton  
Horsley & Witten  
90 Route 6A  
Sandwich, MA 02563

**RE: Squannacook River Dam (231214)**  
**ESS Laboratory Work Order Number: 24B0025**

This signed Certificate of Analysis is our approved release of your analytical results. These results are only representative of sample aliquots received at the laboratory. ESS Laboratory expects its clients to follow all regulatory sampling guidelines. Beginning with this page, the entire report has been paginated. This report should not be copied except in full without the approval of the laboratory. Samples will be disposed of thirty days after the final report has been delivered. If you have any questions or concerns, please feel free to call our Customer Service Department.



Laurel Stoddard  
Laboratory Director

**REVIEWED**

**By ESS Laboratory at 8:03 pm, Feb 09, 2024**

**Analytical Summary**

The project as described above has been analyzed in accordance with the ESS Quality Assurance Plan. This plan utilizes the following methodologies: US EPA SW-846, US EPA Methods for Chemical Analysis of Water and Wastes per 40 CFR Part 136, APHA Standard Methods for the Examination of Water and Wastewater, American Society for Testing and Materials (ASTM), and other recognized methodologies. The analyses with these noted observations are in conformance to the Quality Assurance Plan. In chromatographic analysis, manual integration is frequently used instead of automated integration because it produces more accurate results.

The test results present in this report are in compliance with TNI and relative state standards, and/or client Quality Assurance Project Plans (QAPP). The laboratory has reviewed the following: Sample Preservations, Hold Times, Initial Calibrations, Continuing Calibrations, Method Blanks, Blank Spikes, Blank Spike Duplicates, Duplicates, Matrix Spikes, Matrix Spike Duplicates, Surrogates and Internal Standards. Any results which were found to be outside of the recommended ranges stated in our SOPs will be noted in the Project Narrative.

**Subcontracted Analyses**

CTS - Cranston, RI

Grain Size Analysis



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**SAMPLE RECEIPT**

The following samples were received on February 01, 2024 for the analyses specified on the enclosed Chain of Custody Record.

**Low Level VOA vials were frozen by ESS Laboratory on Febuary 1, 2024 at 17:10.**

**Sample ID 24B0025-01 and 24B0025-02 for Metals were oven dried at 60 degrees Celsius prior to digestion and relogged in as Sample ID 24B0025-03 and 24B0025-04. This was done to increase the dry weight of the sample digested which decreases variability of results and lowers the detection limits for samples with high water content.**

Lab Number	Sample Name	Matrix	Analysis
24B0025-01	Groton DS	Sediment	2540G, 8082A Cong, 8260D Low, EPH8270, EPH8270SIM, LK, MADEP-EPH, SUB
24B0025-02	Groton US	Sediment	2540G, 8082A Cong, 8260D Low, EPH8270, EPH8270SIM, LK, MADEP-EPH, SUB
24B0025-03	Groton DS Oven Dried	Sediment	6010C, 7471B
24B0025-04	Groton US Oven Dried	Sediment	6010C, 7471B

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**PROJECT NARRATIVE**

**8082 Polychlorinated Biphenyls (PCB) / Congeners**

24B0025-02 Lower value is used due to matrix interferences (LC).

BZ#138 , BZ#153 [2C]

24B0025-02 Percent difference between primary and confirmation results exceeds 40% (P).

BZ#138 , BZ#153 [2C]

**Volatile Organics Low Level**

D4B0041-CCV1 Continuing Calibration %Diff/Drift is above control limit (CD+).

1,2-Dibromo-3-Chloropropane (33% @ 20%), 1,4-Dioxane (31% @ 20%), Tetrahydrofuran (41% @ 20%)

DB40219-BS1 Blank Spike recovery is above upper control limit (B+).

Tetrahydrofuran (138% @ 70-130%)

DB40219-BSD1 Relative percent difference for duplicate is outside of criteria (D+).

Acetone (36% @ 20%)

**No other observations noted.**

**End of Project Narrative.**

**DATA USABILITY LINKS**

*To ensure you are viewing the most current version of the documents below, please clear your internet cookies for [www.ESSLaboratory.com](http://www.ESSLaboratory.com). Consult your IT Support personnel for information on how to clear your internet cookies.*

[Definitions of Quality Control Parameters](#)

[Semivolatile Organics Internal Standard Information](#)

[Semivolatile Organics Surrogate Information](#)

[Volatile Organics Internal Standard Information](#)

[Volatile Organics Surrogate Information](#)

[EPH and VPH Alkane Lists](#)

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**CURRENT SW-846 METHODOLOGY VERSIONS**

**Analytical Methods**

1010A - Flashpoint  
6010C - ICP  
6020A - ICP MS  
7010 - Graphite Furnace  
7196A - Hexavalent Chromium  
7470A - Aqueous Mercury  
7471B - Solid Mercury  
8011 - EDB/DBCP/TCP  
8015C - GRO/DRO  
8081B - Pesticides  
8082A - PCB  
8100M - TPH  
8151A - Herbicides  
8260B - VOA  
8270D - SVOA  
8270D SIM - SVOA Low Level  
9014 - Cyanide  
9038 - Sulfate  
9040C - Aqueous pH  
9045D - Solid pH (Corrosivity)  
9050A - Specific Conductance  
9056A - Anions (IC)  
9060A - TOC  
9095B - Paint Filter  
MADEP 04-1.1 - EPH  
MADEP 18-2.1 - VPH

**Prep Methods**

3005A - Aqueous ICP Digestion  
3020A - Aqueous Graphite Furnace / ICP MS Digestion  
3050B - Solid ICP / Graphite Furnace / ICP MS Digestion  
3060A - Solid Hexavalent Chromium Digestion  
3510C - Separatory Funnel Extraction  
3520C - Liquid / Liquid Extraction  
3540C - Manual Soxhlet Extraction  
3541 - Automated Soxhlet Extraction  
3546 - Microwave Extraction  
3580A - Waste Dilution  
5030B - Aqueous Purge and Trap  
5030C - Aqueous Purge and Trap  
5035A - Solid Purge and Trap

SW846 Reactivity Methods 7.3.3.2 (Reactive Cyanide) and 7.3.4.1 (Reactive Sulfide) have been withdrawn by EPA. These methods are reported per client request and are not NELAP accredited.

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton DS  
Date Sampled: 01/31/24 11:05  
Percent Solids: 73  
Initial Volume: 12.4g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-01  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 2/2/24 9:00

**Volatile Organics Low Level**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
1,1,1,2-Tetrachloroethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,1,1-Trichloroethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,1,2,2-Tetrachloroethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,1,2-Trichloroethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,1-Dichloroethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,1-Dichloroethene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,1-Dichloropropene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2,3-Trichlorobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2,3-Trichloropropane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2,4-Trichlorobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2,4-Trimethylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2-Dibromo-3-Chloropropane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2-Dibromoethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2-Dichlorobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2-Dichloroethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,2-Dichloropropane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,3,5-Trimethylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,3-Dichlorobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,3-Dichloropropane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,4-Dichlorobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
1,4-Dioxane	ND (0.0554)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
2,2-Dichloropropane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
2-Butanone	ND (0.0277)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
2-Chlorotoluene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
2-Hexanone	ND (0.0277)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
4-Chlorotoluene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
4-Isopropyltoluene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
4-Methyl-2-Pentanone	ND (0.0277)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Acetone	ND (0.0277)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Benzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Bromobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton DS  
Date Sampled: 01/31/24 11:05  
Percent Solids: 73  
Initial Volume: 12.4g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-01  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 2/2/24 9:00

**Volatile Organics Low Level**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
Bromochloromethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Bromodichloromethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Bromoform	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Bromomethane	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Carbon Disulfide	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Carbon Tetrachloride	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Chlorobenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Chloroethane	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Chloroform	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Chloromethane	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
cis-1,2-Dichloroethene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
cis-1,3-Dichloropropene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Dibromochloromethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Dibromomethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Dichlorodifluoromethane	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Diethyl Ether	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Di-isopropyl ether	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Ethyl tertiary-butyl ether	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Ethylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Hexachlorobutadiene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Isopropylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Methyl tert-Butyl Ether	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Methylene Chloride	ND (0.0138)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Naphthalene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
n-Butylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
n-Propylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
sec-Butylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Styrene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
tert-Butylbenzene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Tertiary-amyl methyl ether	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Tetrachloroethene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219



### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: Groton DS  
 Date Sampled: 01/31/24 11:05  
 Percent Solids: 73  
 Initial Volume: 12.4g  
 Final Volume: 10ml  
 Extraction Method: 5035

ESS Laboratory Work Order: 24B0025  
 ESS Laboratory Sample ID: 24B0025-01  
 Sample Matrix: Sediment  
 Units: mg/kg dry  
 Analyst: MEK  
 Prepared: 2/2/24 9:00

### Volatile Organics Low Level

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
Tetrahydrofuran	ND (0.0111)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Toluene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
trans-1,2-Dichloroethene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
trans-1,3-Dichloropropene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Trichloroethene	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Trichlorofluoromethane	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Vinyl Chloride	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Xylene O	ND (0.0028)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Xylene P,M	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219
Xylenes (Total)	ND (0.0055)		8260D Low		1	MEK	02/02/24 14:37	D4B0041	DB40219

	<u>%Recovery</u>	<u>Qualifier</u>	<u>Limits</u>
Surrogate: 1,2-Dichloroethane-d4	118 %		70-130
Surrogate: 4-Bromofluorobenzene	94 %		70-130
Surrogate: Dibromofluoromethane	110 %		70-130
Surrogate: Toluene-d8	102 %		70-130

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: Groton DS  
 Date Sampled: 01/31/24 11:05  
 Percent Solids: 73  
 Initial Volume: 24.8g  
 Final Volume: 1ml  
 Extraction Method: 3546

ESS Laboratory Work Order: 24B0025  
 ESS Laboratory Sample ID: 24B0025-01  
 Sample Matrix: Sediment  
 Units: mg/kg dry

Prepared: 2/2/24 15:16

### MADEP-EPH Extractable Petroleum Hydrocarbons

Analyte	Results (MRL)	MDL	Method	Limit	DF	Analyst	Analyzed	Sequence	Batch
C9-C18 Aliphatics1	ND (20.8)		MADEP-EPH		1	NXL	02/05/24 18:06	D4B0093	DB40221
C19-C36 Aliphatics1	ND (20.8)		MADEP-EPH		1	NXL	02/05/24 18:06	D4B0093	DB40221
C11-C22 Unadjusted Aromatics1	ND (20.8)		EPH8270		1	MJV	02/07/24 19:28	D4B0154	DB40221
C11-C22 Aromatics1,2	ND (21.0)		EPH8270			TJ	02/07/24 19:28		[CALC]
2-Methylnaphthalene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Acenaphthene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Naphthalene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Phenanthrene	0.020 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Acenaphthylene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Anthracene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Benzo(a)anthracene	0.014 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Benzo(a)pyrene	0.015 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Benzo(b)fluoranthene	0.016 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Benzo(g,h,i)perylene	0.012 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Benzo(k)fluoranthene	0.013 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Chrysene	0.017 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Dibenzo(a,h)Anthracene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Fluoranthene	0.031 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Fluorene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Indeno(1,2,3-cd)Pyrene	ND (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221
Pyrene	0.028 (0.011)		EPH8270SIM		1	TJ	02/06/24 21:48	D4B0131	DB40221

	%Recovery	Qualifier	Limits
Surrogate: 1-Chlorooctadecane	50 %		40-140
Surrogate: 2-Bromonaphthalene	88 %		40-140
Surrogate: 2-Fluorobiphenyl	84 %		40-140
Surrogate: O-Terphenyl	56 %		40-140

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton DS  
Date Sampled: 01/31/24 11:05  
Percent Solids: 73

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-01  
Sample Matrix: Sediment

**Classical Chemistry**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Percent Moisture	27 (1)		2540G		1	EAM	02/01/24 19:41	%	DB40110
Total Organic Carbon (Average)	28700 (477)		LK		1	CCP	02/06/24 11:55	mg/kg	[CALC]

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton DS  
Date Sampled: 01/31/24 11:05

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-01  
Sample Matrix: Sediment

**Subcontracted Analysis**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Grain Size	See Attached (N/A)								

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: Groton DS  
 Date Sampled: 01/31/24 11:05  
 Percent Solids: 73  
 Initial Volume: 30.3g  
 Final Volume: 2ml  
 Extraction Method: 3540C

ESS Laboratory Work Order: 24B0025  
 ESS Laboratory Sample ID: 24B0025-01  
 Sample Matrix: Sediment  
 Units: mg/kg dry  
 Analyst: DMC  
 Prepared: 2/5/24 12:30

### 8082 Polychlorinated Biphenyls (PCB) / Congeners

Analyte	Results (MRL)	MDL	Method	Limit	DF	Analyzed	Sequence	Batch
BZ#8	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#18	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#28	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#44	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#52	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#66	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#101	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#105	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#118 [2C]	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#128	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
<b>BZ#138 [2C]</b>	<b>0.00061</b> (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#153 [2C]	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#170	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#180	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#187	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#195	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#206	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505
BZ#209	ND (0.00037)		8082A Cong		1	02/06/24 13:42	D4B0101	DB40505

	%Recovery	Qualifier	Limits
Surrogate: Tetrachloro-m-xylene [2C]	66 %		30-150



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton US  
Date Sampled: 01/31/24 15:00  
Percent Solids: 77  
Initial Volume: 12.6g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-02  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 2/2/24 9:00

**Volatile Organics Low Level**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
1,1,1,2-Tetrachloroethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,1,1-Trichloroethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,1,2,2-Tetrachloroethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,1,2-Trichloroethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,1-Dichloroethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,1-Dichloroethene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,1-Dichloropropene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2,3-Trichlorobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2,3-Trichloropropane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2,4-Trichlorobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2,4-Trimethylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2-Dibromo-3-Chloropropane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2-Dibromoethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2-Dichlorobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2-Dichloroethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,2-Dichloropropane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,3,5-Trimethylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,3-Dichlorobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,3-Dichloropropane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,4-Dichlorobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
1,4-Dioxane	ND (0.0513)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
2,2-Dichloropropane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
2-Butanone	ND (0.0256)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
2-Chlorotoluene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
2-Hexanone	ND (0.0256)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
4-Chlorotoluene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
4-Isopropyltoluene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
4-Methyl-2-Pentanone	ND (0.0256)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Acetone	ND (0.0256)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Benzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Bromobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton US  
Date Sampled: 01/31/24 15:00  
Percent Solids: 77  
Initial Volume: 12.6g  
Final Volume: 10ml  
Extraction Method: 5035

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-02  
Sample Matrix: Sediment  
Units: mg/kg dry  
Analyst: MEK  
Prepared: 2/2/24 9:00

**Volatile Organics Low Level**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
Bromochloromethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Bromodichloromethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Bromoform	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Bromomethane	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Carbon Disulfide	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Carbon Tetrachloride	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Chlorobenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Chloroethane	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Chloroform	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Chloromethane	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
cis-1,2-Dichloroethene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
cis-1,3-Dichloropropene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Dibromochloromethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Dibromomethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Dichlorodifluoromethane	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Diethyl Ether	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Di-isopropyl ether	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Ethyl tertiary-butyl ether	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Ethylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Hexachlorobutadiene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Isopropylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Methyl tert-Butyl Ether	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Methylene Chloride	ND (0.0128)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Naphthalene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
n-Butylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
n-Propylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
sec-Butylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Styrene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
tert-Butylbenzene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Tertiary-amyl methyl ether	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Tetrachloroethene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: Groton US  
 Date Sampled: 01/31/24 15:00  
 Percent Solids: 77  
 Initial Volume: 12.6g  
 Final Volume: 10ml  
 Extraction Method: 5035

ESS Laboratory Work Order: 24B0025  
 ESS Laboratory Sample ID: 24B0025-02  
 Sample Matrix: Sediment  
 Units: mg/kg dry  
 Analyst: MEK  
 Prepared: 2/2/24 9:00

### Volatile Organics Low Level

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
Tetrahydrofuran	ND (0.0103)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Toluene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
trans-1,2-Dichloroethene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
trans-1,3-Dichloropropene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Trichloroethene	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Trichlorofluoromethane	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Vinyl Chloride	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Xylene O	ND (0.0026)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Xylene P,M	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219
Xylenes (Total)	ND (0.0051)		8260D Low		1	MEK	02/02/24 14:11	D4B0041	DB40219

	<u>%Recovery</u>	<u>Qualifier</u>	<u>Limits</u>
Surrogate: 1,2-Dichloroethane-d4	113 %		70-130
Surrogate: 4-Bromofluorobenzene	99 %		70-130
Surrogate: Dibromofluoromethane	107 %		70-130
Surrogate: Toluene-d8	101 %		70-130

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: Groton US  
 Date Sampled: 01/31/24 15:00  
 Percent Solids: 77  
 Initial Volume: 24.8g  
 Final Volume: 1ml  
 Extraction Method: 3546

ESS Laboratory Work Order: 24B0025  
 ESS Laboratory Sample ID: 24B0025-02  
 Sample Matrix: Sediment  
 Units: mg/kg dry

Prepared: 2/2/24 15:16

**MADEP-EPH Extractable Petroleum Hydrocarbons**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Sequence</u>	<u>Batch</u>
C9-C18 Aliphatics1	ND (19.5)		MADEP-EPH		1	NXL	02/05/24 18:41	D4B0093	DB40221
C19-C36 Aliphatics1	ND (19.5)		MADEP-EPH		1	NXL	02/05/24 18:41	D4B0093	DB40221
C11-C22 Unadjusted Aromatics1	ND (19.5)		EPH8270		1	MJV	02/07/24 20:07	D4B0154	DB40221
C11-C22 Aromatics1,2	ND (19.7)		EPH8270			TJ	02/07/24 20:07		[CALC]
<b>2-Methylnaphthalene</b>	<b>0.011</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Acenaphthene</b>	<b>0.044</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Naphthalene</b>	<b>0.016</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Phenanthrene</b>	<b>0.677</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
Acenaphthylene	ND (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Anthracene</b>	<b>0.179</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Benzo(a)anthracene</b>	<b>0.361</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Benzo(a)pyrene</b>	<b>0.419</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Benzo(b)fluoranthene</b>	<b>0.340</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Benzo(g,h,i)perylene</b>	<b>0.291</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Benzo(k)fluoranthene</b>	<b>0.290</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Chrysene</b>	<b>0.360</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Dibenzo(a,h)Anthracene</b>	<b>0.118</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Fluoranthene</b>	<b>1.01</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Fluorene</b>	<b>0.062</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Indeno(1,2,3-cd)Pyrene</b>	<b>0.233</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221
<b>Pyrene</b>	<b>0.813</b> (0.010)		EPH8270SIM		1	TJ	02/06/24 22:09	D4B0131	DB40221

	<i>%Recovery</i>	<i>Qualifier</i>	<i>Limits</i>
<i>Surrogate: 1-Chlorooctadecane</i>	55 %		40-140
<i>Surrogate: 2-Bromonaphthalene</i>	92 %		40-140
<i>Surrogate: 2-Fluorobiphenyl</i>	87 %		40-140
<i>Surrogate: O-Terphenyl</i>	71 %		40-140

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton US  
Date Sampled: 01/31/24 15:00  
Percent Solids: 77

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-02  
Sample Matrix: Sediment

**Classical Chemistry**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Percent Moisture	23 (1)		2540G		1	EAM	02/01/24 19:41	%	DB40110
Total Organic Carbon (Average)	12400 (483)		LK		1	CCP	02/06/24 13:01	mg/kg	[CALC]



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton US  
Date Sampled: 01/31/24 15:00

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-02  
Sample Matrix: Sediment

**Subcontracted Analysis**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>Units</u>	<u>Batch</u>
Grain Size	See Attached (N/A)								

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
 Client Project ID: Squannacook River Dam  
 Client Sample ID: Groton US  
 Date Sampled: 01/31/24 15:00  
 Percent Solids: 77  
 Initial Volume: 30.1g  
 Final Volume: 2ml  
 Extraction Method: 3540C

ESS Laboratory Work Order: 24B0025  
 ESS Laboratory Sample ID: 24B0025-02  
 Sample Matrix: Sediment  
 Units: mg/kg dry  
 Analyst: DMC  
 Prepared: 2/5/24 12:30

### 8082 Polychlorinated Biphenyls (PCB) / Congeners

Analyte	Results (MRL)	MDL	Method	Limit	DF	Analyzed	Sequence	Batch
BZ#8	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#18	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#28	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#44	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#52	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#66	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
<b>BZ#101 [2C]</b>	<b>0.00061</b> (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#105	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#118 [2C]	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#128	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
<b>BZ#138</b>	<b>P, LC 0.00111</b> (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
<b>BZ#153 [2C]</b>	<b>P, LC 0.00085</b> (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
<b>BZ#170 [2C]</b>	<b>0.00070</b> (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
<b>BZ#180</b>	<b>0.00117</b> (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
<b>BZ#187</b>	<b>0.00055</b> (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#195 [2C]	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#206 [2C]	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505
BZ#209 [2C]	ND (0.00035)		8082A Cong		1	02/06/24 14:13	D4B0101	DB40505

	%Recovery	Qualifier	Limits
Surrogate: Tetrachloro-m-xylene	70 %		30-150

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton DS Oven Dried  
Date Sampled: 01/31/24 11:05  
Percent Solids: 100

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-03  
Sample Matrix: Sediment  
Units: mg/kg dry

Extraction Method: 3050B

**Total Metals**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>I/V</u>	<u>F/V</u>	<u>Batch</u>
Arsenic	13.5 (0.98)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521
Cadmium	0.44 (0.10)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521
Chromium	6.24 (0.39)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521
Copper	6.00 (0.98)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521
Lead	13.5 (1.95)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521
Mercury	0.029 (0.009)		7471B		1	AFV	02/05/24 17:13	2.09	40	DB40504
Nickel	5.87 (0.98)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521
Zinc	35.8 (0.98)		6010C		1	KJB	02/07/24 19:58	5.12	100	DB40521

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam  
Client Sample ID: Groton US Oven Dried  
Date Sampled: 01/31/24 15:00  
Percent Solids: 100

ESS Laboratory Work Order: 24B0025  
ESS Laboratory Sample ID: 24B0025-04  
Sample Matrix: Sediment  
Units: mg/kg dry

Extraction Method: 3050B

**Total Metals**

<u>Analyte</u>	<u>Results (MRL)</u>	<u>MDL</u>	<u>Method</u>	<u>Limit</u>	<u>DF</u>	<u>Analyst</u>	<u>Analyzed</u>	<u>I/V</u>	<u>F/V</u>	<u>Batch</u>
Arsenic	6.17 (0.98)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521
Cadmium	0.17 (0.10)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521
Chromium	5.70 (0.39)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521
Copper	6.46 (0.98)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521
Lead	31.5 (1.96)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521
Mercury	0.024 (0.009)		7471B		1	AFV	02/05/24 17:15	2.12	40	DB40504
Nickel	7.01 (0.98)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521
Zinc	22.9 (0.98)		6010C		1	KJB	02/07/24 20:00	5.11	100	DB40521

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Total Metals

##### Batch DB40504 - 7471B

###### Blank

Mercury	ND	0.031	mg/kg wet
---------	----	-------	-----------

###### LCS

Mercury	19.1	3.00	mg/kg wet	21.60	88	80-120
---------	------	------	-----------	-------	----	--------

###### LCS Dup

Mercury	19.0	2.87	mg/kg wet	21.60	88	80-120	0.4	30
---------	------	------	-----------	-------	----	--------	-----	----

##### Batch DB40521 - 3050B

###### Blank

Arsenic	ND	2.50	mg/kg wet
Cadmium	ND	0.25	mg/kg wet
Chromium	ND	1.00	mg/kg wet
Copper	ND	2.50	mg/kg wet
Lead	ND	5.00	mg/kg wet
Nickel	ND	2.50	mg/kg wet
Zinc	ND	2.50	mg/kg wet

###### LCS

Arsenic	180	8.33	mg/kg wet	223.0	81	70-102
Cadmium	180	0.83	mg/kg wet	226.0	79	74-105
Chromium	204	3.33	mg/kg wet	230.0	88	80-120
Copper	216	8.33	mg/kg wet	239.0	90	80-120
Lead	243	16.7	mg/kg wet	275.0	88	80-120
Nickel	103	8.33	mg/kg wet	118.0	87	80-120
Zinc	242	8.33	mg/kg wet	286.0	85	80-120

###### LCS Dup

Arsenic	178	7.46	mg/kg wet	223.0	80	70-102	2	20
Cadmium	178	0.75	mg/kg wet	226.0	79	74-105	1	20
Chromium	200	2.99	mg/kg wet	230.0	87	80-120	2	20
Copper	213	7.46	mg/kg wet	239.0	89	80-120	1	20
Lead	241	14.9	mg/kg wet	275.0	88	80-120	1	20
Nickel	101	7.46	mg/kg wet	118.0	86	80-120	2	30
Zinc	241	7.46	mg/kg wet	286.0	84	80-120	0.5	20

#### Volatile Organics Low Level

##### Batch DB40219 - 5035

###### Blank

1,1,1,2-Tetrachloroethane	ND	0.0050	mg/kg wet
1,1,1-Trichloroethane	ND	0.0050	mg/kg wet
1,1,2,2-Tetrachloroethane	ND	0.0050	mg/kg wet
1,1,2-Trichloroethane	ND	0.0050	mg/kg wet
1,1-Dichloroethane	ND	0.0050	mg/kg wet
1,1-Dichloroethene	ND	0.0050	mg/kg wet
1,1-Dichloropropene	ND	0.0050	mg/kg wet



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**Quality Control Data**

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

**Volatile Organics Low Level**

**Batch DB40219 - 5035**

1,2,3-Trichlorobenzene	ND	0.0050	mg/kg wet
1,2,3-Trichloropropane	ND	0.0050	mg/kg wet
1,2,4-Trichlorobenzene	ND	0.0050	mg/kg wet
1,2,4-Trimethylbenzene	ND	0.0050	mg/kg wet
1,2-Dibromo-3-Chloropropane	ND	0.0050	mg/kg wet
1,2-Dibromoethane	ND	0.0050	mg/kg wet
1,2-Dichlorobenzene	ND	0.0050	mg/kg wet
1,2-Dichloroethane	ND	0.0050	mg/kg wet
1,2-Dichloropropane	ND	0.0050	mg/kg wet
1,3,5-Trimethylbenzene	ND	0.0050	mg/kg wet
1,3-Dichlorobenzene	ND	0.0050	mg/kg wet
1,3-Dichloropropane	ND	0.0050	mg/kg wet
1,4-Dichlorobenzene	ND	0.0050	mg/kg wet
1,4-Dioxane	ND	0.100	mg/kg wet
2,2-Dichloropropane	ND	0.0050	mg/kg wet
2-Butanone	ND	0.0500	mg/kg wet
2-Chlorotoluene	ND	0.0050	mg/kg wet
2-Hexanone	ND	0.0500	mg/kg wet
4-Chlorotoluene	ND	0.0050	mg/kg wet
4-Isopropyltoluene	ND	0.0050	mg/kg wet
4-Methyl-2-Pentanone	ND	0.0500	mg/kg wet
Acetone	ND	0.0500	mg/kg wet
Benzene	ND	0.0050	mg/kg wet
Bromobenzene	ND	0.0050	mg/kg wet
Bromochloromethane	ND	0.0050	mg/kg wet
Bromodichloromethane	ND	0.0050	mg/kg wet
Bromoform	ND	0.0050	mg/kg wet
Bromomethane	ND	0.0100	mg/kg wet
Carbon Disulfide	ND	0.0050	mg/kg wet
Carbon Tetrachloride	ND	0.0050	mg/kg wet
Chlorobenzene	ND	0.0050	mg/kg wet
Chloroethane	ND	0.0100	mg/kg wet
Chloroform	ND	0.0050	mg/kg wet
Chloromethane	ND	0.0100	mg/kg wet
cis-1,2-Dichloroethene	ND	0.0050	mg/kg wet
cis-1,3-Dichloropropene	ND	0.0050	mg/kg wet
Dibromochloromethane	ND	0.0050	mg/kg wet
Dibromomethane	ND	0.0050	mg/kg wet
Dichlorodifluoromethane	ND	0.0100	mg/kg wet
Diethyl Ether	ND	0.0050	mg/kg wet
Di-isopropyl ether	ND	0.0050	mg/kg wet
Ethyl tertiary-butyl ether	ND	0.0050	mg/kg wet
Ethylbenzene	ND	0.0050	mg/kg wet
Hexachlorobutadiene	ND	0.0050	mg/kg wet

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DB40219 - 5035

Isopropylbenzene	ND	0.0050	mg/kg wet
Methyl tert-Butyl Ether	ND	0.0050	mg/kg wet
Methylene Chloride	ND	0.0250	mg/kg wet
Naphthalene	ND	0.0050	mg/kg wet
n-Butylbenzene	ND	0.0050	mg/kg wet
n-Propylbenzene	ND	0.0050	mg/kg wet
sec-Butylbenzene	ND	0.0050	mg/kg wet
Styrene	ND	0.0050	mg/kg wet
tert-Butylbenzene	ND	0.0050	mg/kg wet
Tertiary-amyl methyl ether	ND	0.0050	mg/kg wet
Tetrachloroethene	ND	0.0050	mg/kg wet
Tetrahydrofuran	ND	0.0200	mg/kg wet
Toluene	ND	0.0050	mg/kg wet
trans-1,2-Dichloroethene	ND	0.0050	mg/kg wet
trans-1,3-Dichloropropene	ND	0.0050	mg/kg wet
Trichloroethene	ND	0.0050	mg/kg wet
Trichlorofluoromethane	ND	0.0050	mg/kg wet
Vinyl Chloride	ND	0.0100	mg/kg wet
Xylene O	ND	0.0050	mg/kg wet
Xylene P,M	ND	0.0100	mg/kg wet

#### LCS

1,1,1,2-Tetrachloroethane	0.0551	0.0050	mg/kg wet	0.05000	110	70-130
1,1,1-Trichloroethane	0.0603	0.0050	mg/kg wet	0.05000	121	70-130
1,1,2,2-Tetrachloroethane	0.0583	0.0050	mg/kg wet	0.05000	117	40-160
1,1,2-Trichloroethane	0.0565	0.0050	mg/kg wet	0.05000	113	70-130
1,1-Dichloroethane	0.0597	0.0050	mg/kg wet	0.05000	119	70-130
1,1-Dichloroethene	0.0649	0.0050	mg/kg wet	0.05000	130	70-130
1,1-Dichloropropene	0.0594	0.0050	mg/kg wet	0.05000	119	70-130
1,2,3-Trichlorobenzene	0.0566	0.0050	mg/kg wet	0.05000	113	70-130
1,2,3-Trichloropropane	0.0574	0.0050	mg/kg wet	0.05000	115	70-130
1,2,4-Trichlorobenzene	0.0561	0.0050	mg/kg wet	0.05000	112	70-130
1,2,4-Trimethylbenzene	0.0590	0.0050	mg/kg wet	0.05000	118	70-130
1,2-Dibromo-3-Chloropropane	0.0640	0.0050	mg/kg wet	0.05000	128	70-130
1,2-Dibromoethane	0.0559	0.0050	mg/kg wet	0.05000	112	70-130
1,2-Dichlorobenzene	0.0538	0.0050	mg/kg wet	0.05000	108	70-130
1,2-Dichloroethane	0.0576	0.0050	mg/kg wet	0.05000	115	70-130
1,2-Dichloropropane	0.0575	0.0050	mg/kg wet	0.05000	115	70-130
1,3,5-Trimethylbenzene	0.0588	0.0050	mg/kg wet	0.05000	118	70-130
1,3-Dichlorobenzene	0.0537	0.0050	mg/kg wet	0.05000	107	70-130
1,3-Dichloropropane	0.0574	0.0050	mg/kg wet	0.05000	115	70-130
1,4-Dichlorobenzene	0.0540	0.0050	mg/kg wet	0.05000	108	70-130
1,4-Dioxane	1.29	0.100	mg/kg wet	1.000	129	70-130
2,2-Dichloropropane	0.0623	0.0050	mg/kg wet	0.05000	125	70-130
2-Butanone	0.328	0.0500	mg/kg wet	0.2500	131	40-160

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DB40219 - 5035

2-Chlorotoluene	0.0570	0.0050	mg/kg wet	0.05000		114	70-130			
2-Hexanone	0.295	0.0500	mg/kg wet	0.2500		118	40-160			
4-Chlorotoluene	0.0573	0.0050	mg/kg wet	0.05000		115	70-130			
4-Isopropyltoluene	0.0556	0.0050	mg/kg wet	0.05000		111	70-130			
4-Methyl-2-Pentanone	0.281	0.0500	mg/kg wet	0.2500		112	40-160			
Acetone	0.372	0.0500	mg/kg wet	0.2500		149	40-160			
Benzene	0.0588	0.0050	mg/kg wet	0.05000		118	70-130			
Bromobenzene	0.0539	0.0050	mg/kg wet	0.05000		108	70-130			
Bromochloromethane	0.0574	0.0050	mg/kg wet	0.05000		115	70-130			
Bromodichloromethane	0.0635	0.0050	mg/kg wet	0.05000		127	70-130			
Bromoform	0.0493	0.0050	mg/kg wet	0.05000		99	40-160			
Bromomethane	0.0503	0.0100	mg/kg wet	0.05000		101	40-160			
Carbon Disulfide	0.0632	0.0050	mg/kg wet	0.05000		126	70-130			
Carbon Tetrachloride	0.0618	0.0050	mg/kg wet	0.05000		124	70-130			
Chlorobenzene	0.0543	0.0050	mg/kg wet	0.05000		109	70-130			
Chloroethane	0.0514	0.0100	mg/kg wet	0.05000		103	40-160			
Chloroform	0.0581	0.0050	mg/kg wet	0.05000		116	70-130			
Chloromethane	0.0505	0.0100	mg/kg wet	0.05000		101	40-160			
cis-1,2-Dichloroethene	0.0590	0.0050	mg/kg wet	0.05000		118	70-130			
cis-1,3-Dichloropropene	0.0614	0.0050	mg/kg wet	0.05000		123	40-160			
Dibromochloromethane	0.0540	0.0050	mg/kg wet	0.05000		108	40-160			
Dibromomethane	0.0569	0.0050	mg/kg wet	0.05000		114	70-130			
Dichlorodifluoromethane	0.0378	0.0100	mg/kg wet	0.05000		76	40-160			
Diethyl Ether	0.0617	0.0050	mg/kg wet	0.05000		123	70-130			
Di-isopropyl ether	0.0605	0.0050	mg/kg wet	0.05000		121	70-130			
Ethyl tertiary-butyl ether	0.0591	0.0050	mg/kg wet	0.05000		118	70-130			
Ethylbenzene	0.0568	0.0050	mg/kg wet	0.05000		114	70-130			
Hexachlorobutadiene	0.0569	0.0050	mg/kg wet	0.05000		114	40-160			
Isopropylbenzene	0.0605	0.0050	mg/kg wet	0.05000		121	70-130			
Methyl tert-Butyl Ether	0.0578	0.0050	mg/kg wet	0.05000		116	70-130			
Methylene Chloride	0.0582	0.0250	mg/kg wet	0.05000		116	70-130			
Naphthalene	0.0573	0.0050	mg/kg wet	0.05000		115	40-160			
n-Butylbenzene	0.0599	0.0050	mg/kg wet	0.05000		120	70-130			
n-Propylbenzene	0.0580	0.0050	mg/kg wet	0.05000		116	70-130			
sec-Butylbenzene	0.0547	0.0050	mg/kg wet	0.05000		109	70-130			
Styrene	0.0565	0.0050	mg/kg wet	0.05000		113	40-160			
tert-Butylbenzene	0.0567	0.0050	mg/kg wet	0.05000		113	70-130			
Tertiary-amyl methyl ether	0.0575	0.0050	mg/kg wet	0.05000		115	70-130			
Tetrachloroethene	0.0448	0.0050	mg/kg wet	0.05000		90	70-130			
Tetrahydrofuran	0.0690	0.0200	mg/kg wet	0.05000		138	70-130			B+
Toluene	0.0573	0.0050	mg/kg wet	0.05000		115	70-130			
trans-1,2-Dichloroethene	0.0620	0.0050	mg/kg wet	0.05000		124	70-130			
trans-1,3-Dichloropropene	0.0580	0.0050	mg/kg wet	0.05000		116	70-130			
Trichloroethene	0.0564	0.0050	mg/kg wet	0.05000		113	70-130			

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**Quality Control Data**

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

**Volatile Organics Low Level**

**Batch DB40219 - 5035**

Trichlorofluoromethane	0.0575	0.0050	mg/kg wet	0.05000		115	40-160			
Vinyl Chloride	0.0572	0.0100	mg/kg wet	0.05000		114	70-130			
Xylene O	0.0564	0.0050	mg/kg wet	0.05000		113	70-130			
Xylene P,M	0.117	0.0100	mg/kg wet	0.1000		117	70-130			

**LCS Dup**

1,1,1,2-Tetrachloroethane	0.0540	0.0050	mg/kg wet	0.05000		108	70-130	2	20	
1,1,1-Trichloroethane	0.0585	0.0050	mg/kg wet	0.05000		117	70-130	3	20	
1,1,2,2-Tetrachloroethane	0.0562	0.0050	mg/kg wet	0.05000		112	40-160	4	20	
1,1,2-Trichloroethane	0.0556	0.0050	mg/kg wet	0.05000		111	70-130	2	20	
1,1-Dichloroethane	0.0590	0.0050	mg/kg wet	0.05000		118	70-130	1	20	
1,1-Dichloroethene	0.0631	0.0050	mg/kg wet	0.05000		126	70-130	3	20	
1,1-Dichloropropene	0.0577	0.0050	mg/kg wet	0.05000		115	70-130	3	20	
1,2,3-Trichlorobenzene	0.0579	0.0050	mg/kg wet	0.05000		116	70-130	2	20	
1,2,3-Trichloropropane	0.0541	0.0050	mg/kg wet	0.05000		108	70-130	6	20	
1,2,4-Trichlorobenzene	0.0579	0.0050	mg/kg wet	0.05000		116	70-130	3	20	
1,2,4-Trimethylbenzene	0.0587	0.0050	mg/kg wet	0.05000		117	70-130	0.4	20	
1,2-Dibromo-3-Chloropropane	0.0598	0.0050	mg/kg wet	0.05000		120	70-130	7	20	
1,2-Dibromoethane	0.0533	0.0050	mg/kg wet	0.05000		107	70-130	5	20	
1,2-Dichlorobenzene	0.0544	0.0050	mg/kg wet	0.05000		109	70-130	1	20	
1,2-Dichloroethane	0.0567	0.0050	mg/kg wet	0.05000		113	70-130	2	20	
1,2-Dichloropropane	0.0572	0.0050	mg/kg wet	0.05000		114	70-130	0.7	20	
1,3,5-Trimethylbenzene	0.0579	0.0050	mg/kg wet	0.05000		116	70-130	2	20	
1,3-Dichlorobenzene	0.0542	0.0050	mg/kg wet	0.05000		108	70-130	0.9	20	
1,3-Dichloropropane	0.0558	0.0050	mg/kg wet	0.05000		112	70-130	3	20	
1,4-Dichlorobenzene	0.0539	0.0050	mg/kg wet	0.05000		108	70-130	0.1	20	
1,4-Dioxane	1.19	0.100	mg/kg wet	1.000		119	70-130	8	20	
2,2-Dichloropropane	0.0605	0.0050	mg/kg wet	0.05000		121	70-130	3	20	
2-Butanone	0.288	0.0500	mg/kg wet	0.2500		115	40-160	13	20	
2-Chlorotoluene	0.0567	0.0050	mg/kg wet	0.05000		113	70-130	0.4	20	
2-Hexanone	0.252	0.0500	mg/kg wet	0.2500		101	40-160	16	20	
4-Chlorotoluene	0.0571	0.0050	mg/kg wet	0.05000		114	70-130	0.3	20	
4-Isopropyltoluene	0.0547	0.0050	mg/kg wet	0.05000		109	70-130	2	20	
4-Methyl-2-Pentanone	0.260	0.0500	mg/kg wet	0.2500		104	40-160	8	20	
Acetone	0.257	0.0500	mg/kg wet	0.2500		103	40-160	36	20	D+
Benzene	0.0579	0.0050	mg/kg wet	0.05000		116	70-130	1	20	
Bromobenzene	0.0533	0.0050	mg/kg wet	0.05000		107	70-130	1	20	
Bromochloromethane	0.0567	0.0050	mg/kg wet	0.05000		113	70-130	1	20	
Bromodichloromethane	0.0637	0.0050	mg/kg wet	0.05000		127	70-130	0.3	20	
Bromoform	0.0473	0.0050	mg/kg wet	0.05000		95	40-160	4	20	
Bromomethane	0.0496	0.0100	mg/kg wet	0.05000		99	40-160	1	20	
Carbon Disulfide	0.0612	0.0050	mg/kg wet	0.05000		122	70-130	3	20	
Carbon Tetrachloride	0.0595	0.0050	mg/kg wet	0.05000		119	70-130	4	20	
Chlorobenzene	0.0530	0.0050	mg/kg wet	0.05000		106	70-130	2	20	
Chloroethane	0.0492	0.0100	mg/kg wet	0.05000		98	40-160	4	20	

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### Volatile Organics Low Level

#### Batch DB40219 - 5035

Chloroform	0.0578	0.0050	mg/kg wet	0.05000		116	70-130	0.4	20	
Chloromethane	0.0488	0.0100	mg/kg wet	0.05000		98	40-160	3	20	
cis-1,2-Dichloroethene	0.0585	0.0050	mg/kg wet	0.05000		117	70-130	0.8	20	
cis-1,3-Dichloropropene	0.0611	0.0050	mg/kg wet	0.05000		122	40-160	0.5	20	
Dibromochloromethane	0.0534	0.0050	mg/kg wet	0.05000		107	40-160	1	20	
Dibromomethane	0.0554	0.0050	mg/kg wet	0.05000		111	70-130	3	20	
Dichlorodifluoromethane	0.0353	0.0100	mg/kg wet	0.05000		71	40-160	7	20	
Diethyl Ether	0.0620	0.0050	mg/kg wet	0.05000		124	70-130	0.5	20	
Di-isopropyl ether	0.0606	0.0050	mg/kg wet	0.05000		121	70-130	0.2	20	
Ethyl tertiary-butyl ether	0.0597	0.0050	mg/kg wet	0.05000		119	70-130	0.9	20	
Ethylbenzene	0.0547	0.0050	mg/kg wet	0.05000		109	70-130	4	20	
Hexachlorobutadiene	0.0565	0.0050	mg/kg wet	0.05000		113	40-160	0.7	20	
Isopropylbenzene	0.0590	0.0050	mg/kg wet	0.05000		118	70-130	3	20	
Methyl tert-Butyl Ether	0.0573	0.0050	mg/kg wet	0.05000		115	70-130	0.8	20	
Methylene Chloride	0.0591	0.0250	mg/kg wet	0.05000		118	70-130	2	20	
Naphthalene	0.0565	0.0050	mg/kg wet	0.05000		113	40-160	1	20	
n-Butylbenzene	0.0588	0.0050	mg/kg wet	0.05000		118	70-130	2	20	
n-Propylbenzene	0.0567	0.0050	mg/kg wet	0.05000		113	70-130	2	20	
sec-Butylbenzene	0.0533	0.0050	mg/kg wet	0.05000		107	70-130	3	20	
Styrene	0.0556	0.0050	mg/kg wet	0.05000		111	40-160	1	20	
tert-Butylbenzene	0.0556	0.0050	mg/kg wet	0.05000		111	70-130	2	20	
Tertiary-amyl methyl ether	0.0579	0.0050	mg/kg wet	0.05000		116	70-130	0.6	20	
Tetrachloroethene	0.0412	0.0050	mg/kg wet	0.05000		82	70-130	8	20	
Tetrahydrofuran	0.0617	0.0200	mg/kg wet	0.05000		123	70-130	11	20	
Toluene	0.0557	0.0050	mg/kg wet	0.05000		111	70-130	3	20	
trans-1,2-Dichloroethene	0.0607	0.0050	mg/kg wet	0.05000		121	70-130	2	20	
trans-1,3-Dichloropropene	0.0575	0.0050	mg/kg wet	0.05000		115	70-130	1	20	
Trichloroethene	0.0553	0.0050	mg/kg wet	0.05000		111	70-130	2	20	
Trichlorofluoromethane	0.0550	0.0050	mg/kg wet	0.05000		110	40-160	4	20	
Vinyl Chloride	0.0544	0.0100	mg/kg wet	0.05000		109	70-130	5	20	
Xylene O	0.0550	0.0050	mg/kg wet	0.05000		110	70-130	2	20	
Xylene P,M	0.113	0.0100	mg/kg wet	0.1000		113	70-130	4	20	

#### MADEP-EPH Extractable Petroleum Hydrocarbons

#### Batch DB40221 - 3546

##### Blank

C19-C36 Aliphatics1	ND	15.0	mg/kg wet
C9-C18 Aliphatics1	ND	15.0	mg/kg wet

##### Blank

C11-C22 Unadjusted Aromatics1	ND	15.0	mg/kg wet
-------------------------------	----	------	-----------

##### Blank

2-Methylnaphthalene	ND	0.008	mg/kg wet
Acenaphthene	ND	0.008	mg/kg wet



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**Quality Control Data**

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

**MADEP-EPH Extractable Petroleum Hydrocarbons**

**Batch DB40221 - 3546**

Acenaphthylene	ND	0.008	mg/kg wet							
Anthracene	ND	0.008	mg/kg wet							
Benzo(a)anthracene	ND	0.008	mg/kg wet							
Benzo(a)pyrene	ND	0.008	mg/kg wet							
Benzo(b)fluoranthene	ND	0.008	mg/kg wet							
Benzo(g,h,i)perylene	ND	0.008	mg/kg wet							
Benzo(k)fluoranthene	ND	0.008	mg/kg wet							
Chrysene	ND	0.008	mg/kg wet							
Dibenzo(a,h)Anthracene	ND	0.008	mg/kg wet							
Fluoranthene	ND	0.008	mg/kg wet							
Fluorene	ND	0.008	mg/kg wet							
Indeno(1,2,3-cd)Pyrene	ND	0.008	mg/kg wet							
Naphthalene	ND	0.008	mg/kg wet							
Phenanthrene	ND	0.008	mg/kg wet							
Pyrene	ND	0.008	mg/kg wet							

**LCS**

C19-C36 Aliphatics1	13.7	15.0	mg/kg wet	16.00		85	40-140			
C9-C18 Aliphatics1	7.8	15.0	mg/kg wet	12.00		65	40-140			

**LCS**

C11-C22 Unadjusted Aromatics1	30.0	15.0	mg/kg wet	34.00		88	40-140			
-------------------------------	------	------	-----------	-------	--	----	--------	--	--	--

**LCS**

2-Methylnaphthalene Breakthrough	0.0		%				0-5			
Naphthalene Breakthrough	0.0		%				0-5			

**LCS**

2-Methylnaphthalene	1.20	0.040	mg/kg wet	2.000		60	40-140			
Acenaphthene	1.26	0.040	mg/kg wet	2.000		63	40-140			
Acenaphthylene	1.34	0.040	mg/kg wet	2.000		67	40-140			
Anthracene	1.48	0.040	mg/kg wet	2.000		74	40-140			
Benzo(a)anthracene	1.38	0.040	mg/kg wet	2.000		69	40-140			
Benzo(a)pyrene	1.59	0.040	mg/kg wet	2.000		79	40-140			
Benzo(b)fluoranthene	1.53	0.040	mg/kg wet	2.000		77	40-140			
Benzo(g,h,i)perylene	1.56	0.040	mg/kg wet	2.000		78	40-140			
Benzo(k)fluoranthene	1.46	0.040	mg/kg wet	2.000		73	40-140			
Chrysene	1.43	0.040	mg/kg wet	2.000		71	40-140			
Dibenzo(a,h)Anthracene	1.61	0.040	mg/kg wet	2.000		81	40-140			
Fluoranthene	1.45	0.040	mg/kg wet	2.000		72	40-140			
Fluorene	1.32	0.040	mg/kg wet	2.000		66	40-140			
Indeno(1,2,3-cd)Pyrene	1.55	0.040	mg/kg wet	2.000		78	40-140			
Naphthalene	1.16	0.040	mg/kg wet	2.000		58	40-140			
Phenanthrene	1.33	0.040	mg/kg wet	2.000		66	40-140			
Pyrene	1.52	0.040	mg/kg wet	2.000		76	40-140			

**LCS Dup**

C19-C36 Aliphatics1	11.6	15.0	mg/kg wet	16.00		72	40-140	16	25	
---------------------	------	------	-----------	-------	--	----	--------	----	----	--

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### MADEP-EPH Extractable Petroleum Hydrocarbons

##### Batch DB40221 - 3546

C9-C18 Aliphatics1	6.8	15.0	mg/kg wet	12.00		57	40-140	14	25	
--------------------	-----	------	-----------	-------	--	----	--------	----	----	--

##### LCS Dup

C11-C22 Unadjusted Aromatics1	29.7	15.0	mg/kg wet	34.00		87	40-140	0.9	25	
-------------------------------	------	------	-----------	-------	--	----	--------	-----	----	--

##### LCS Dup

2-Methylnaphthalene Breakthrough	0.0		%				0-5		200	
Naphthalene Breakthrough	0.0		%				0-5		200	

##### LCS Dup

2-Methylnaphthalene	1.30	0.040	mg/kg wet	2.000		65	40-140	8	30	
Acenaphthene	1.32	0.040	mg/kg wet	2.000		66	40-140	5	30	
Acenaphthylene	1.41	0.040	mg/kg wet	2.000		71	40-140	5	30	
Anthracene	1.53	0.040	mg/kg wet	2.000		77	40-140	3	30	
Benzo(a)anthracene	1.14	0.040	mg/kg wet	2.000		57	40-140	19	30	
Benzo(a)pyrene	1.34	0.040	mg/kg wet	2.000		67	40-140	17	30	
Benzo(b)fluoranthene	1.34	0.040	mg/kg wet	2.000		67	40-140	13	30	
Benzo(g,h,i)perylene	1.33	0.040	mg/kg wet	2.000		67	40-140	16	30	
Benzo(k)fluoranthene	1.22	0.040	mg/kg wet	2.000		61	40-140	18	30	
Chrysene	1.17	0.040	mg/kg wet	2.000		58	40-140	20	30	
Dibenzo(a,h)Anthracene	1.37	0.040	mg/kg wet	2.000		68	40-140	16	30	
Fluoranthene	1.48	0.040	mg/kg wet	2.000		74	40-140	2	30	
Fluorene	1.39	0.040	mg/kg wet	2.000		69	40-140	5	30	
Indeno(1,2,3-cd)Pyrene	1.32	0.040	mg/kg wet	2.000		66	40-140	17	30	
Naphthalene	1.23	0.040	mg/kg wet	2.000		61	40-140	5	30	
Phenanthrene	1.38	0.040	mg/kg wet	2.000		69	40-140	4	30	
Pyrene	1.23	0.040	mg/kg wet	2.000		62	40-140	21	30	

#### Classical Chemistry

##### Batch DB40239 - General Preparation

##### Blank

Total Organic Carbon (1)	ND	500	mg/kg							
Total Organic Carbon (2)	ND	500	mg/kg							

##### LCS

Total Organic Carbon (1)	8730	500	mg/kg	10010		87	80-120			
Total Organic Carbon (2)	8820	500	mg/kg	10010		88	80-120			

##### LCS Dup

Total Organic Carbon (1)	8880	500	mg/kg	10010		89	80-120	2	25	
Total Organic Carbon (2)	8260	500	mg/kg	10010		83	80-120	7	25	

#### 8082 Polychlorinated Biphenyls (PCB) / Congeners

##### Batch DB40505 - 3540C

##### Blank

BZ#101	ND	0.00027	mg/kg wet							
BZ#101 [2C]	ND	0.00027	mg/kg wet							

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### 8082 Polychlorinated Biphenyls (PCB) / Congeners

#### Batch DB40505 - 3540C

BZ#105	ND	0.00027	mg/kg wet
BZ#105 [2C]	ND	0.00027	mg/kg wet
BZ#118	ND	0.00027	mg/kg wet
BZ#118 [2C]	ND	0.00027	mg/kg wet
BZ#128	ND	0.00027	mg/kg wet
BZ#128 [2C]	ND	0.00027	mg/kg wet
BZ#138	ND	0.00027	mg/kg wet
BZ#138 [2C]	ND	0.00027	mg/kg wet
BZ#153	ND	0.00027	mg/kg wet
BZ#153 [2C]	ND	0.00027	mg/kg wet
BZ#170	ND	0.00027	mg/kg wet
BZ#170 [2C]	ND	0.00027	mg/kg wet
BZ#18	ND	0.00027	mg/kg wet
BZ#18 [2C]	ND	0.00027	mg/kg wet
BZ#180	ND	0.00027	mg/kg wet
BZ#180 [2C]	ND	0.00027	mg/kg wet
BZ#187	ND	0.00027	mg/kg wet
BZ#187 [2C]	ND	0.00027	mg/kg wet
BZ#195	ND	0.00027	mg/kg wet
BZ#195 [2C]	ND	0.00027	mg/kg wet
BZ#206	ND	0.00027	mg/kg wet
BZ#206 [2C]	ND	0.00027	mg/kg wet
BZ#209	ND	0.00027	mg/kg wet
BZ#209 [2C]	ND	0.00027	mg/kg wet
BZ#28	ND	0.00027	mg/kg wet
BZ#28 [2C]	ND	0.00027	mg/kg wet
BZ#44	ND	0.00027	mg/kg wet
BZ#44 [2C]	ND	0.00027	mg/kg wet
BZ#52	ND	0.00027	mg/kg wet
BZ#52 [2C]	ND	0.00027	mg/kg wet
BZ#66	ND	0.00027	mg/kg wet
BZ#66 [2C]	ND	0.00027	mg/kg wet
BZ#8	ND	0.00027	mg/kg wet
BZ#8 [2C]	ND	0.00027	mg/kg wet

#### LCS

BZ#101	0.00223	0.00027	mg/kg wet	0.003333	67	40-140
BZ#101 [2C]	0.00219	0.00027	mg/kg wet	0.003333	66	40-140
BZ#105	0.00238	0.00027	mg/kg wet	0.003333	71	40-140
BZ#105 [2C]	0.00236	0.00027	mg/kg wet	0.003333	71	40-140
BZ#118	0.00222	0.00027	mg/kg wet	0.003333	67	40-140
BZ#118 [2C]	0.00224	0.00027	mg/kg wet	0.003333	67	40-140
BZ#128	0.00227	0.00027	mg/kg wet	0.003333	68	40-140
BZ#128 [2C]	0.00231	0.00027	mg/kg wet	0.003333	69	40-140
BZ#138	0.00223	0.00027	mg/kg wet	0.003333	67	40-140

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### 8082 Polychlorinated Biphenyls (PCB) / Congeners

#### Batch DB40505 - 3540C

BZ#138 [2C]	0.00227	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#153	0.00222	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#153 [2C]	0.00221	0.00027	mg/kg wet	0.003333		66	40-140			
BZ#170	0.00226	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#170 [2C]	0.00228	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#18	0.00223	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#18 [2C]	0.00225	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#180	0.00228	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#180 [2C]	0.00232	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#187	0.00268	0.00027	mg/kg wet	0.003333		80	40-140			
BZ#187 [2C]	0.00228	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#195	0.00222	0.00027	mg/kg wet	0.003333		66	40-140			
BZ#195 [2C]	0.00229	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#206	0.00216	0.00027	mg/kg wet	0.003333		65	40-140			
BZ#206 [2C]	0.00222	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#209	0.00210	0.00027	mg/kg wet	0.003333		63	40-140			
BZ#209 [2C]	0.00217	0.00027	mg/kg wet	0.003333		65	40-140			
BZ#28	0.00238	0.00027	mg/kg wet	0.003333		71	40-140			
BZ#28 [2C]	0.00229	0.00027	mg/kg wet	0.003333		69	40-140			
BZ#44	0.00228	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#44 [2C]	0.00227	0.00027	mg/kg wet	0.003333		68	40-140			
BZ#52	0.00269	0.00027	mg/kg wet	0.003333		81	40-140			
BZ#52 [2C]	0.00219	0.00027	mg/kg wet	0.003333		66	40-140			
BZ#66	0.00213	0.00027	mg/kg wet	0.003333		64	40-140			
BZ#66 [2C]	0.00224	0.00027	mg/kg wet	0.003333		67	40-140			
BZ#8	0.00235	0.00027	mg/kg wet	0.003333		71	40-140			
BZ#8 [2C]	0.00215	0.00027	mg/kg wet	0.003333		64	40-140			

#### LCS Dup

BZ#101	0.00211	0.00027	mg/kg wet	0.003333		63	40-140	6	30	
BZ#101 [2C]	0.00214	0.00027	mg/kg wet	0.003333		64	40-140	2	30	
BZ#105	0.00234	0.00027	mg/kg wet	0.003333		70	40-140	2	30	
BZ#105 [2C]	0.00227	0.00027	mg/kg wet	0.003333		68	40-140	4	30	
BZ#118	0.00213	0.00027	mg/kg wet	0.003333		64	40-140	4	30	
BZ#118 [2C]	0.00218	0.00027	mg/kg wet	0.003333		65	40-140	3	30	
BZ#128	0.00237	0.00027	mg/kg wet	0.003333		71	40-140	4	30	
BZ#128 [2C]	0.00223	0.00027	mg/kg wet	0.003333		67	40-140	4	30	
BZ#138	0.00219	0.00027	mg/kg wet	0.003333		66	40-140	2	30	
BZ#138 [2C]	0.00219	0.00027	mg/kg wet	0.003333		66	40-140	4	30	
BZ#153	0.00215	0.00027	mg/kg wet	0.003333		64	40-140	3	30	
BZ#153 [2C]	0.00213	0.00027	mg/kg wet	0.003333		64	40-140	4	30	
BZ#170	0.00219	0.00027	mg/kg wet	0.003333		66	40-140	3	30	
BZ#170 [2C]	0.00221	0.00027	mg/kg wet	0.003333		66	40-140	3	30	
BZ#18	0.00198	0.00027	mg/kg wet	0.003333		59	40-140	12	30	
BZ#18 [2C]	0.00218	0.00027	mg/kg wet	0.003333		65	40-140	3	30	

### CERTIFICATE OF ANALYSIS

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

### Quality Control Data

Analyte	Result	MRL	Units	Spike Level	Source Result	%REC	%REC Limits	RPD	RPD Limit	Qualifier
---------	--------	-----	-------	-------------	---------------	------	-------------	-----	-----------	-----------

#### 8082 Polychlorinated Biphenyls (PCB) / Congeners

#### Batch DB40505 - 3540C

BZ#180	0.00220	0.00027	mg/kg wet	0.003333		66	40-140	4	30	
BZ#180 [2C]	0.00224	0.00027	mg/kg wet	0.003333		67	40-140	3	30	
BZ#187	0.00262	0.00027	mg/kg wet	0.003333		79	40-140	2	30	
BZ#187 [2C]	0.00220	0.00027	mg/kg wet	0.003333		66	40-140	4	30	
BZ#195	0.00216	0.00027	mg/kg wet	0.003333		65	40-140	2	30	
BZ#195 [2C]	0.00223	0.00027	mg/kg wet	0.003333		67	40-140	3	30	
BZ#206	0.00210	0.00027	mg/kg wet	0.003333		63	40-140	3	30	
BZ#206 [2C]	0.00217	0.00027	mg/kg wet	0.003333		65	40-140	2	30	
BZ#209	0.00204	0.00027	mg/kg wet	0.003333		61	40-140	3	30	
BZ#209 [2C]	0.00212	0.00027	mg/kg wet	0.003333		64	40-140	2	30	
BZ#28	0.00239	0.00027	mg/kg wet	0.003333		72	40-140	0.5	30	
BZ#28 [2C]	0.00231	0.00027	mg/kg wet	0.003333		69	40-140	1	30	
BZ#44	0.00217	0.00027	mg/kg wet	0.003333		65	40-140	5	30	
BZ#44 [2C]	0.00222	0.00027	mg/kg wet	0.003333		67	40-140	2	30	
BZ#52	0.00262	0.00027	mg/kg wet	0.003333		78	40-140	3	30	
BZ#52 [2C]	0.00214	0.00027	mg/kg wet	0.003333		64	40-140	2	30	
BZ#66	0.00221	0.00027	mg/kg wet	0.003333		66	40-140	4	30	
BZ#66 [2C]	0.00220	0.00027	mg/kg wet	0.003333		66	40-140	2	30	
BZ#8	0.00232	0.00027	mg/kg wet	0.003333		70	40-140	1	30	
BZ#8 [2C]	0.00226	0.00027	mg/kg wet	0.003333		68	40-140	5	30	



*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten

Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**Notes and Definitions**

Z-08	See Attached
U	Analyte included in the analysis, but not detected
P	Percent difference between primary and confirmation results exceeds 40% (P).
LC	Lower value is used due to matrix interferences (LC).
D+	Relative percent difference for duplicate is outside of criteria (D+).
D	Diluted.
CD+	Continuing Calibration %Diff/Drift is above control limit (CD+).
B+	Blank Spike recovery is above upper control limit (B+).
ND	Analyte NOT DETECTED at or above the MRL (LOQ), LOD for DoD Reports, MDL for J-Flagged Analytes
dry	Sample results reported on a dry weight basis
RPD	Relative Percent Difference
MDL	Method Detection Limit
MRL	Method Reporting Limit
LOD	Limit of Detection
LOQ	Limit of Quantitation
DL	Detection Limit
I/V	Initial Volume
F/V	Final Volume
§	Subcontracted analysis; see attached report
1	Range result excludes concentrations of surrogates and/or internal standards eluting in that range.
2	Range result excludes concentrations of target analytes eluting in that range.
3	Range result excludes the concentration of the C9-C10 aromatic range.
Avg	Results reported as a mathematical average.
NR	No Recovery
[CALC]	Calculated Analyte
SUB	Subcontracted analysis; see attached report
RL	Reporting Limit
EDL	Estimated Detection Limit
MF	Membrane Filtration
MPN	Most Probable Number
TNTC	Too numerous to Count
CFU	Colony Forming Units

*CERTIFICATE OF ANALYSIS*

Client Name: Horsley & Witten  
Client Project ID: Squannacook River Dam

ESS Laboratory Work Order: 24B0025

**ESS LABORATORY CERTIFICATIONS AND ACCREDITATIONS**

**ENVIRONMENTAL**

Rhode Island Potable and Non Potable Water: LAI00179

<http://www.health.ri.gov/find/labs/analytical/ESS.pdf>

Connecticut Potable and Non Potable Water, Solid and Hazardous Waste: PH-0750

[http://www.ct.gov/dph/lib/dph/environmental\\_health/environmental\\_laboratories/pdf/OutOfStateCommercialLaboratories.pdf](http://www.ct.gov/dph/lib/dph/environmental_health/environmental_laboratories/pdf/OutOfStateCommercialLaboratories.pdf)

Maine Potable and Non Potable Water, and Solid and Hazardous Waste: RI00002

<http://www.maine.gov/dhhs/mecdc/environmental-health/dwp/partners/labCert.shtml>

Massachusetts Potable and Non Potable Water: M-RI002

<http://public.dep.state.ma.us/Labcert/Labcert.aspx>

New Hampshire (NELAP accredited) Potable and Non Potable Water, Solid and Hazardous Waste: 2424

<http://des.nh.gov/organization/divisions/water/dwgb/nhelap/index.htm>

New York (NELAP accredited) Non Potable Water, Solid and Hazardous Waste: 11313


<http://www.wadsworth.org/labcert/elap/comm.html>

New Jersey (NELAP accredited) Non Potable Water, Solid and Hazardous Waste: RI006

[http://datamine2.state.nj.us/DEP\\_Opra/OpraMain/pi\\_main?mode=pi\\_by\\_site&sort\\_order=PI\\_NAMEA&Select+a+Site:=58715](http://datamine2.state.nj.us/DEP_Opra/OpraMain/pi_main?mode=pi_by_site&sort_order=PI_NAMEA&Select+a+Site:=58715)

Pennsylvania: 68-01752

<http://www.dep.pa.gov/Business/OtherPrograms/Labs/Pages/Laboratory-Accreditation-Program.aspx>

 <b>Thielsch</b> DIVISION OF THE RISE GROUP	195 Frances Avenue Cranston RI, 02910 Phone: (401)-467-6454 Fax: (401)-467-2398 <a href="http://cts.thielsch.com">cts.thielsch.com</a> <i>Let's Build a Solid Foundation</i>	Client Information:	Project Information:
		Horsley Witten Group Boston, MA 02109 Project Manager: Jonas Proctor Assigned By: ESS Laboratory Collected By: HW	Saquanacook River Dam Removal Groton, MA Project Number: 24B0025 Summary Page: 1 of 1 Report Date: 2.5.24

LABORATORY TESTING DATA SHEET, Report No.: 7424-B-108


Material Source	Sample ID	Depth (ft)	Laboratory No.	Identification Tests										Proctor / CBR / Permeability Tests							Laboratory Log and Soil Description
				As Rcvd Moisture Content %	LL %	PL %	OD LL	Gravel %	Sand %	Fines %	Org. %	pH	g <sub>d</sub> MAX (pcf) W <sub>opt</sub> (%)	g <sub>d</sub> MAX (pcf) W <sub>opt</sub> (%) (Corr.)	Dry unit wt. (pcf)	Test Moisture Content %	Target Test Setup as % of Proctor	CBR @ 0.1"	CBR @ 0.2"	Permeability cm/sec	
				D2216	D4318			D6913			D2974	D4792	D1557								
Composite	Groton DS	-	24B0025-01					9.9	85.5	4.6											Brown poorly graded sand
Composite	Groton US	-	24B0025-02					5.5	91.7	2.8											Brown poorly graded sand

Date Received: 2.2.24
 Reviewed By: 
 Date Reviewed: 2.7.24

This report only relates to items inspect and/or tested. No warranty, expressed or implied, is made.  
This report shall not be reproduced, except in full, without prior written approval from the Agency, as defined in ASTM E329.

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspected and/or tested. No warranty, expressed or implied, is made.

## Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	9.9	4.6	32.8	48.1	4.6	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/4"	100.0		
1/2"	96.4		
3/8"	93.9		
#4	90.1		
#10	85.5		
#20	74.5		
#40	52.7		
#60	30.8		
#100	14.1		
#200	4.6		

\* (no specification provided)

### Soil Description

Brown poorly graded sand

PL= NP      Atterberg Limits      LL= NV      PI= NP

Coefficients

D<sub>90</sub>= 4.6202      D<sub>85</sub>= 1.8990      D<sub>60</sub>= 0.5213  
D<sub>50</sub>= 0.3960      D<sub>30</sub>= 0.2447      D<sub>15</sub>= 0.1555  
D<sub>10</sub>= 0.1191      C<sub>u</sub>= 4.38      C<sub>c</sub>= 0.96

Classification

USCS= SP      AASHTO= A-3

Remarks

Source of Sample: Composite  
Sample Number: Groton DS

Depth: -

Date: 2.6.24

Thielsch Engineering Inc.

Cranston, RI


Client: ESS Laboratory  
Project: Saquanacook River Dam Removal  
Groton, MA  
Project No: 24B0025

Fig. 24B0025-01

Tested By: SP      Checked By: Kris Roland

These results are for the exclusive use of the client for whom they were obtained. This report only relates to items inspected and/or tested. No warranty, expressed or implied, is made.

## Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	5.5	2.4	52.9	36.4	2.8	

SIEVE SIZE OR DIAMETER	PERCENT FINER	SPEC.* PERCENT	PASS? (X=NO)
3/4"	100.0		
1/2"	98.7		
3/8"	97.6		
#4	94.5		
#10	92.1		
#20	83.1		
#40	39.2		
#60	15.9		
#100	7.0		
#200	2.8		

\* (no specification provided)

### Soil Description

Brown poorly graded sand

PL= NP      Atterberg Limits      LL= NV      PI= NP

Coefficients

D<sub>90</sub>= 1.2525      D<sub>85</sub>= 0.9102      D<sub>60</sub>= 0.5768  
D<sub>50</sub>= 0.5037      D<sub>30</sub>= 0.3552      D<sub>15</sub>= 0.2424  
D<sub>10</sub>= 0.1904      C<sub>u</sub>= 3.03      C<sub>c</sub>= 1.15

Classification

USCS= SP      AASHTO= A-1-b

Remarks

Source of Sample: Composite  
Sample Number: Groton US

Depth: -

Date: 2.6.24

Thielsch Engineering Inc.

Cranston, RI

Client: ESS Laboratory  
Project: Saquanacook River Dam Removal  
Groton, MA  
Project No: 24B0025

Fig. 24B0025-02

Tested By: SP      Checked By: Kris Roland



## ESS Laboratory Sample and Cooler Receipt Checklist

Client: Horsley Witten Group - TJM

ESS Project ID: 24B0025

Date Received: 2/1/2024

Project Due Date: 2/8/2024

Days for Project: 5 Day

Shipped/Delivered Via: ESS Courier

1. Air bill manifest present? ☐ No

Air No.: NA

2. Were custody seals present? ☐ No

3. Is radiation count <100 CPM? ☐ Yes

4. Is a Cooler Present? ☐ Yes

Temp: 0.5 Iced with: Ice

5. Was COC signed and dated by client? ☐ Yes

6. Does COC match bottles? ☐ Yes

7. Is COC complete and correct? ☐ Yes

8. Were samples received intact? ☐ Yes

9. Were labs informed about short holds & rushes? Yes / No ☒ NA

10. Were any analyses received outside of hold time? Yes ☒ No

11. Any Subcontracting needed? ☒ Yes / No

ESS Sample IDs: 1--2

Analysis: Grain size

TAT: 5 day

12. Were VOAs received? ☒ Yes / No

a. Air bubbles in aqueous VOAs? ☒ Yes / No

b. Does methanol cover soil completely? ☒ Yes / No / NA

13. Are the samples properly preserved? ☒ Yes / No

a. If metals preserved upon receipt: Date: 2/1/24

b. Low Level VOA vials frozen: Date: 2/1/24

Time: 1710 By/Acid Lot#: 75

Time: 1710 By: 75

Sample Receiving Notes:

14. Was there a need to contact Project Manager? Yes / ☒ No

a. Was there a need to contact the client? Yes / ☒ No

Who was contacted? \_\_\_\_\_ Date: \_\_\_\_\_ Time: \_\_\_\_\_ By: \_\_\_\_\_

Resolution:

Sample Number	Container ID	Proper Container	Air Bubbles Present	Sufficient Volume	Container Type	Preservative	Record pH (Cyanide and 608 Pesticides)
1	516557	Yes	N/A	Yes	VOA Vial	MeOH	
1	516559	Yes	N/A	Yes	VOA Vial	DI Water	
1	516560	Yes	N/A	Yes	VOA Vial	DI Water	
1	516563	Yes	N/A	Yes	Driller Jar	NP	
1	516565	Yes	N/A	Yes	8 oz jar	NP	
1	516566	Yes	N/A	Yes	8 oz jar	NP	
1	516569	Yes	N/A	Yes	4 oz. Jar	NP	
2	516558	Yes	N/A	Yes	VOA Vial	MeOH	
2	516561	Yes	N/A	Yes	VOA Vial	DI Water	
2	516562	Yes	N/A	Yes	VOA Vial	DI Water	
2	516564	Yes	N/A	Yes	Driller Jar	NP	
2	516567	Yes	N/A	Yes	8 oz jar	NP	
2	516568	Yes	N/A	Yes	8 oz jar	NP	
2	516570	Yes	N/A	Yes	4 oz. Jar	NP	

2nd Review

Were all containers scanned into storage/lab?

Initials RL

# ESS Laboratory Sample and Cooler Receipt Checklist

Client: Horsley Witten Group - TJM

ESS Project ID: 24B0025  
Date Received: 2/1/2024

- Are barcode labels on correct containers?
- Are all Flashpoint stickers attached/container ID # circled?
- Are all Hex Chrome stickers attached?
- Are all QC stickers attached?
- Are VOA stickers attached if bubbles noted?

Yes / No  
Yes / No / NA  
Yes / No / NA  
Yes / No / NA  
Yes / No / NA

Completed

By: [Signature]

Date & Time: 2/1/24 1640

Reviewed

By: [Signature]

Date & Time: 2/1/24 1711

185 Frances Avenue  
Cranston, RI 02910  
Phone: 401-461-7181  
Fax: 401-461-4486  
[www.esslaboratory.com](http://www.esslaboratory.com)

## CHAIN OF CUSTODY

ESS Lab # 2480025 Page 1 of 1

**ELECTRONIC DELIVERABLES (Final Reports are PDF)**

Turn Time (Days) ☒ > 5 ☐ 5 ☐ 4 ☐ 3 ☐ 2 ☐ 1 ☐ Same Day

Regulatory State:	Criteria:
-------------------	-----------

**Is this project for any of the following?:**

☐ CT RCP    ☐ MA MCP    ☐ RGP    ☐ Permit    ☒ 401 WQ

<input type="checkbox"/> Limit Checker	<input type="checkbox"/> State Forms	<input type="checkbox"/> EQulS
<input checked="" type="checkbox"/> Excel	<input type="checkbox"/> Hard Copy	<input type="checkbox"/> Enviro Data
<input type="checkbox"/> CLP-Like Package	<input type="checkbox"/> Other (Specify) →	

## CLIENT INFORMATION

<b>Client:</b>	Horsley Witten Group
<b>Address:</b>	112 Water St, 6 <sup>th</sup> floor Boston MA 02109
<b>Phone:</b>	857-263-8193
<b>Email</b>	nprice@horsleywitten.com
<b>Distribution</b>	procton@horsleywitten.com carmonstrong@horsleywitten.com
<b>List:</b>	aschullu@horsleywitten.com

## PROJECT INFORMATION

Project Name:	Saguanacook River Dam	Removal Client acknowledges that sampling is compliant with all EPA / State regulatory programs
Project Location:	Groton MA	
Project Number:	231244	
Project Manager:	Jonas Proctor / HW	
Bill to:	torciuch@wharsleywitten.com	
PO#:		
Quote#:		

### REQUESTED ANALYSES

ESS Lab ID	Collection Date	Collection Time	Sample Type	Sample Matrix	Sample ID	Mat	PC	EL	TO	o/o	Gr								
1	1/31/24	11:05	Composite	J 1	Groton DS	✓	✓	✓	✓	✓	✓								
1		11:05		AG 1		✓	✓	✓	✓	✓	✓								
1		11:05		AG 1		✓	✓	✓	✓	✓	✓								
1		11:05		AG 1		✓	✓	✓	✓	✓	✓								
2		2:10		J 1	Groton VS	✓	✓	✓	✓	✓	✓								
2		2:15		AG 1		✓	✓	✓	✓	✓	✓								
2		2:30		AG 1		✓	✓	✓	✓	✓	✓								
2		3:00		AG 1		✓	✓	✓	✓	✓	✓								
<b>Container Type:</b>						AC-Air Cassette	AG-Amber Glass	B-BOD Bottle	C-Cubitainer	J-Jar	O-Other	P-Poly	S-Sterile	V-Vial					
<b>Container Volume:</b>						1-100 mL	2-2.5 gal	3-250 mL	4-300 mL	5-500 mL	6-1L	7-VOA	8-2 oz	9-4 oz	10-8 oz	11-Other*			
<b>Preservation Code:</b>						1-Non Preserved	2-HCl	3-H2SO4	4-HNO3	5-NaOH	6-Methanol	7-Na2S2O3	8-ZnAce, NaOH	9-NH4Cl	10-DI H2O	11-Other*			

Sampled by : HMI

**Chain needs to be filled out neatly and completely for on time delivery.**

**Laboratory Use Only**

**Comments:** \* Please specify "Other" preservative and containers types in this space

All samples submitted are subject to ESS Laboratory's payment terms and conditions.

### Dissolved Filtration

Cooler Temperature ( $^{\circ}\text{C}$ ):  $-0.5$ 

8 oz Amber Jar      2 oz Driller Jar  
2 oz Amber Jar

☐ Lab Filter

Relinquished by (Signature)

Date \_\_\_\_\_

Time

Received by (Signature)

Relinquished by (Signature)

Date \_\_\_\_\_

Time

Received by (Signature)

Relinquished by (Signature)

Date \_\_\_\_\_

Time

Received by (Signature)

Relinquished by (Signature)

Date \_\_\_\_\_

Time

Received by (Signature)





## ATTACHMENT B

---

*ResilientMass Action Team (RMAT) Report*



## Climate Resilience Design Standards Tool Project Report

### Squannacook River

Date Created: 2/16/2024 2:14:54 PM

Created By: aschully

Date Report Generated: 2/16/2024 3:18:55 PM

Tool Version: Version 1.2

Project Contact Information: Ava Schully ([aschully@horsleywitten.com](mailto:aschully@horsleywitten.com))

## Project Summary

[Link to Project](#)

Estimated Capital Cost: \$500000.00

End of Useful Life Year: 2026

Project within mapped Environmental Justice neighborhood: No

### Ecosystem Service Scores

#### Benefits

Project Score ■ High

#### Exposure Scores

Sea Level Rise/Storm Surge ■ Not Exposed

Extreme Precipitation - ■ High

Urban Flooding Exposure

Extreme Precipitation - ■ High

Riverine Flooding Exposure

Extreme Heat ■ Moderate Exposure



## Asset Preliminary Climate Risk Rating

Number of Assets: 1

### Summary

#### Asset Risk

#### Sea Level Rise/Storm Surge

#### Extreme Precipitation - Urban Flooding

#### Extreme Precipitation - Riverine Flooding

#### Extreme Heat

river — Natural Resource project assets do not receive a preliminary climate risk rating. —

## Climate Resilience Design Standards Summary

	Target Planning Horizon	Intermediate Planning Horizon	Percentile	Return Period	Tier
Sea Level Rise/Storm Surge					
river					
Extreme Precipitation					
river	2030				Tier 1
Extreme Heat					
river	2030		th		Tier 1

## Scoring Rationale - Project Exposure Score

The purpose of the Exposure Score output is to provide a preliminary assessment of whether the overall project site and subsequent assets are exposed to impacts of natural hazard events and/or future impacts of climate change. For each climate parameter, the Tool will calculate one of the following exposure ratings: Not Exposed, Low Exposure, Moderate Exposure, or High Exposure. The rationale behind the exposure rating is provided below.

### Sea Level Rise/Storm Surge

This project received a "Not Exposed" because of the following:

- Not located within the predicted mean high water shoreline by 2030
- No historic coastal flooding at project site
- Not located within the Massachusetts Coast Flood Risk Model (MC-FRM)

### Extreme Precipitation - Urban Flooding

This project received a "High Exposure" because of the following:

- Historic flooding at the project site
- No increase to impervious area
- Maximum annual daily rainfall is within 6 to 10 inches within the overall project's useful life
- Existing impervious area of the project site is between 10% and 50%

### Extreme Precipitation - Riverine Flooding

This project received a "High Exposure" because of the following:

- Project site has a history of riverine flooding
- Part of the project is within a mapped FEMA floodplain, outside of the Massachusetts Coast Flood Risk Model (MC-FRM)
- Part of the project is within 100ft of a waterbody
- Project is potentially susceptible to riverine erosion

### Extreme Heat

This project received a "Moderate Exposure" because of the following:

- Existing impervious area of the project site is between 10% and 50%
- 10 to 30 day increase in days over 90 deg. F within project's useful life
- Located within 100 ft of existing water body
- No increase to the impervious area of the project site
- No tree removal

## Scoring Rationale - Asset Preliminary Climate Risk Rating

A Preliminary Climate Risk Rating is determined for each infrastructure and building asset by considering the overall project Exposure Score and responses to Step 4 questions provided by the user in the Tool. Natural Resource assets do not receive a risk rating. The following factors are what influenced the risk ratings for each asset.

#### Asset - river

Primary asset criticality factors influencing risk ratings for this asset:

No score available

## Project Climate Resilience Design Standards Output

Climate Resilience Design Standards and Guidance are recommended for each asset and climate parameter. The Design Standards for each climate parameter include the following: recommended planning horizon (target and/or intermediate), recommended return period (Sea Level Rise/Storm Surge and Precipitation) or percentile (Heat), and a list of applicable design criteria that are likely to be affected by climate change. Some design criteria have numerical values associated with the recommended return period and planning horizon, while others have tiered methodologies with step-by-step instructions on how to estimate design values given the other recommended design standards.

Asset: river

Natural Resources

### Sea Level Rise/Storm Surge

#### Applicable Design Criteria

**Projected Tidal Datums:** NOT APPLICABLE

**Projected Water Surface Elevation:** NOT APPLICABLE

**Projected Wave Action Water Elevation:** NOT APPLICABLE

**Projected Wave Heights:** NOT APPLICABLE

*Return Period Recommendations for natural resource assets and subsequent projected values are provided as a consideration for users, not a formal standard. Users should follow industry best practices for designing natural resource assets in coordination with the appropriate regulatory agencies.*

**Projected Duration of Flooding:** NOT APPLICABLE

**Projected Design Flood Velocity:** NOT APPLICABLE

**Projected Scour & Erosion:** NOT APPLICABLE

### Extreme Precipitation

Target Planning Horizon: 2030

**LIMITATIONS:** The recommended Standards for Total Precipitation Depth & Peak Intensity are determined by the user drawn polygon and relationships as defined in the Supporting Documents. The projected Total Precipitation Depth values provided through the Tool are based on the climate projections developed by Cornell University as part of EEA's Massachusetts Climate and Hydrologic Risk Project, GIS-based data as of 10/15/21. For additional information on the methodology of these precipitation outputs, see Supporting Documents.

While Total Precipitation Depth & Peak Intensity for 24-hour Design Storms are useful to inform planning and design, it is recommended to also consider additional longer- and shorter-duration precipitation events and intensities in accordance with best practices. Longer-duration, lower-intensity storms allow time for infiltration and reduce the load on infrastructure over the duration of the storm. Shorter-duration, higher-intensity storms often have higher runoff volumes because the water does not have enough time to infiltrate infrastructure systems (e.g., catch basins) and may overflow or back up during such storms, resulting in flooding. In the Northeast, short-duration high intensity rain events are becoming more frequent, and there is often little early warning for these events, making it difficult to plan operationally. While the Tool does not provide recommended design standards for these scenarios, users should still consider both short- and long-duration precipitation events and how they may impact the asset.

The projected values, standards, and guidance provided within this Tool may be used to inform plans and designs, but they do not provide guarantees for future conditions or resilience. The projected values are not to be considered final or appropriate for construction documents without supporting engineering analyses. The guidance provided within this Tool is intended to be general and users are encouraged to do their own due diligence

#### Applicable Design Criteria

**Tiered Methodology:** Tier 1

**Projected Total Precipitation Depth & Peak Intensity for 24-hr Design Storms:** APPLICABLE

Asset Name	Recommended Planning Horizon	Recommended Return Period (Design Storm)	Projected 24-hr Total Precipitation Depth (inches)	Step-by-Step Methodology for Peak Intensity
river	2030	25-Year (4%)	6.6	<a href="#">Downloadable Methodology. PDF</a>

*Return Period Recommendations for natural resource assets and subsequent projected values are provided as a consideration for users, not a formal standard. Users should follow industry best practices for designing natural resource assets in coordination with the appropriate regulatory agencies.*

**ATTENTION: This is a Tier 1 project.** It is advised to compare the extreme precipitation output values to the NOAA+ methodology to calculate total precipitation depth for 24-hr design storms.

This methodology can be found in the following PDF. ([Link](#)).

**Projected Riverine Peak Discharge & Peak Flood Elevation:** APPLICABLE  
[Methodology to Estimate Projected Values](#) : Tier 1

### **Extreme Heat**

Target Planning Horizon: 2030  
Percentile: Does not apply

#### **Applicable Design Criteria**

**Tiered Methodology:** Tier 1

**Projected Annual/Summer/Winter Average Temperatures:** APPLICABLE  
[Methodology to Estimate Projected Values](#) : Tier 1

**Projected Heat Index:** NOT APPLICABLE

**Projected Growing Degree Days:** NOT APPLICABLE

**Projected Days Per Year With Max Temp > 95°F, >90°F, <32°F:** NOT APPLICABLE

**Projected Number of Heat Waves Per Year & Average Heat Wave Duration:** NOT APPLICABLE

**Projected Cooling Degree Days & Heating Degree Days (base = 65°F):** NOT APPLICABLE

## Project Inputs

### Core Project Information

Name:	Squannacook River
Given the expected useful life of the project, through what year do you estimate the project to last (i.e. before a major reconstruction/renovation)?	2026
Location of Project:	Groton
Estimated Capital Cost:	\$500,000
Who is the Submitting Entity?	Private Other Horsley Witten Group Ava Schully (aschully@horsleywitten.com)
Is this project being submitted as part of a state grant application?	No
Which grant program?	
What stage are you in your project lifecycle?	No physical assets planned for this project
Is climate resiliency a core objective of this project?	Yes
Is this project being submitted as part of the state capital planning process?	No
Is this project being submitted as part of a regulatory review process or permitting?	No
Brief Project Description:	Through this project, HW will develop feasibility assessments and preliminary designs for the potential removal of the Squannacook River Dam in North Andover, MA. The primary goals of this initial feasibility project are: 1.) Identify the anticipated benefits and challenges to each specific dam removal in order to assess its overall feasibility and then rank it among other potential dam removal projects for further project advancement; and 2.) Create preliminary project designs that can then be further advanced during later project phases, assuming that the overall project feasibility and ranking proves suitable for further advancement.

Project Submission Comments:

### Project Ecosystem Service Benefits

#### Factors Influencing Output

- ✓ This is an ecological restoration project
- ✓ Project provides flood protection through nature-based solutions
- ✓ Project reduces storm damage
- ✓ Project improves water quality
- ✓ Project protects fisheries, wildlife, and plant habitat
- ✓ Project protects land containing shellfish
- ✓ Project provides recreation
- ✓ Project provides cultural resources/education

#### Factors to Improve Output

- ✓ Protect public water supply by reducing the risk of contamination, pollution, and/or runoff of surface and groundwater sources used for human consumption
- ✓ Increase plants, trees, and/or other vegetation to provide oxygen production

#### Is the primary purpose of this project ecological restoration?

Yes

#### Project Benefits

Provides flood protection through nature-based solutions	Yes
Reduces storm damage	Yes
Recharges groundwater	No
Protects public water supply	Maybe
Filters stormwater using green infrastructure	No
Improves water quality	Yes
Promotes decarbonization	No
Enables carbon sequestration	No
Provides oxygen production	Maybe
Improves air quality	No
Prevents pollution	No
Remediates existing sources of pollution	No
Protects fisheries, wildlife, and plant habitat	Yes
Protects land containing shellfish	Yes
Provides pollinator habitat	No
Provides recreation	Yes
Provides cultural resources/education	Yes



### Project Climate Exposure

Is the primary purpose of this project ecological restoration?	Yes
Does the project site have a history of coastal flooding?	No
Does the project site have a history of flooding during extreme precipitation events (unrelated to water/sewer damages)?	Yes
Does the project site have a history of riverine flooding?	Yes
Does the project result in a net increase in impervious area of the site?	No
Are existing trees being removed as part of the proposed project?	No

### Project Assets

Asset: river  
Asset Type: Aquatic Ecosystems  
Asset Sub-Type: Large- and mid-size rivers  
Construction Type: Dam Removal  
Construction Year: 2025  
Monitoring Frequency: 1

### Report Comments

N/A

# ATTACHMENT C

---

*60% Design Plans*




# DAM REMOVAL - 60% DESIGN

## SQUANNACOOK RIVER DAM


### GROTON & SHIRLEY, MASSACHUSETTS

SEPTEMBER 2025



MASSACHUSETTS

Graphic Scale  
0 150000  
SCALE IN FEET  
1:150000



TOWN

Graphic Scale  
0 12000  
SCALE IN FEET  
1:12000



VICINITY MAP

Graphic Scale  
1-inch = 1000-feet

Sheet List Table	
Sheet Number	Sheet Title
1	COVER
2	CONSTRUCTION NOTES
3	OVERALL EXISTING CONDITIONS
4	EXISTING CONDITIONS
5	CROSS SECTIONS (1)
6	CROSS SECTIONS (2)
7	CROSS SECTIONS (3)
8	LONGITUDINAL PROFILE
9	SITE PREPARATION AND DEMOLITION PLAN
10	SEDIMENT TRANSPORT AND GRADING PLAN
11	RESTORATION AND STABILIZATION PLAN


- GENERAL NOTES:
- THIS PLAN SET IS 60% DESIGN LEVEL ONLY AND NOT FOR CONSTRUCTION.
  - ABUTTER INFORMATION FROM ASSESSOR'S MAP.
  - SITE INFORMATION:
    - PLAT: 101
    - LOT: 10
    - ADDRESS: 6 WEST MAIN STREET, GROTON, MA
    - ZONING DISTRICT: BUSINESS 1

Plan Set:

DAM REMOVAL - 60% DESIGN  
SQUANNACOOK RIVER DAM  
GROTON & SHIRLEY, MASSACHUSETTS


Prepared For:

Town of Groton  
173 Main Street  
Groton, MA  
(978) 448-1162



Prepared By:

Horsley Witten Group, Inc.  
Sustainable Environmental Solutions  
www.horsleywitten.com



Headquarters  
90 Route 6A, Unit 1  
Sandwich, MA 02563  
Phone: (508) 833-6600  
Fax: (508) 833-3150

112 Water Street, 6th Floor  
Boston, MA 02109  
Phone: (857) 263-8193

1 Turks Head Place, Suite 300  
Providence, RI 02903  
Phone: (401) 272-1717  
Fax: (401) 437-8368

113 R2 Water Street  
Exeter, NH 03833  
Phone: (603) 658-1660

Date Issued:  
SEPTEMBER 2025

Designed By:  
JMP/CE

Drawn By:  
JMP/CE

Checked By:  
NP

Registration:

DRAFT

NOT FOR

CONSTRUCTION

Revisions

Rev.	Date	By	Appr.	Description

Project Number:  
23144

Sheet Number:  
1 of 11

Drawing Number:  
C-1



1. ALL SITE WORK TO COMPLETE THIS PROJECT AS INDICATED ON THE DRAWINGS AND IN THE SPECIFICATIONS IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
2. IMMEDIATELY CONTACT AND COORDINATE WITH THE ENGINEER AND OWNER IF ANY DEVIATION OR ALTERATION OF THE WORK PROPOSED ON THESE DRAWINGS IS REQUIRED.
3. UTILIZE ALL PRECAUTIONS AND MEASURES TO ENSURE THE SAFETY OF THE PUBLIC, ALL PERSONNEL AND PROPERTY DURING CONSTRUCTION IN ACCORDANCE WITH OSHA STANDARDS, INCLUDING THE INSTALLATION OF TEMPORARY FENCING BARRICADES, STREET LIGHTING, CONES, POLICE DETAIL AND/OR FLAGMEN AS DETERMINED NECESSARY BY THE TOWN. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF POLICE DETAIL, AND FOR COORDINATING WITH THE LOCAL OR STATE POLICE DEPARTMENT FOR ALL REQUIRED POLICE DETAIL.
4. MAKE ALL NECESSARY CONSTRUCTION NOTIFICATIONS AND APPLY FOR AND OBTAIN ALL NECESSARY CONSTRUCTION PERMITS, PAY ALL FEES INCLUDING POLICE DETAILS AND POST ALL BONDS, IF NECESSARY, ASSOCIATED WITH THE SAME, AND COORDINATE WITH ASHLAND CONSERVATION COMMISSION, THE DEPARTMENT OF PUBLIC WORKS, AND THE ENGINEER.
5. ALL EXISTING CONDITIONS SHOWN ARE APPROXIMATE AND ARE BASED ON THE BEST INFORMATION AVAILABLE. PRIOR TO THE START OF CONSTRUCTION, VERIFY THAT THE PROPOSED IMPROVEMENTS SHOWN ON THE PLANS DO NOT CONFLICT WITH ANY KNOWN EXISTING OR OTHER PROPOSED IMPROVEMENTS. IF ANY CONFLICTS ARE DISCOVERED, NOTIFY THE OWNER AND THE ENGINEER PRIOR TO INSTALLING ANY PORTION OF THE SITE WORK WHICH WOULD BE AFFECTED.
6. IMPORT ONLY CLEAN MATERIAL. MATERIAL FROM AN EXISTING OR FORMER 21E SITE AS DEFINED BY THE MASSACHUSETTS CONTINGENCY PLAN 310 CMR 40.0000 WILL NOT BE ACCEPTED.
7. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH AND MAINTAIN ALL CONTROL POINTS AND BENCHMARKS DURING CONSTRUCTION INCLUDING BENCHMARK LOCATIONS AND ELEVATIONS AT CRITICAL AREAS. COORDINATE WITH THE ENGINEER THE LOCATION OF ALL CONTROL POINTS AND BENCHMARKS.
8. SITE LAYOUT SURVEY REQUIRED FOR CONSTRUCTION MUST BE PROVIDED BY THE CONTRACTOR AND PERFORMED BY A MASSACHUSETTS REGISTERED PROFESSIONAL LAND SURVEYOR. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH THE SURVEYOR FOR ALL SITE SURVEY WORK.
9. MAINTAIN ALL GRADE STAKES SET BY THE SURVEYOR. GRADE STAKES ARE TO REMAIN UNTIL A FINAL INSPECTION OF THE ITEM HAS BEEN COMPLETED BY THE ENGINEER. RE-STAKING OF PREVIOUSLY SURVEYED SITE FEATURES IS THE RESPONSIBILITY (INCLUDING COST) OF THE CONTRACTOR.
10. UNLESS OTHERWISE INDICATED ON THE DRAWINGS AND/OR IN THE SPECIFICATIONS, ALL SITE CONSTRUCTION MATERIALS AND METHODOLOGIES ARE TO CONFORM TO THE MOST RECENT VERSION OF THE MASSACHUSETTS DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS
11. PROVIDE ALL CONSTRUCTION SERVICE IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS REGARDING NOISE, VIBRATION, DUST, SEDIMENTATION CONTAINMENT, AND TRENCH WORK.
12. COLLECT SOLID WASTES AND STORE IN A SECURED DUMPSTER. THE DUMPSTER MUST MEET ALL LOCAL AND STATE SOLID WASTE MANAGEMENT REGULATIONS.
13. RESTORE ALL SURFACES EQUAL TO THEIR ORIGINAL CONDITION AFTER CONSTRUCTION IS COMPLETE PER SPECIFICATIONS. LEAVE ALL AREAS NOT DISTURBED BY CONSTRUCTION IN THEIR NATURAL STATE. TAKE CARE TO PREVENT DAMAGE TO SHRUBS, TREES, OTHER LANDSCAPING AND/OR NATURAL FEATURES. WHEREAS THE PLANS DO NOT SHOW ALL LANDSCAPE FEATURES, EXISTING CONDITIONS MUST BE VERIFIED BY THE CONTRACTOR IN ADVANCE OF THE WORK.
14. REGULARLY INSPECT THE PERIMETER OF THE PROPERTY TO CLEAN UP AND REMOVE LOOSE CONSTRUCTION DEBRIS BEFORE IT LEAVES THE SITE. PROMPTLY REMOVE ALL DEMOLITION DEBRIS FROM THE SITE TO AN APPROVED DUMP SITE.
15. ALL TRUCKS LEAVING THE SITE MUST BE COVERED.
16. AT THE END OF CONSTRUCTION, REMOVE ALL CONSTRUCTION DEBRIS AND SURPLUS MATERIALS FROM THE SITE AS INDICATED IN THE SPECIFICATIONS. PERFORM A THOROUGH INSPECTION OF THE WORK PERIMETER. COLLECT AND REMOVE ALL MATERIALS AND BLOWN OR WATER CARRIED DEBRIS FROM THE SITE.

THIS PLAN SET DOES NOT INCLUDE DETAILS & SPECIFICATIONS FOR ALL DEMOLITION WORK REQUIRED WITHIN THE PROPOSED CONSTRUCTION LIMITS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE OWNER AND OTHER PROJECT ENGINEERS INVOLVED WITH THE PROPOSED NEW CONSTRUCTION TO DEVELOP A SUITABLE DEMOLITION PLAN, WHICH WILL ALLOW THE FACILITIES TO REMAIN IN OPERATION DURING THE ENTIRETY OF CONSTRUCTION.

1. UNLESS OTHERWISE NOTED, THE CONTRACTOR IS RESPONSIBLE FOR THE RELOCATION, DEMOLITION, REMOVAL AND DISPOSAL, IN A LOCATION APPROVED BY ALL GOVERNING AUTHORITIES, OF ALL EXISTING SITE ELEMENTS AND STRUCTURES INCLUDING, BUT NOT LIMITED TO: REMAINING CONCRETE FOUNDATIONS, EXISTING SIDEWALKS, FENCES, BOLLARDS, POSTS, PLANTING BEDS, TREES, SHRUBS, AND ALL OTHER STRUCTURES SHOWN AND NOT SHOWN WITHIN CONSTRUCTION LIMITS, AND WHERE NEEDED, TO ALLOW FOR CONSTRUCTION.
2. REMOVE ALL DEBRIS FROM THE SITE AND DISPOSE OF THE DEBRIS IN A PROPER AND LEGAL MANNER.
3. OBTAIN ALL PERMITS REQUIRED FOR DEMOLITION AND DISPOSAL.
4. PRIOR TO DEMOLITION OCCURRING, ALL EROSION AND WATER CONTROL DEVICES ARE TO BE INSTALLED.
5. 401 WATER QUALITY CERTIFICATION MUST BE RECEIVED PRIOR TO PASSIVE RELEASE OF SEDIMENT.

1. IF Dewatering is required during excavation, implement the following measures to ensure that the water table is lowered to the required level:
  - INSTALL A DEWATERING BASIN AS INDICATED IN A DEWATERING BASIN PLAN, TO BE PROVIDED BY THE ENGINEER, AND PUMP A MINIMUM OF 10% EXCESS WATER TO THE DRAINAGE PLAN TO BE PROVIDED BY THE ENGINEER. DISCHARGE TO BASIN TO PREVENT SEDIMENTS FROM LEAVING THE CONSTRUCTION AREA. INSTALL ADDITIONAL BASINS IF REQUIRED. INSTALL ADDITIONAL BASINS AS INDICATED IN THE DRAINAGE PLAN TO BE PROVIDED BY THE ENGINEER. (SEE BASINS) WITHIN THE LIMIT OF DISTURBANCE INDICATED BY THE SILT FENCE OR STRAWBALES, OR AS SHOWN ON THE PLANS.
2. PRIOR TO ANY DEWATERING, THE DEWATERING PLAN MUST BE APPROVED BY THE ENGINEER.
3. IF Dewatering is necessary during construction, implement the proper ESC measures on site to prevent erosion and sediment runoff. THESE MEASURES CAN INCLUDE DEWATERING BAGS, STRAWBALES, SILT FENCES, SILT SOCKS AND/OR OTHER APPROVED DEVICES AS INDICATED IN THE DETAILS.

1. SURVEY AND STAKE THE PROPOSED LIMIT OF DISTURBANCE AND LIMIT OF SEDIMENTATION BARRIERS.
2. PLACE SEDIMENTATION BARRIERS AS INDICATED ON DRAWINGS AND STAKED OUT IN THE FIELD. UNDER NO CIRCUMSTANCES IS THE LIMIT OF WORK TO EXTEND BEYOND THE SEDIMENTATION BARRIERS/LIMIT OF DISTURBANCE AS INDICATED ON DRAWINGS AS APPROVED BY THE GROTON AND SHIRLEY CONSERVATION COMMISSIONS AND DEPARTMENT OF ENVIRONMENTAL PROTECTION (DEP).
3. INSTALL TEMPORARY CONSTRUCTION ENTRANCES IN LOCATIONS INDICATED ON DRAWINGS. NO OTHER ENTRANCES ARE TO BE USED TO GAIN ACCESS TO THE SITE BY ANY CONSTRUCTION OR DELIVERY VEHICLES.
4. CONSTRUCTION ACCESS TO THE RIVER MAY REQUIRE A CRANE, ACCESS RAMP, OR ADDITIONAL WATER CONTROLS AT THE CONTRACTOR'S DISCRETION. THE CONTRACTOR SHALL INDICATE A PREFERRED ACCESS METHOD TO THE ENGINEER FOR APPROVAL.
5. BEGIN CLEARING THE SITE AS REQUIRED IN ORDER TO ACCESS THE DAM.
6. EXAMINE THE INTEGRITY OF THE EXISTING DAM AND DETERMINE MEANS OF REMOVAL. DEMOLITION METHODOLOGY TO BE APPROVED BY THE ENGINEER AND THE GROTON AND SHIRLEY CONSERVATION AGENTS.
7. LOWER IMPOUNDMENT WATER LEVEL USING LOW LEVEL OUTLET LOCATED BELOW AUXILIARY SPILLWAY.
8. IF ANY DOWATERING OR FLOW CONTROL IS REQUIRED, CONTRACTOR TO PROVIDE DOWATERING PLAN FOR APPROVAL BY ENGINEER. DEMOLISH AS NECESSARY.
9. DEMOLISH EXPOSED PORTION OF THE DAM, WORKING INCREMENTALLY, AS NEEDED. FLOW AND SEDIMENT TRANSPORT SHALL BE OBSERVED THROUGH REMOVAL PROCESS FOR POTENTIAL NEGATIVE DOWNSTREAM IMPACTS BEFORE PROCEEDING.
10. IDENTIFY VERTICAL LOCATION OF BEDROCK OR COMPETENT BOTTOM BELOW DAM AND EVALUATE CHANNEL RECONSTRUCTION BASED ON OBSERVED BEDROCK PRESENCE. ENSURE THAT AN ADEQUATE LOW-FLOW CHANNEL IS PRESENT FOR FISH PASSAGE, AS DIRECTED BY THE ENGINEER. Dewater as necessary, according to approved dewatering plan.
11. ONCE DAM IS ENTIRELY REMOVED, INSTALL BANK STABILIZATION MEASURES. DO NOT DESTABILIZE SURROUNDING AREAS DURING THIS PROCESS. ACCUMULATED COARSE MATERIAL MAY BE REDISTRIBUTED TO BANKS DURING THE DAM REMOVAL PROCESS AS NEEDED.
12. MONITOR IMPOUNDMENT TO ENSURE THAT NATIVE SEEDBANK NATURALLY REVEGETATES WITHIN FIRST 2 WEEKS OF THE GROWING SEASON.
13. SWEEP THE ROADWAY TO REMOVE ALL SEDIMENTS.
14. ENGINEER TO APPROVE THE REMOVAL OF ALL TEMPORARY SOIL EROSION AND SEDIMENTATION CONTROL MEASURES FOLLOWING VEGETATIVE ESTABLISHMENT OF ALL DISTURBED AREAS AND DETERMINE WHEN THE CONTRIBUTING AREA HAS REACHED A MINIMUM OF 80% STABILIZATION.
15. MONITOR DISTURBED AREA AND EVALUATE WHETHER OR NOT ADDITIONAL EROSION CONTROL SEED MIX APPLICATIONS OR OTHER MEASURES ARE WARRANTED FOR IMPROVED STABILIZATION.

1. ALL CUT AND FILL SLOPES SHALL BE 3:1 OR FLATTER UNLESS OTHERWISE NOTED.

2.

3. EXISTING GRADE CONTOUR INTERVALS SHOWN AT 1 FOOT.

4. PROPOSED GRADE CONTOUR INTERVALS SHOWN AT 1 FOOT.

5. PROPOSED ELEVATIONS ARE SHOWN TO FINISH GRADE UNLESS NOTED OTHERWISE.

6. ALL EARTHWORK AND SITE PREPARATION MUST BE DONE IN STRICT ACCORDANCE WITH THE RECOMMENDATIONS OF ANY SUBSURFACE INVESTIGATION OR GEOTECHNICAL REPORTS PREPARED FOR THIS SITE.

7. GENERAL AREA UPSTREAM OF DAM SHALL RECEIVE MINIMAL EARTHWORK EXCEPT AS NEEDED TO REDISTRIBUTE BANK STABILIZATION MATERIALS. ALL EARTH MOVING ACTIVITIES SUBSEQUENT TO DAM REMOVAL MUST BE APPROVED BY THE CONSERVATION AGENTS AND BY THE TENANTS AND THE EARTHWORK SHALL BE CONFINED TO BANK STABILIZATION ACTIVITIES AND CONSTRUCTION OF A LOW FLOW CHANNEL, AS REQUIRED.

1. DESIGNATE THE SITE CONSTRUCTION FOREMAN AS THE ON-SITE PERSONNEL RESPONSIBLE FOR THE DAILY INSPECTION AND MAINTENANCE OF ALL SEDIMENT AND EROSION CONTROLS AND IMPLEMENTATION OF ALL NECESSARY MEASURES TO CONTROL EROSION AND PREVENT SEDIMENT FROM LEAVING THE SITE.
2. INSTALL ALL EROSION AND SEDIMENT CONTROL (ESC) MEASURES AS INDICATED ON DRAWINGS IN CONJUNCTION WITH THE CONSERVATION AGENCY, AND ENGINEER BEFORE ANY CONSTRUCTION ACTIVITIES BEGIN. INSPECT, MAINTAIN REPAIR AND REPLACE EROSION CONTROL MEASURES AS NECESSARY. DURING THE ENTIRE CONSTRUCTION PERIOD OF THE PROJECT, THE SITE PERIMETER EROSION CONTROLS ARE THE DESIGNATED LIMIT OF WORK. INFORM ALL PERSONNEL WORKING ON THE PROJECT SITE THAT NO CONSTRUCTION ACTIVITY IS TO OCCUR BEYOND THE LIMIT OF WORK AT ANY TIME THROUGHOUT THE CONSTRUCTION PERIOD.
3. MAINTAIN A MINIMUM SURPLUS OF 100 FEET OF EROSION CONTROL BARRIER (SILT FENCE AND/OR SILT SOCK) ONSITE AT ALL TIMES. IF DETERMINING IS REQUIRED, PROVIDE EXTRA DETERAWERING BAG.
4. PROTECT THE ADJACENT RESOURCE AREA FROM SEDIMENTATION DURING PROJECT CONSTRUCTION UNTIL ACCEPTANCE BY THE OWNER & IN CONFORMANCE WITH THE ORDER OF CONDITIONS.
5. PROVIDE CONSTRUCTION EXITS AS INDICATED ON DRAWINGS TO SHED DIRT FROM CONSTRUCTION VEHICLE TIRES. CLEAN AND/OR REPLACE THE CRUSHED STONE PAD, AS NECESSARY, TO MAINTAIN ITS EFFECTIVENESS.
6. KEEP THE LIMIT OF CLEARING, GRADING AND DISTURBANCES TO A MINIMUM WITHIN THE PROPOSED AREA OF CONSTRUCTION. PHASE THE SITE WORK IN A MANNER TO MINIMIZE RISK OF EXPOSED SOIL. IF TREES ARE TO BE CUT ON THE ENTIRE SITE, CLEAR AND GRADUALLY THOSE AREAS WHICH ARE ABOVE AND/OR CONSTRUCTION. PROPERLY INSTALL THE SEDIMENTATION CONTROLS PRIOR TO BEGINNING ANY LAND CLEARING ACTIVITY AND/OR OTHER CONSTRUCTION RELATED WORK.
7. MONITOR LOCAL WEATHER REPORTS DURING CONSTRUCTION AND PRIOR TO SCHEDULING EARTH/MOVING OR OTHER CONSTRUCTION ACTIVITIES WHICH LEAVE LARGE DISTURBED AREAS UNSTABILIZED. IF INCLEMENT WEATHER IS PREDICTED, USE BEST PROFESSIONAL JUDGEMENT AND GOOD CONSTRUCTION PRACTICES WHEN SCHEDULING CONSTRUCTION ACTIVITIES AND ENSURE THE NECESSARY EROSION CONTROL DEVICES ARE INSTALLED AND FUNCTIONING PROPERLY TO MINIMIZE EROSION FROM ANY IMPENDING WEATHER EVENTS.
8. INSPECT EROSION AND SEDIMENT CONTROL DEVICES AND STABILIZED SLOPES ON A WEEKLY BASIS AND AFTER EACH RAINFALL EVENT OF 0.25 INCHES OR GREATER. REPAIR IDENTIFIED PROBLEMS WITHIN 24 HOURS TO ENSURE EROSION AND SEDIMENT CONTROLS ARE IN GOOD WORKING ORDER. RESET OR REPLACE MATERIALS AS REQUIRED.
9. SURROUND THE PERIMETER OF SOIL STOCKPILES WITH SILT SOCK OR SILT FENCE.
10. DISTURBED AREAS AND SLOPES MUST NOT BE LEFT UNATTENDED OR EXPOSED FOR EXCESSIVE PERIODS OF TIME SUCH AS THE INACTIVE WINTER SEASON. PROVIDE APPROPRIATE STABILIZATION PRACTICES ON ALL DISTURBED AREAS AS SOON AS POSSIBLE BUT NOT MORE THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT AREA HAS TEMPORARILY OR PERMANENTLY CEASED. REPAIR TEMPORARY AREAS HAVING A SLOPE GRATER THAN 4:1 WITH EROSION BLANKETS OR APPROVED EQUAL UNTIL THE SITE IS PROPERLY STABILIZED. TEMPORARY SWALES MAY ALSO BE REQUIRED IF DETERMINED NECESSARY IN THE FIELD BY THE ENGINEER.
11. INSTALL A SILT SACK OR APPROVED EQUIVLENT IN EACH EXISTING CATCH-BASIN RECEIVING RUNOFF FROM THE SITE. UPON THE INSTALLATION OF EACH CATCH BASIN, INSTALL A SILT SACK OR APPROVED EQUIVLENT. INSPECT SILT SACKS, AFTER EACH SIGNIFICANT STORM EVENT AND REMOVE AND EMPTY AS NEEDED FOR THE DURATION OF THE CONSTRUCTION PERIOD.
12. CONTAIN ALL SEDIMENT ONSITE. SWEEP ALL EXITS FROM THE SITE AS NECESSARY INCLUDING ANY SEDIMENT TRACKING. SWEEP PAVED AREAS AS NEEDED TO REMOVE SEDIMENT AND POTENTIAL POLLUTANTS ACCUMULATED DURING SITE CONSTRUCTION.
13. REMOVE ACCUMULATED SEDIMENT FROM ALL TEMPORARY PRACTICES AND DISPOSE OF IN A PRE-APPROVED LOCATION.
14. PROVIDE ON SITE OR MAKE READILY AVAILABLE THE NECESSARY EQUIPMENT AND SITE PERSONNEL DURING CONSTRUCTION HOURS FOR THE DURATION OF THE PROJECT TO ENSURE ALL EROSION AND SEDIMENTATION CONTROL DEVICES ARE PROPERLY MAINTAINED AND REPAIRED IN A TIMELY AND RESPONSIBLE MANNER. IF SITE WORK IS SUSPENDED DURING THE WINTER MONTHS THE PROJECTOR MUST CONTINUE TO PROVIDE PERSONNEL AND EQUIPMENT EITHER ON SITE OR READILY AVAILABLE TO PROPERLY MAINTAIN AND REPAIR ALL EROSION AND SEDIMENTATION CONTROL DEVICES IN A TIMELY AND RESPONSIBLE MANNER.
15. CONTROL DUST BY WATERING OR OTHER APPROVED METHODS AS NECESSARY, OR AS DIRECTED BY THE ENGINEER.
16. SEDIMENT MANAGEMENT TO BE DETERMINED IN CONSULTATION WITH MASSEP DURING PERMITTING PROCESS.

TOTAL LIMIT OF WORK (SF)		25,900					
	Alteration - Immediate LOW		Notes	Alteration - Overall Impact Area			Notes
Resource Area	Temporary	Permanent	Most alterations will be Temporary (i.e., within limit of work)	Existing	Proposed	Overall Change	
	(SF)	(SF)	Permanent impacts ar those in which resource areas are converted, lost, or from which structures are removed.				
Bordering Vegetated Wetland (BVW)	0	0		0	195,070	+195,070	Converted from LUW
Bank (MA) (linear feet)	2,010	0					
Bank (Groton) (linear feet)	2,020	0		4,560	2,930	-1,630	Reduced impoundment Groton bank assumed equivalent to MA bank
Land Under Water (area below OHW)	18,950	0		274,780	79,710	-195,070	Converted to BVW
Flood Zone (BLSF)	4,230	0		134,500	45,620	-88,880	Reduced 100-year flood extents
<b>Riverfront Area</b>							
RA altered within 0-100 feet	4,910	0	Equivalent to Buffer 0-100 alterations	246,520	208,950	-37,570	
RA altered within 100-200 feet	1,950	0		238,060	178,760	-59,300	
<b>Total Riverfront Area altered</b>	6,860	0		484,580	387,710	-96,870	Existing RA will decrease by 22% in Overall Impact Area
<b>Buffer Zone</b>							
altered from 0-25 feet (Shirley only)	45	0		73,290	73,290	0	
altered from 0-50 feet (both towns)	2,670	0		138,170	138,170	0	
altered from 50-100 feet	2,240	0		108,350	108,350	0	
<b>Total Alteration 0-100 feet</b>	4,910	0	Equivalent to RA 0-100 alterations	246,520	246,520	0	Luw converted to BVW, so no net reduction in buffer zone
	Area	Volume					
<b>Dredging &amp; Filling</b> (below OHW)	(SF)	(CY)					
Dredging	-4,510	-1,070	Removal of dam and concrete pads. Redistribution of coarse sediment.				
Filling	6,740	650	Constructed banks and scour protection				
Net Dredge/Fill	2,230	-420					




































<div>Project Number: 23144</div> <div>Sheet: 2 of 11</div>										<div>Project Title: DAM REMOVAL - 60% DESIGN</div> <div>Client: SQUANNACOOK RIVER DAM</div> <div>Location: GROTON &amp; SHIRLEY, MASSACHUSETTS</div>										<div>Plan Title: CONSTRUCTION NOTES</div> <div>Plan Set: DAM REMOVAL - 60% DESIGN</div>										<div>Survey Provided By: Horsley Witten Group, Inc.</div> <div>Address: 90 Route 6A, Sandwich, MA 02563</div> <div>Phone: 508-833-3150</div> <div>Dated: November 20, 2024</div>										<div>Prepared For: Town of Groton</div> <div>Address: 173 Main Street, Groton, MA</div> <div>Phone: (978) 448-1162</div> <div>Fax: - -</div>										<div>Registration:</div> <div>DRAFT NOT FOR CONSTRUCTION</div>										<div>Revisions</div> <table><tr><th>Rev</th><th>Date</th><th>By</th><th>Asgr</th><th>Description</th></tr><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table>										Rev	Date	By	Asgr	Description	1					2					3					4					5					6					7					8					9					10				
Rev	Date	By	Asgr	Description																																																																																																																								
1																																																																																																																												
2																																																																																																																												
3																																																																																																																												
4																																																																																																																												
5																																																																																																																												
6																																																																																																																												
7																																																																																																																												
8																																																																																																																												
9																																																																																																																												
10																																																																																																																												
<div>Project Number: 23144</div> <div>Sheet: 2 of 11</div>										<div>Project Title: DAM REMOVAL - 60% DESIGN</div> <div>Client: SQUANNACOOK RIVER DAM</div> <div>Location: GROTON &amp; SHIRLEY, MASSACHUSETTS</div>										<div>Plan Title: CONSTRUCTION NOTES</div> <div>Plan Set: DAM REMOVAL - 60% DESIGN</div>										<div>Survey Provided By: Horsley Witten Group, Inc.</div> <div>Address: 90 Route 6A, Sandwich, MA 02563</div> <div>Phone: 508-833-3150</div> <div>Dated: November 20, 2024</div>										<div>Prepared For: Town of Groton</div> <div>Address: 173 Main Street, Groton, MA</div> <div>Phone: (978) 448-1162</div> <div>Fax: - -</div>										<div>Registration:</div> <div>DRAFT NOT FOR CONSTRUCTION</div>										<div>Revisions</div> <table><tr><th>Rev</th><th>Date</th><th>By</th><th>Asgr</th><th>Description</th></tr><tr><td>1</td><td></td><td></td><td></td><td></td></tr><tr><td>2</td><td></td><td></td><td></td><td></td></tr><tr><td>3</td><td></td><td></td><td></td><td></td></tr><tr><td>4</td><td></td><td></td><td></td><td></td></tr><tr><td>5</td><td></td><td></td><td></td><td></td></tr><tr><td>6</td><td></td><td></td><td></td><td></td></tr><tr><td>7</td><td></td><td></td><td></td><td></td></tr><tr><td>8</td><td></td><td></td><td></td><td></td></tr><tr><td>9</td><td></td><td></td><td></td><td></td></tr><tr><td>10</td><td></td><td></td><td></td><td></td></tr></table>										Rev	Date	By	Asgr	Description	1					2					3					4					5					6					7					8					9					10				
Rev	Date	By	Asgr	Description																																																																																																																								
1																																																																																																																												
2																																																																																																																												
3																																																																																																																												
4																																																																																																																												
5																																																																																																																												
6																																																																																																																												
7																																																																																																																												
8																																																																																																																												
9																																																																																																																												
10																																																																																																																												






SURVEY NOTES

- THE TOPOGRAPHY AND EXISTING SITE CONDITIONS DEPICTED HEREON ARE THE RESULT OF AN ON THE GROUND FIELD SURVEY CONDUCTED BY THE HORSLEY WITTEN GROUP, INC. JANUARY 24, JANUARY 31, 2024, NOVEMBER 19, 2024, AND NOVEMBER 20, 2024.
- HORIZONTAL DATUM IS MASS STATE PLANE COORDINATE SYSTEM. DATUM ESTABLISHED BY RTK GPS.
- THE ELEVATIONS DEPICTED HEREON WERE BASED ON THE NORTH AMERICAN VERTICAL DATUM (NAVD) OF 1988 IN UNITS OF FEET.
- THE PROPERTY LINES, RIGHTS OF WAYS, AND TOWN LINE DEPICTED ARE TAKEN FROM MASSGIS (BUREAU OF GEOGRAPHIC INFORMATION), COMMONWEALTH OF MASSACHUSETTS EOTSS AND ARE APPROXIMATE ONLY.
- THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS SHOWN ON THESE PLANS ARE BASED ON RECORDS OF VARIOUS UTILITY COMPANIES, AND WHEREVER POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED UPON AS BEING EXACT OR COMPLETE. THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES SHALL BE VERIFIED IN THE FIELD PRIOR TO THE START OF ANY CONSTRUCTION. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY IN THE TOWNS OF SHIRLEY AND GROTON, AND "DIGSAFE" (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION WORK IN PREVIOUSLY UNALTERED AREAS TO REQUEST EXACT FIELD LOCATION OF UTILITIES.
- UTILITY PROVIDERS: ELECTRIC - MUNICIPAL TELEPHONE - VERIZON CABLE - COMCAST WATER - MUNICIPAL GAS - NATIONAL GRID
- THE PROPERTY IS LOCATED WITHIN FEMA FLOOD ZONE AE EL. 226.9-237 AS SHOWN ON PRELIMINARY PANEL NO. 25017C0182F DATED JUNE 8, 2023.
- REGULATORY FLOODWAY AND APPROXIMATE FLOOD ZONE AE LINES ARE TAKEN FROM MASSGIS (BUREAU OF GEOGRAPHIC INFORMATION), COMMONWEALTH OF MASSACHUSETTS EOTSS AND ARE APPROXIMATE ONLY.
- THE WETLAND DELINEATION SHOWN HEREON WAS CONDUCTED BY THE HORSLEY WITTEN GROUP, INC. ON JANUARY 30, 2024.
- EDGE OF WATER FOR TRANSECTS 1-13 ARE BASED ON SURVEY DATA FROM JANUARY 24, 2024 AND JANUARY 31, 2024. EDGE OF WATER FOR TRANSECTS 14-17 ARE BASED ON SURVEY DATA FROM NOVEMBER 19, 2024 AND NOVEMBER 20, 2024.
- REFERENCE PLANS:  
PLAN TITLED "PROPOSED BRIDGE REPLACEMENT" BY LUCHS ASSOCIATES INC. DATED NOVEMBER 14, 1995.  
PLAN TITLED "EXISTING CONDITIONS PLAN" BY HALEY & ALDRICH DATED FEBRUARY 1, 2013.

LEGEND:

GENERAL		SYMBOLS	
	BERM		CONTROL POINT
	BUILDING		BOLLARD
	CONTOUR - MINOR		ELECTRIC METER
	CONTOUR - MAJOR		CATCHBASIN
	CONCRETE		EXISTING TREE
	EDGE OF PAVEMENT		UTILITY POLE
	FENCE - CHAIN LINK		GUY
	FENCE - METAL		WETLAND FLAG
	GUARD RAIL		SIGN
	STONE		EXISTING SPOT GRADE
	WALL - RETAINING		DRILL HOLE
	OVERHEAD WIRE		
PROPERTY INFORMATION			
	PROPERTY LINE (APPROXIMATE)		
	TOWN BOUNDARY		
ENVIRONMENTAL			
	INLAND BANK - GROTON		
	INLAND BANK - MASSACHUSETTS (EQUIVALENT TO ORDINARY HIGH WATER LINE)		
	25' VEGETATED BUFFER		
	50' NO DISTURB BUFFER ZONE		
	100' BUFFER TO INLAND BANK		
	100' RIVERFRONT AREA		
	200' RIVERFRONT AREA		
	FEMA PRELIMINARY FLOOD ZONE		
	EDGE OF WATER		
	CROSS SECTION/LONGITUDINAL PROFILE LINE		



Revisions

Rev	Date	By	Appr	Description
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

**Horsley Witten Group, Inc.**  
Sustainable Environmental Solutions  
90 Route 6A  
Sandwich, MA 02563  
www.horsleywitten.com  
508-433-6600

**DAM REMOVAL - 60% DESIGN**  
**SQUANNACOOK RIVER DAM**  
**GROTON & SHIRLEY, MASSACHUSETTS**

Prepared For:  
**Town of Groton**  
173 Main Street  
Groton, MA  
Phone: (978) 448-1162

Survey Provided By:  
**Horsley Witten Group, Inc.**  
90 Route 6A  
Sandwich, MA 02563  
Phone: 508-433-6600  
Dated: November 20, 2024

Registration:  
**DRAFT**  
**NOT FOR**  
**CONSTRUCTION**

Project Number:  
**23144**

Sheet:  
**3 of 11**

Sheet Number:  
**EX - 3**











H:\Projects\2023\23144 Squannacook River Dam\Drawings\23144 SQUANACOOK EX.dwg


last modified: 09/12/25 printed: 09/12/25 by j/p

LEGEND	
	RIVER BED
	WATER LEVEL (JANUARY 31, 2024)
	DEPTH TO REFUSAL


NOTE:  
1. ALL TRANSECTS ARE SHOWN FROM THE PERSPECTIVE OF LOOKING DOWNSTREAM.




TRANSECT 1 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'




TRANSECT 2 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'




TRANSECT 3 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'




TRANSECT 4 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'




TRANSECT 5 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'




TRANSECT 6 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'



TRANSECT 7 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'



TRANSECT 8 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'



TRANSECT 9 PROFILE  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 4'

DAM REMOVAL - 60% DESIGN  
SQUANACOOK RIVER DAM  
GROTON & SHIRLEY, MASSACHUSETTS

Prepared For:  
Town of Groton  
173 Main Street  
Groton, MA  
Phone: (978) 448-1162

Survey Provided By:  
Horsley Witten Group, Inc.  
90 Route 6A  
Sandwich, MA 02536  
Phone: 508-433-6600  
Dated: November 20, 2024


Project Number:  
23144

Sheet:  
5 of 11

Sheet Number:  
EX - 5

Revisions

Rev	Date	By	Appr	Description
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				



**Horsley Witten Group, Inc.**  
Sustainable Environmental Solutions  
90 Route 6A  
Sandwich, MA 02536  
www.horsleywitten.com  
508-433-6600

Task: SEPTEMBER 2025

Designed By: JDP






Drawn By: JDP


Checked By: DWM


CROSS SECTIONS (1)

DRAFT  
NOT FOR  
CONSTRUCTION

last modified: 09/12/25    printed: 09/12/25 by jp



Project Number: <div>23144</div>		Sheet : <div>6 of 11</div>		Sheet Number: <div>EX - 6</div>			
<div>DRAFT NOT FOR CONSTRUCTION</div>							
Registration:		Survey Provided By: Horsley Witten Group, Inc. 90 Route 6A Sandwich, MA 02536 Phone: 508-833-6600  Dated: November 20, 2024		Prepared For: Town of Groton 173 Main Street Groton, MA Phone: (878) 448-1162			
Plan Set: <div>DAM REMOVAL - 60% DESIGN SQUANNAHOOK RIVER DAM GROTON &amp; SHIRLEY, MASSACHUSETTS</div>							
Plan Title: <div>CROSS SECTIONS (2)</div>							
<div><div><div>Date: SEPTEMBER 2025</div><div>Designed By: - -</div><div>Drawn By: JDP</div><div>Checked By: DWM</div></div><div><div>Revis.</div><div>Date</div><div>By</div><div>Appr.</div><div>Description</div></div></div>				<div><div><div><div>Horsley Witten Group, Inc.</div><div>Sustainable Environmental Solutions</div><div>90 Route 6A, Sandwich, MA 02563</div><div>www.horsleywitten.com</div><div>508-833-6600</div></div></div></div>		Revisions	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	
				<div>△</div>		<div>△</div>	





Project Number: 23144	Sheet : 7 of 11
Sheet Number:	

**Horsley Witten Group, Inc.**  
Sustainable Environmental Solutions  
90 Route 6A Sandwich, MA 02563  
[www.horsleywitten.com](http://www.horsleywitten.com)  
508-833-6600

Date:	SEPTEMBER 2025	Designed By:	- -	Drawn By:	JDP	Checked By:	DWM
-------	----------------	--------------	-----	-----------	-----	-------------	-----






	<b>Horsley Witten Group, Inc.</b> Sustainable Environmental Solutions 90 Route 6A Sandwich, MA 02563 <a href="http://www.horsleywitten.com">www.horsleywitten.com</a> 508-833-5600	Designed By: JDP	Drawn By: JDP	Checked By: DWN
Date: SEPTEMBER 2025				


[illegible]




last modified: 09/12/25 printed: 09/12/25 by jp H:\Projects\2023\23144 Squannacook River Dam\Drawings\23144 SQUANNA COOK ESC.dwg




**TREE PROTECTION**  
NOT TO SCALE




**SILT SOCK**  
NOT TO SCALE




**INLET PROTECTION**  
NOT TO SCALE



**STABILIZED STONE CONSTRUCTION ENTRANCE**  
NOT TO SCALE



**DAM REMOVAL SECTION**  
HORIZONTAL SCALE: 1" = 20'  
VERTICAL SCALE: 1" = 2'






1. DASHED GRADING SHOWN BELOW INDICATES HYPOTHETICAL RIVER CHANNEL BATHYMETRY POST-DAM REMOVAL. DASHED GRADES DO NOT INDICATE WORK TO BE DONE IN CHANNEL.


[illegible]



last modified: 09/12/25 printed: 09/12/25 by jp H:\Projects\2023\23144 Squannacook River Dam\Drawings\23144 SQUANACOOK RESTORATION.dwg




ISOMETRIC



SECTION

- NOTES:
1. PLANTABLE WALL BY FLEX MSE OR APPROVED EQUIVALENT.
  2. EMBEDMENT DEPTH PER MANUFACTURER GUIDANCE.
  3. THERE WILL BE A MAXIMUM OF THREE 4" PLANTS PER BAG.
  4. HOLES MUST BE ON TOP HALF, BAG SHOULDER, OR SET BACK.
  5. EACH INVERTED "T" CUT WILL BE 3 1/2" X 3 1/2" MAXIMUM.
  6. SPACE PLANTS EVENLY AND OFFSET FOR COMPLETE COVERAGE.



**PLANTABLE WALL**  
NOT TO SCALE



SECTION VIEW

- NOTES:
1. CONSTRUCT ROCK TOE WITH SALVAGED ROCK ACCEPTED FOR RE-USE ONLY BY THE ENGINEER OR WITH ROUNDED TO SUBANGULAR STONE.
  2. D50 OF ALL SALVAGED ROCK TO BE 4" OR LARGER.

**CONSTRUCTED BANK**  
NOT TO SCALE



Revisions

Rev	Date	By	Appr	Description
1				
2				
3				
4				
5				

**Horsley Witten Group, Inc.**  
Sustainable Environmental Solutions  
90 Route 6A, Unit 1  
Sandwich, MA 02563  
Phone: (508) 833-6600  
Fax: (508) 833-3150

Designed By: JIM PCE  
Drawn By: JIM PCE  
Checked By: JIM PCE  
Date: SEPTEMBER 2025

**DAM REMOVAL - 60% DESIGN**  
**SQUANACOOK RIVER DAM**  
**GROTON & SHIRLEY, MASSACHUSETTS**

RESTORATION AND STABILIZATION PLAN

Prepared For:  
**Town of Groton**  
173 Main Street  
Groton, MA  
Phone: (978) 448-1162  
Fax: -

Survey Provided By:  
**Horsley Witten Group, Inc.**  
90 Route 6A  
Sandwich, MA 02563  
Phone: 508-833-6600  
Fax: 508-833-3150  
Dated: November 20, 2024

**DRAFT**  
NOT FOR  
CONSTRUCTION

Project Number: 23144  
Sheet: 11 of 11  
Sheet Number: C-11



## ATTACHMENT D

---

*60% Opinion of Probable Cost*

# Horsley Witten Group

## Sustainable Environmental Solutions

90 Route 6A • Unit 1 • Sandwich, MA 02563  
508-833-6600 • horsleywitten.com



**Project:** Squannacook River Dam Removal  
**Location:** Groton & Shirley, MA

**Submission:** Pre-Permit Level Design  
**Date:** 9/11/2025

**Estimator:** JPM **Checked By:** NP

GENERAL SITEWORK	Unit	Quantity	Unit Cost	Total Cost
<b>SITE PREPARATION &amp; DEMOLITION</b>				
Site Mobilization / Demobilization	LS	1	\$ 80,000.00	\$ 80,000.00
Temp. Entrance Mat For Truck Traffic & Sediment Control	TON	44	\$ 70.00	\$ 3,080.00
Silt Sock Erosion Control	LF	330	\$ 8.00	\$ 2,640.00
Catch Basin Inserts (silt sack)	EA	1	\$ 230.00	\$ 230.00
Tree Protection	LF	50	\$ 16.00	\$ 800.00
Flow Management	LS	1	\$ 35,000.00	\$ 35,000.00
Remove and Replace Fence	LF	30	\$ 75.00	\$ 2,250.00
Remove and Stockpile Vertical Granite Curb	LF	30	\$ 50.00	\$ 1,500.00
Sawcut Vertical Concrete Faces	LF	30	\$ 15.00	\$ 450.00
Concrete Excavation - Concrete Splashpad	CY	170	\$ 1,000.00	\$ 170,000.00
Concrete Excavation - Dam	CY	250	\$ 1,000.00	\$ 250,000.00
<b>Subtotal Site Preparation &amp; Demolition</b>			<b>\$ 545,950.00</b>	
<b>GRADING</b>				
Excavate and Relocate Material	CY	650	\$ 140.00	\$ 91,000.00
<b>Subtotal Grading</b>			<b>\$ 91,000.00</b>	
<b>RESTORATION AND STABILIZATION</b>				
Filter Fabric for Constructed Banks	SY	320	\$ 10.00	\$ 3,200.00
Flex MSE	LS	1	\$ 53,600.00	\$ 53,600.00
Loam	CY	8	\$ 100.00	\$ 800.00
Landscaping	LS	1	\$ 40,000.00	\$ 40,000.00
<b>Subtotal Restoration and Stabilization</b>			<b>\$ 97,600.00</b>	
<b>TOTAL GENERAL SITEWORK</b>			<b>\$ 734,600.00</b>	

<b>TOTAL ESTIMATED CONSTRUCTION COST</b>		<b>\$ 734,600.00</b>
General Conditions	10%	\$ 73,500.00
<b>ESTIMATED CONSTRUCTION COSTS (Including General Conditions)</b>		<b>\$ 808,100.00</b>
Construction Overhead and Profit	15%	\$ 121,300.00
Contingency	20%	\$ 161,700.00
<b>TOTAL ESTIMATED CONSTRUCTION COSTS</b>		<b>\$ 1,091,100.00</b>
<b>ALLOWANCES</b>		
Additional Dewatering and Access		\$ 75,000.00
<b>TOTAL ESTIMATED CONSTRUCTION COSTS INCLUDING ALLOWANCES</b>		<b>\$ 1,166,100.00</b>
<b>RANGE (-15% TO +20%)</b>		
Low	-10%	\$ 1,049,500.00
High	15%	\$ 1,341,100.00

### Qualifications:

The following items are not included in the scope of work:

Police / Traffic details  
Sheeting / Earth Support

Quantities provided are based on conceptual plans "Dam Removal - 60% Design, Squannacook River Dam, Groton & Shirley, MA" September 2025, prepared by Horsley Witten Group.

Unit prices provided are based upon typical 2025 construction costs and data. Unit prices are subject to change due to adjustments to material and labor costs, site conditions and inflation.



# ATTACHMENT E

---

*Proposed Site Renderings*



# SQUANNACOOK RIVER DAM REMOVAL

SEPTEMBER 2025

## LEGEND

- TOWN BOUNDARY
- - - - - EXISTING 1 FT CONTOUR
- PREDICTED 1 FT CONTOUR
- . - . - EXISTING TOP OF BANK
- . - . - PREDICTED TOP OF BANK - 50% FLOW
- EXISTING DAM STRUCTURE TO BE REMOVED
- - - - - EXISTING RETAINING WALLS TO REMAIN
- RIVER FLOW DIRECTION - 50% FLOW
- RIPRAP BANK STABILIZATION
- EXISTING BEDROCK (APPROXIMATE)
- REVEGETATED AREA

NOTE: RIVER SHOWN AT 50% FLOW EXCEEDANCE -  
MEDIAN FLOW CONDITION

